BRUHAT BANGALORE MAHANAGARA PALIKE

NAME OF WORK:- Improvements to Roads and Drains at Mariyannapalya, Munikempanna Layout, Bhuvaneshwarinagra, Dasarahalli Balance Roads and Surrounding Area in Ward No.06 Byatarayanapura Sub Division

MODIFIED ESTIMATE-2

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
Item no.01		Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications and as per the directions of the Engineer-in-charge of the work										
		Kaveri Layout										
		Krishna Nivas House (W1309)										
		LHS										
		South to North										
0.00	2.50		Cum	1	2.50			0.90	0.90	2.03		
2.50	15.00			1	12.50			0.90	0.90	10.13		
15.00	18.40			1	3.40			0.90	0.90	2.75		
18.40	24.40			1	6.00			0.90	0.90	4.86		
24.40	35.00			1	10.60			0.90	0.90	8.59		
35.00	50.00			1	15.00			0.90	0.90	12.15		
50.00	64.10			1	14.10			0.90	0.90	11.42		
64.10	75.00			1	10.90			0.90	0.90	8.83		
75.00	87.80			1	12.80			0.90	0.90	10.37		
87.80	91.20			1	3.40			0.90	0.90	2.75		
		RHS										
		North to South										
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	19.40			1	4.40			0.90	0.90	3.56		
19.40	28.20			1	8.80			0.90	0.90	7.13		
28.20	33.50			1	5.30			0.90	0.90	4.29		
33.50	42.50			1	9.00			0.90	0.90	7.29		
42.50	54.90			1	12.40			0.90	0.90	10.04		
54.90	65.70			1	10.80			0.90	0.90	8.75		
65.70	74.10			1	8.40			0.90	0.90	6.80		
74.10	85.00			1	10.90			0.90	0.90	8.83		
85.00	92.60			1	7.60			0.90	0.90	6.16		
		Joseph House Road (W0884)										
		RHS										
		West to East										
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	30.00			1	15.00			0.90	0.90	12.15		
30.00	36.40			1	6.40			0.90	0.90	5.18		
36.40	48.10			1	11.70			0.90	0.90	9.48		
		LHS										
		West to East										
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	27.20			1	12.20			0.90	0.90	9.88		
		1st Main Road (W1307)										
		LHS										
		North to South										
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	21.30			1	6.30			0.90	0.90	5.10		
		Moto Works Oppo. (W1299)										
		RHS										
		North to South										
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	17.60			1	2.60			0.90	0.90	2.11		
17.60	23.40	Culvert		1	0.00			0.90	0.90	0.00		
23.40	30.00			1	6.60			0.90	0.90	5.35		
30.00	45.00			1	15.00			0.90	0.90	12.15		
45.00	55.20			1	10.20			0.90	0.90	8.26		
55.20	60.30	Culvert		1	0.00			0.90	0.90	0.00		
60.30	75.00			1	14.70			0.90	0.90	11.91		
75.00	86.30			1	11.30			0.90	0.90	9.15		
86.30	91.50	Culvert		1	0.00			0.90	0.90	0.00		
91.50	105.00			1	13.50			0.90	0.90	10.94		
105.00	120.00			1	15.00			0.90	0.90	12.15		
120.00	129.60			1	9.60			0.90	0.90	7.78		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
om	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		LHS										
		South to North										
	15.00			1	15.00			0.90	0.90	12.15		
	19.20			1	4.20			0.90	0.90	3.40		
0	25.50			1	6.30			0.90	0.90	5.10		
.50	30.00			1	4.50			0.90	0.90	3.65		
30.00	45.00			1	15.00			0.90	0.90	12.15		
45.00	60.00			1	15.00			0.90	0.90	12.15		
60.00	75.00			1	15.00			0.90	0.90	12.15		
75.00	90.00			1	15.00			0.90	0.90	12.15		
90.00	105.00			1	15.00			0.90	0.90	12.15		
105.00	120.00			1	15.00			0.90	0.90	12.15		
120.00	125.70			1	5.70			0.90	0.90	4.62		
		Cross Road 1 (W0870)										
		East to West										
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	26.10			1	11.10			0.90	0.90	8.99		
		Cross Road 2 (W0862)										
		East to West										
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	30.00			1	15.00			0.90	0.90	12.15		
30.00	33.00			1	3.00			0.90	0.90	2.43		
		Cross Road 3										
		East to West										
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	30.00			1	15.00			0.90	0.90	12.15		
30.00	37.40			1	7.40			0.90	0.90	5.99		
		Cross Road (W1297)										
		LHS										
		South to North										
0.00	15.00			1	15.00			1.10	0.90	14.85		
15.00	30.00			1	15.00			1.10	0.90	14.85		
30.00	45.00			1	15.00			1.10	0.90	14.85		
45.00	60.00			1	15.00			1.10	0.90	14.85		
60.00	75.00			1	15.00			1.10	0.90	14.85		
75.00	90.00			1	15.00			1.10	0.90	14.85		
90.00	105.00			1	15.00			1.10	0.90	14.85		
105.00	106.60			1	1.60			1.10	0.90	1.58		
		RHS										
		North to South										
0.00	15.00			1	15.00			1.10	0.90	14.85		
15.00	30.00			1	15.00			1.10	0.90	14.85		
30.00	45.00			1	15.00			1.10	0.90	14.85		
45.00	60.00			1	15.00			1.10	0.90	14.85		
60.00	75.00			1	15.00			1.10	0.90	14.85		
75.00	90.00			1	15.00			1.10	0.90	14.85		
90.00	105.00			1	15.00			1.10	0.90	14.85		
105.00	107.20			1	2.20			1.10	0.90	2.18		
		Kuvempu Layout										
		2nd Main, 2nd Cross (W0616)										
		RHS										
		North to South										
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	30.00			1	15.00			0.90	0.90	12.15		
		LHS										
		South to North										
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	29.80			1	14.80			0.90	0.90	11.99		
		1st Main, 3rd Cross (W0989)										
		RHS										
		North to South										
0.00	15.00			1	15.00			0.90	0.90	12.15		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		₹/-	₹/-
15.00	30.00			1	15.00			0.90	0.90	12.15		
30.00	45.00			1	15.00			0.90	0.90	12.15		
45.00	60.00			1	15.00			0.90	0.90	12.15		
60.00	61.80			1	1.80			0.90	0.90	1.46		
		LHS										
		South to North										
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	30.00			1	15.00			0.90	0.90	12.15		
30.00	45.00			1	15.00			0.90	0.90	12.15		
45.00	60.00			1	15.00			0.90	0.90	12.15		
60.00	66.90			1	6.90			0.90	0.90	5.59		
		Dead END										
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	16.80			1	1.80			0.90	0.90	1.46		
		1st Main, 2nd Cross (W0983)										
		RHS										
		North to South										
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	30.00			1	15.00			0.90	0.90	12.15		
30.00	45.00			1	15.00			0.90	0.90	12.15		
45.00	60.00			1	15.00			0.90	0.90	12.15		
60.00	63.10			1	3.10			0.90	0.90	2.51		
		LHS										
		South to North										
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	30.00			1	15.00			0.90	0.90	12.15		
30.00	45.00			1	15.00			0.90	0.90	12.15		
45.00	60.00			1	15.00			0.90	0.90	12.15		
60.00	66.30			1	6.30			0.90	0.90	5.10		
		Dead END										
0.00	5.00			1	5.00			0.90	0.90	4.05		
		1st Main, 1st Cross (W0973)										
		RHS										
		North to South										
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	30.00			1	15.00			0.90	0.90	12.15		
30.00	45.00			1	15.00			0.90	0.90	12.15		
45.00	45.80			1	0.80			0.90	0.90	0.65		
45.80	59.20			1	13.40			0.90	0.90	10.85		
		LHS										
		South to North										
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	27.00			1	12.00			0.90	0.90	9.72		
27.00	41.80			1	14.80			0.90	0.90	11.99		
41.80	55.00			1	13.20			0.90	0.90	10.69		
55.00	60.20			1	5.20			0.90	0.90	4.21		
		Dead END										
0.00	7.30			1	7.30			0.90	0.90	5.91		
		1st Main Road (W0612)										
		LHS										
		East To West										
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	30.00			1	15.00			0.90	0.90	12.15		
30.00	36.60			1	6.60			0.90	0.90	5.35		
0.00	15.00			1	15.00			1.10	0.90	14.85		
15.00	30.00			1	15.00			1.10	0.90	14.85		
30.00	45.00			1	15.00			1.10	0.90	14.85		
45.00	53.30			1	8.30			1.10	0.90	8.22		
53.30	61.10	Road Break		1	0.00			1.10	0.90	0.00		
61.10	70.70			1	9.60			1.10	0.90	9.50		
70.70	85.00			1	14.30			1.10	0.90	14.16		
85.00	100.00			1	15.00			1.10	0.90	14.85		
100.00	115.00			1	15.00			1.10	0.90	14.85		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
15.00	125.80			1	10.80			1.10	0.90	10.69		
		RHS										
		West To East										
0.00	15.00			1	15.00			1.10	0.90	14.85		
15.00	30.00			1	15.00			1.10	0.90	14.85		
30.00	45.00			1	15.00			1.10	0.90	14.85		
45.00	48.80			1	3.80			1.10	0.90	3.76		
48.80	63.80			1	15.00			1.10	0.90	14.85		
0.00	15.00			1	15.00			1.10	0.90	14.85		
15.00	30.00			1	15.00			1.10	0.90	14.85		
30.00	45.00			1	15.00			1.10	0.90	14.85		
45.00	60.00			1	15.00			1.10	0.90	14.85		
60.00	74.20			1	14.20			1.10	0.90	14.06		
		21st Cross Road (W0969)										
		RHS										
		North to South										
0.00	15.00			1	15.00			1.10	0.90	14.85		
15.00	20.20			1	5.20			1.10	0.90	5.15		
20.20	33.00	No Work		1	0.00			1.10	0.90	0.00		
33.00	45.00			1	12.00			1.10	0.90	11.88		
45.00	60.00			1	15.00			1.10	0.90	14.85		
60.00	68.40			1	8.40			1.10	0.90	8.32		
68.40	74.60			1	6.20			1.10	0.90	6.14		
74.60	85.00			1	10.40			1.10	0.90	10.30		
85.00	100.00			1	15.00			1.10	0.90	14.85		
100.00	115.00			1	15.00			1.10	0.90	14.85		
115.00	128.50			1	13.50			1.10	0.90	13.37		
		LHS										
		South to North										
0.00	15.00			1	15.00			1.10	0.90	14.85		
15.00	17.60			1	2.60			1.10	0.90	2.57		
17.60	21.80			1	4.20			1.10	0.90	4.16		
21.80	26.50			1	4.70			1.10	0.90	4.65		
26.50	36.40			1	9.90			1.10	0.90	9.80		
36.40	46.80			1	10.40			1.10	0.90	10.30		
46.80	57.20			1	10.40			1.10	0.90	10.30		
57.20	70.00			1	12.80			1.10	0.90	12.67		
70.00	78.40			1	8.40			1.10	0.90	8.32		
78.40	82.50	No Work		1	0.00			1.10	0.90	0.00		
82.50	91.00			1	8.50			1.10	0.90	8.42		
91.00	95.30			1	4.30			1.10	0.90	4.26		
95.30	104.20			1	8.90			1.10	0.90	8.81		
104.20	113.40			1	9.20			1.10	0.90	9.11		
113.40	128.20			1	14.80			1.10	0.90	14.65		
		Connecting Road 1 (W0608)										
		RHS										
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	23.80			1	8.80			0.90	0.90	7.13		
		LHS										
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	25.40			1	10.40			0.90	0.90	8.42		
		Dead END (W0965)										
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	17.70			1	2.70			0.90	0.90	2.19		
		Connecting Road 2										
		RHS										
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	21.60			1	6.60			0.90	0.90	5.35		
		LHS										

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	23.90			1	8.90			0.90	0.90	7.21		
		1st Main, 1st A Cross (W0975)										
0.00	15.00			1	15.00			1.10	0.90	14.85		
15.00	20.50			1	5.50			1.10	0.90	5.45		
20.50	30.30			1	9.80			1.10	0.90	9.70		
		2nd Main Road (W0616)										
		RHS										
		North to South										
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	30.00			1	15.00			0.90	0.90	12.15		
30.00	45.00			1	15.00			0.90	0.90	12.15		
45.00	60.00			1	15.00			0.90	0.90	12.15		
60.00	74.40			1	14.40			0.90	0.90	11.66		
0.00	10.70			1	10.70			1.10	0.90	10.59		
10.70	25.00			1	14.30			1.10	0.90	14.16		
25.00	32.50			1	7.50			1.10	0.90	7.43		
32.50	45.00			1	12.50			1.10	0.90	12.38		
45.00	60.00			1	15.00			1.10	0.90	14.85		
60.00	75.00			1	15.00			1.10	0.90	14.85		
75.00	90.00			1	15.00			1.10	0.90	14.85		
90.00	105.00			1	15.00			1.10	0.90	14.85		
105.00	120.00			1	15.00			1.10	0.90	14.85		
120.00	121.20			1	1.20			1.10	0.90	1.19		
		LHS										
		South to North										
0.00	14.20			1	14.20			0.90	0.90	11.50		
		2nd A Main Road (W0616)										
		RHS										
0.00	15.00			1	15.00			1.00	0.90	13.50		
15.00	26.50			1	11.50			1.00	0.90	10.35		
26.50	35.70			1	9.20			1.00	0.90	8.28		
35.70	46.40			1	10.70			1.00	0.90	9.63		
46.40	58.00			1	11.60			1.00	0.90	10.44		
58.00	70.60			1	12.60			1.00	0.90	11.34		
70.60	83.30			1	12.70			1.00	0.90	11.43		
		18th A Cross Road (W0618)										
		LHS										
		South to North										
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	27.20			1	12.20			0.90	0.90	9.88		
27.20	36.90			1	9.70			0.90	0.90	7.86		
36.90	44.40			1	7.50			0.90	0.90	6.08		
44.40	50.00			1	5.60			0.90	0.90	4.54		
50.00	65.00			1	15.00			0.90	0.90	12.15		
65.00	75.00			1	10.00			0.90	0.90	8.10		
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	25.10			1	10.10			0.90	0.90	8.18		
		Munikempanna Layout										
		1st Cross Road (W0973)										
		RHS										
		North to South										
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	30.00			1	15.00			0.90	0.90	12.15		
30.00	45.00			1	15.00			0.90	0.90	12.15		
45.00	60.00			1	15.00			0.90	0.90	12.15		
60.00	75.00			1	15.00			0.90	0.90	12.15		
75.00	85.60			1	10.60			0.90	0.90	8.59		
		Dead END (W0965)										
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	30.00			1	15.00			0.90	0.90	12.15		
30.00	35.70			1	5.70			0.90	0.90	4.62		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Dasarahalli Main Road (M0022)										
		RHS										
0.00	15.00			1	15.00			0.90	0.90	12.15		
15.00	30.00			1	15.00			0.90	0.90	12.15		
30.00	45.00			1	15.00			0.90	0.90	12.15		
45.00	59.10			1	14.10			0.90	0.90	11.42		
		2nd Cross (W0983) Dead End										
0.00	12.90			1	12.90			0.90	0.90	10.45		
		Bhuvaneshwari Nagar										
		20th R Cross Road (W0961)										
		RHS										
0	15		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
15	30		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
30	45		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
45	47.5		Cum	1	2.50	0.95	0.95	0.95	0.90	2.14		
47.5	53	Culvert	Cum	1	0.00	0.95	0.95	0.95	0.90	0.00		
53	65		Cum	1	12.00	0.95	0.95	0.95	0.90	10.26		
65	80		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
80	95		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
95	99.7		Cum	1	4.70	0.95	0.95	0.95	0.90	4.02		
99.7	112		Cum	1	12.30	0.95	0.95	0.95	0.90	10.52		
112	125		Cum	1	13.00	0.95	0.95	0.95	0.90	11.12		
125	140		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
140	155		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
155	159.9		Cum	1	4.90	0.95	0.95	0.95	0.90	4.19		
		LHS										
0	15		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
15	30		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
30	40.5		Cum	1	10.50	0.95	0.95	0.95	0.90	8.98		
40.5	55		Cum	1	14.50	0.95	0.95	0.95	0.90	12.40		
55	65.5		Cum	1	10.50	0.95	0.95	0.95	0.90	8.98		
65.5	70.7	Culvert	Cum	1	0.00	0.95	0.95	0.95	0.90	0.00		
70.7	85		Cum	1	14.30	0.95	0.95	0.95	0.90	12.23		
85	100		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
100	111.8		Cum	1	11.80	0.95	0.95	0.95	0.90	10.09		
111.8	116.9	No Work	Cum	1	0.00	0.95	0.95	0.95	0.90	0.00		
116.9	130		Cum	1	13.10	0.95	0.95	0.95	0.90	11.20		
130	144.5		Cum	1	14.50	0.95	0.95	0.95	0.90	12.40		
144.5	148.7	No Work.	Cum	1	0.00	0.95	0.95	0.95	0.90	0.00		
148.7	164.3		Cum	1	15.60	0.95	0.95	0.95	0.90	13.34		
		Dasarahalli Circle										
		West to East										
0.00	15.00		Cum	1	15.00	1.00	1.00	1.00	1.50	22.50		
15.00	27.70		Cum	1	12.70	1.00	1.00	1.00	1.50	19.05		
27.70	42.70		Cum	1	15.00	1.30	1.30	1.30	1.50	29.25		
42.70	57.70		Cum	1	15.00	1.30	1.30	1.30	1.50	29.25		
57.70	72.70		Cum	1	15.00	1.30	1.30	1.30	1.50	29.25		
72.70	87.70		Cum	1	15.00	1.30	1.30	1.30	1.50	29.25		
87.70	102.70		Cum	1	15.00	1.30	1.30	1.30	1.50	29.25		
102.70	117.70		Cum	1	15.00	1.30	1.30	1.30	1.50	29.25		
117.70	132.70		Cum	1	15.00	1.30	1.30	1.30	1.50	29.25		
132.70	147.70		Cum	1	15.00	1.30	1.30	1.30	1.50	29.25		
147.70	155.00		Cum	1	7.30	1.30	1.30	1.30	1.50	14.24		
		For Culvert										
		Kuvempu Layout										
		2nd Main Road (W0616) CD1	Cum	1	5.75			1.40	0.85	6.84		
				1	8.20			1.40	0.85	9.76		
				1	6.20			1.40	0.85	7.38		
				1	10.40			1.40	0.85	12.38		
		Dead End Road (W0965) CD5		1	8.10			1.40	0.85	9.64		
		21st Cross Road (W0969) CD6		1	7.40			1.40	0.85	8.81		
		Dasarahalli Main Road (M0022) CD7		1	7.00			1.40	0.85	8.33		
		1st Main Road (W0612) CD8		1	7.70			1.40	0.85	9.16		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
				1	4.70			1.40	0.85	5.59		
				1	9.50			1.40	0.85	11.31		
		20th R Cross Road (W0961) CD11		1	7.00			1.40	0.85	8.33		
		18th A Cross Road (W0618) CD12		1	6.30			1.40	0.85	7.50		
		1st Main Road (W0612) CD13		1	5.50			1.40	0.85	6.55		
		Mariyanna Palya										
		Joseph House Road (W0884) CD14		1	5.60			1.70	0.85	8.09		
		Moto Works Oppo. (W1299) CD15		1	6.10			1.70	0.85	8.81		
				1	5.80			1.70	0.85	8.38		
				1	5.10			1.70	0.85	7.37		
				1	5.20			1.70	0.85	7.51		
		Cross Road	Cum	1	5.80	1.70	1.70	1.70	0.95	9.37		
		Desilt										
		Mariyanna Palya										
		St. Anthony Church Road (10794)										
0.00	15.00		Cum	1	15.00			0.75	0.75	8.44		
15.00	30.00			1	15.00			0.75	0.75	8.44		
30.00	37.50	Culvert		0	0.00			0.75	0.75	0.00		
37.50	50.00			1	12.50			0.75	0.75	7.03		
50.06	65.00			1	15.00			0.75	0.75	8.44		
65.00	80.00			1	15.00			0.75	0.75	8.44		
80.00	94.80			1	14.80			0.75	0.75	8.33		
94.80	103.80	Culvert		0	0.00			0.00	0.75	0.00		
103.80	115.00			1	11.20			0.75	0.75	6.30		
115.00	128.10			1	13.10			0.75	0.75	7.37		
128.10	135.00	Culvert		0	0.00			0.75	0.75	0.00		
135.00	147.30			1	12.30			0.75	0.75	6.92		
147.30	152.50			1	5.20			0.75	0.75	2.92		
152.50	162.00			1	9.50			0.75	0.75	5.34		
162.00	177.00			1	15.00			0.75	0.75	8.44		
177.00	191.50			1	14.50			0.75	0.75	8.16		
191.50	200.00			1	8.50			0.75	0.75	4.78		
200.00	215.00			1	15.00			0.75	0.75	8.44		
215.00	228.00			1	13.00			0.75	0.75	7.31		
228.00	240.00			1	12.00			0.75	0.75	6.75		
240.00	244.50			1	4.50			0.75	0.75	2.53		
									Total Executed Quantity	**3069.74**		
									Tender Quantity	**2854.05**		
									Quantity upto 125%	**3069.74**	**215.00**	**659994.00**
Item no.02		Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications and directions of the Engineer in charge.										
		Mariyanna Palya										
		St. Anthony Church Road (10794)										
3.00	10.00		Cum	2	7.00			0.50	0.90	6.30		
16.00	28.00			1	12.00			0.50	0.90	5.40		
30.00	37.50	Culvert		0	0.00			0.50	0.90	0.00		
42.00	46.30			2	4.30			0.50	0.90	3.87		
55.00	61.00			2	6.00			0.50	0.90	5.40		
70.00	75.00			2	5.00			0.50	0.90	4.50		
94.80	103.80	Culvert		0	0.00			0.50	0.90	0.00		
105.00	113.00			2	8.00			0.50	0.90	7.20		
120.00	128.10			2	8.10			0.50	0.90	7.29		
128.10	135.00	Culvert		0	0.00			0.50	0.90	0.00		
141.00	145.00			2	4.00			0.50	0.90	3.60		
147.30	152.50			2	5.20			0.50	0.90	4.68		
155.00	162.00			2	7.00			0.50	0.90	6.30		
169.00	177.00			2	8.00			0.50	0.90	7.20		
182.00	189.00			2	7.00			0.50	0.90	6.30		
									Total Executed Quantity	**68.04**	**5500.00**	**374220.00**
									Tender Quantity	**68.04**		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
Item no.03		Providing and Filling in foundation with granite / trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift.complete as per specifications and directions of the Engineer in charge										
		Dasarahalli Circle										
		West to East										
0.00	15.00		Cum	1	15.00	1.00	1.00	1.00	0.25	3.75		
15.00	27.70		Cum	1	12.70	1.00	1.00	1.00	0.25	3.18		
27.70	42.70		Cum	1	15.00	1.30	1.30	1.30	0.25	4.88		
42.70	57.70		Cum	1	15.00	1.30	1.30	1.30	0.25	4.88		
57.70	72.70		Cum	1	15.00	1.30	1.30	1.30	0.25	4.88		
72.70	87.70		Cum	1	15.00	1.30	1.30	1.30	0.25	4.88		
87.70	102.70		Cum	1	15.00	1.30	1.30	1.30	0.25	4.88		
102.70	117.70		Cum	1	15.00	1.30	1.30	1.30	0.25	4.88		
117.70	132.70		Cum	1	15.00	1.30	1.30	1.30	0.25	4.88		
132.70	147.70		Cum	1	15.00	1.30	1.30	1.30	0.25	4.88		
147.70	155.00		Cum	1	7.30	1.30	1.30	1.30	0.25	2.37		
									Total Executed Quantity	48.30	2700.00	130404.00
									Tender Quantity	53.66		
Item no.04		Providing and laying Plain cement concrete of mix1:3:6 with OPC cement @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days Including cost of materials,labour, HOM curing form work, Scaffolding and Centering complete as per specifications and as per the directions of the Engineer-in-charge of the work										
		Drain PCC										
		Kaveri Layout										
		Krishna Nivas House (W1309)										
		LHS										
		South to North										
0.00	2.50		Cum	1	2.50			0.90	0.15	0.34		
2.50	15.00			1	12.50			0.90	0.15	1.69		
15.00	18.40			1	3.40			0.90	0.15	0.46		
18.40	24.40			1	6.00			0.90	0.15	0.81		
24.40	35.00			1	10.60			0.90	0.15	1.43		
35.00	50.00			1	15.00			0.90	0.15	2.03		
50.00	64.10			1	14.10			0.90	0.15	1.90		
64.10	75.00			1	10.90			0.90	0.15	1.47		
75.00	87.80			1	12.80			0.90	0.15	1.73		
87.80	91.20			1	3.40			0.90	0.15	0.46		
		RHS										
		North to South										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	19.40			1	4.40			0.90	0.15	0.59		
19.40	28.20			1	8.80			0.90	0.15	1.19		
28.20	33.50			1	5.30			0.90	0.15	0.72		
33.50	42.50			1	9.00			0.90	0.15	1.22		
42.50	54.90			1	12.40			0.90	0.15	1.67		
54.90	65.70			1	10.80			0.90	0.15	1.46		
65.70	74.10			1	8.40			0.90	0.15	1.13		
74.10	85.00			1	10.90			0.90	0.15	1.47		
85.00	92.60			1	7.60			0.90	0.15	1.03		
		Joseph House Road (W0884)										
		RHS										
		West to East										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	15.00			0.90	0.15	2.03		
30.00	36.40			1	6.40			0.90	0.15	0.86		
36.40	48.10			1	11.70			0.90	0.15	1.58		
		LHS										
		West to East										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	27.20			1	12.20			0.90	0.15	1.65		
		1st Main Road (W1307)										
		LHS										
		North to South										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	21.30			1	6.30			0.90	0.15	0.85		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Moto Works Oppo. (W1299)										
		RHS										
		North to South										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	17.60			1	2.60			0.90	0.15	0.35		
17.60	23.40	**Culvert**		1	0.00			0.90	0.15	0.00		
23.40	30.00			1	6.60			0.90	0.15	0.89		
30.00	45.00			1	15.00			0.90	0.15	2.03		
45.00	55.20			1	10.20			0.90	0.15	1.38		
55.20	60.30	**Culvert**		1	0.00			0.90	0.15	0.00		
60.30	75.00			1	14.70			0.90	0.15	1.98		
75.00	86.30			1	11.30			0.90	0.15	1.53		
86.30	91.50	**Culvert**		1	0.00			0.90	0.15	0.00		
91.50	105.00			1	13.50			0.90	0.15	1.82		
105.00	120.00			1	15.00			0.90	0.15	2.03		
120.00	129.60			1	9.60			0.90	0.15	1.30		
		LHS										
		South to North										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	19.20			1	4.20			0.90	0.15	0.57		
19.20	25.50			1	6.30			0.90	0.15	0.85		
25.50	30.00			1	4.50			0.90	0.15	0.61		
30.00	45.00			1	15.00			0.90	0.15	2.03		
45.00	60.00			1	15.00			0.90	0.15	2.03		
60.00	75.00			1	15.00			0.90	0.15	2.03		
75.00	90.00			1	15.00			0.90	0.15	2.03		
90.00	105.00			1	15.00			0.90	0.15	2.03		
105.00	120.00			1	15.00			0.90	0.15	2.03		
120.00	125.70			1	5.70			0.90	0.15	0.77		
		Cross Road 1 (W0870)										
		East to West										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	26.10			1	11.10			0.90	0.15	1.50		
		Cross Road 2 (W0862)										
		East to West										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	15.00			0.90	0.15	2.03		
30.00	33.00			1	3.00			0.90	0.15	0.41		
		Cross Road 3										
		East to West										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	15.00			0.90	0.15	2.03		
30.00	37.40			1	7.40			0.90	0.15	1.00		
		Cross Road (W1297)										
		LHS										
		South to North										
0.00	15.00			1	15.00			1.10	0.15	2.48		
15.00	30.00			1	15.00			1.10	0.15	2.48		
30.00	45.00			1	15.00			1.10	0.15	2.48		
45.00	60.00			1	15.00			1.10	0.15	2.48		
60.00	75.00			1	15.00			1.10	0.15	2.48		
75.00	90.00			1	15.00			1.10	0.15	2.48		
90.00	105.00			1	15.00			1.10	0.15	2.48		
105.00	106.60			1	1.60			1.10	0.15	0.26		
		RHS										
		North to South										
0.00	15.00			1	15.00			1.10	0.15	2.48		
15.00	30.00			1	15.00			1.10	0.15	2.48		
30.00	45.00			1	15.00			1.10	0.15	2.48		
45.00	60.00			1	15.00			1.10	0.15	2.48		
60.00	75.00			1	15.00			1.10	0.15	2.48		
75.00	90.00			1	15.00			1.10	0.15	2.48		
90.00	105.00			1	15.00			1.10	0.15	2.48		
105.00	107.20			1	2.20			1.10	0.15	0.36		
		Kuvempu Layout										

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		2nd Main, 2nd Cross (W0618)										
		RHS										
		North to South										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	15.00			0.90	0.15	2.03		
		LHS										
		South to North										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	29.80			1	14.80			0.90	0.15	2.00		
		1st Main, 3rd Cross (W0989)										
		RHS										
		North to South										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	15.00			0.90	0.15	2.03		
30.00	45.00			1	15.00			0.90	0.15	2.03		
45.00	60.00			1	15.00			0.90	0.15	2.03		
60.00	61.80			1	1.80			0.90	0.15	0.24		
		LHS										
		South to North										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	15.00			0.90	0.15	2.03		
30.00	45.00			1	15.00			0.90	0.15	2.03		
45.00	60.00			1	15.00			0.90	0.15	2.03		
60.00	66.90			1	6.90			0.90	0.15	0.93		
		Dead END										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	16.80			1	1.80			0.90	0.15	0.24		
		1st Main, 2nd Cross (W0983)										
		RHS										
		North to South										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	15.00			0.90	0.15	2.03		
30.00	45.00			1	15.00			0.90	0.15	2.03		
45.00	60.00			1	15.00			0.90	0.15	2.03		
60.00	63.10			1	3.10			0.90	0.15	0.42		
		LHS										
		South to North										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	15.00			0.90	0.15	2.03		
30.00	45.00			1	15.00			0.90	0.15	2.03		
45.00	60.00			1	15.00			0.90	0.15	2.03		
60.00	66.30			1	6.30			0.90	0.15	0.85		
		Dead END										
0.00	5.00			1	5.00			0.90	0.15	0.68		
		1st Main, 1st Cross (W0973)										
		RHS										
		North to South										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	15.00			0.90	0.15	2.03		
30.00	45.00			1	15.00			0.90	0.15	2.03		
45.00	45.80			1	0.80			0.90	0.15	0.11		
45.80	59.20			1	13.40			0.90	0.15	1.81		
		LHS										
		South to North										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	27.00			1	12.00			0.90	0.15	1.62		
27.00	41.80			1	14.80			0.90	0.15	2.00		
41.80	55.00			1	13.20			0.90	0.15	1.78		
55.00	60.20			1	5.20			0.90	0.15	0.70		
		Dead END										
0.00	7.30			1	7.30			0.90	0.15	0.99		
		1st Main Road (W0612)										

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		LHS										
		East To West										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	15.00			0.90	0.15	2.03		
30.00	36.60			1	6.60			0.90	0.15	0.89		
0.00	15.00			1	15.00			1.10	0.15	2.48		
15.00	30.00			1	15.00			1.10	0.15	2.48		
30.00	45.00			1	15.00			1.10	0.15	2.48		
45.00	53.30			1	8.30			1.10	0.15	1.37		
53.30	61.10	Road Break		1	0.00			1.10	0.15	0.00		
61.10	70.70			1	9.60			1.10	0.15	1.58		
70.70	85.00			1	14.30			1.10	0.15	2.36		
85.00	100.00			1	15.00			1.10	0.15	2.48		
100.00	115.00			1	15.00			1.10	0.15	2.48		
115.00	125.80			1	10.80			1.10	0.15	1.78		
		RHS										
		West To East										
0.00	15.00			1	15.00			1.10	0.15	2.48		
15.00	30.00			1	15.00			1.10	0.15	2.48		
30.00	45.00			1	15.00			1.10	0.15	2.48		
45.00	48.80			1	3.80			1.10	0.15	0.63		
48.80	63.80			1	15.00			1.10	0.15	2.48		
0.00	15.00			1	15.00			1.10	0.15	2.48		
15.00	30.00			1	15.00			1.10	0.15	2.48		
30.00	45.00			1	15.00			1.10	0.15	2.48		
45.00	60.00			1	15.00			1.10	0.15	2.48		
60.00	74.20			1	14.20			1.10	0.15	2.34		
		21st Cross Road (W0969)										
		RHS										
		North to South										
0.00	15.00			1	15.00			1.10	0.15	2.48		
15.00	20.20			1	5.20			1.10	0.15	0.86		
20.20	33.00	No Work		1	0.00			1.10	0.15	0.00		
33.00	45.00			1	12.00			1.10	0.15	1.98		
45.00	60.00			1	15.00			1.10	0.15	2.48		
60.00	68.40			1	8.40			1.10	0.15	1.39		
68.40	74.60			1	6.20			1.10	0.15	1.02		
74.60	85.00			1	10.40			1.10	0.15	1.72		
85.00	100.00			1	15.00			1.10	0.15	2.48		
100.00	115.00			1	15.00			1.10	0.15	2.48		
115.00	128.50			1	13.50			1.10	0.15	2.23		
		LHS										
		South to North										
0.00	15.00			1	15.00			1.10	0.15	2.48		
15.00	17.60			1	2.60			1.10	0.15	0.43		
17.60	21.80			1	4.20			1.10	0.15	0.69		
21.80	26.50			1	4.70			1.10	0.15	0.78		
26.50	36.40			1	9.90			1.10	0.15	1.63		
36.40	46.80			1	10.40			1.10	0.15	1.72		
46.80	57.20			1	10.40			1.10	0.15	1.72		
57.20	70.00			1	12.80			1.10	0.15	2.11		
70.00	78.40			1	8.40			1.10	0.15	1.39		
78.40	82.50	No Work		1	0.00			1.10	0.15	0.00		
82.50	91.00			1	8.50			1.10	0.15	1.40		
91.00	95.30			1	4.30			1.10	0.15	0.71		
95.30	104.20			1	8.90			1.10	0.15	1.47		
104.20	113.40			1	9.20			1.10	0.15	1.52		
113.40	128.20			1	14.80			1.10	0.15	2.44		
		Connecting Road 1 (W0608)										
		RHS										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	23.80			1	8.80			0.90	0.15	1.19		
		LHS										

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth A or B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	25.40			1	10.40			0.90	0.15	1.40		
		Dead END (W/05/5)										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	17.70			1	2.70			0.90	0.15	0.36		
		Connecting Road 2										
		RHS										
				1	15.00			0.90	0.15	2.03		
0.00	15.00			1	6.60			0.90	0.15	0.89		
15.00	21.60											
		LHS										
				1	15.00			0.90	0.15	2.03		
0.00	15.00			1	8.90			0.90	0.15	1.20		
15.00	23.90											
		1st Main, 1st A Cross (W/05/5)										
				1	15.00			1.10	0.15	2.48		
0.00	15.00			1	5.50			1.10	0.15	0.91		
15.00	20.50			1	9.80			1.10	0.15	1.62		
20.50	30.30											
		2nd Main Road (W/06/6)										
		RHS										
		North to South										
				1	15.00			0.90	0.15	2.03		
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	15.00			0.90	0.15	2.03		
30.00	45.00			1	15.00			0.90	0.15	2.03		
45.00	60.00			1	14.40			0.90	0.15	1.94		
60.00	74.40											
				1	10.70			1.10	0.15	1.77		
0.00	10.70			1	14.30			1.10	0.15	2.36		
10.70	25.00			1	7.50			1.10	0.15	1.24		
25.00	32.50			1	12.50			1.10	0.15	2.06		
32.50	45.00			1	15.00			1.10	0.15	2.48		
45.00	60.00			1	15.00			1.10	0.15	2.48		
60.00	75.00			1	15.00			1.10	0.15	2.48		
75.00	90.00			1	15.00			1.10	0.15	2.48		
90.00	105.00			1	15.00			1.10	0.15	2.48		
105.00	120.00			1	1.20			1.10	0.15	0.20		
120.00	121.20											
		LHS										
		South to North										
				1	14.20			0.90	0.15	1.92		
0.00	14.20											
		2nd A Main Road (W/06/6)										
		RHS										
				1	15.00			1.00	0.15	2.25		
0.00	15.00			1	11.50			1.00	0.15	1.73		
15.00	26.50			1	9.20			1.00	0.15	1.38		
26.50	35.70			1	10.70			1.00	0.15	1.61		
35.70	46.40			1	11.60			1.00	0.15	1.74		
46.40	58.00			1	12.60			1.00	0.15	1.89		
58.00	70.60			1	12.70			1.00	0.15	1.91		
70.60	83.30											
		12th A Cross Road (W/06/12)										
		LHS										
		South to North										
				1	15.00			0.90	0.15	2.03		
0.00	15.00			1	12.20			0.90	0.15	1.65		
15.00	27.20			1	9.70			0.90	0.15	1.31		
27.20	36.90			1	7.50			0.90	0.15	1.01		
36.90	44.40			1	5.60			0.90	0.15	0.76		
44.40	59.40			1	15.00			0.90	0.15	2.03		
59.40	69.40			1	10.00			0.90	0.15	1.35		
69.40	79.40											
				1	15.00			0.90	0.15	2.03		
0.00	15.00			1	10.10			0.90	0.15	1.36		
15.00	25.10											

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Munikempanna Layout										
		1st Cross Road (W0973)										
		RHS										
		North to South										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	15.00			0.90	0.15	2.03		
30.00	45.00			1	15.00			0.90	0.15	2.03		
45.00	60.00			1	15.00			0.90	0.15	2.03		
60.00	75.00			1	15.00			0.90	0.15	2.03		
75.00	85.60			1	10.60			0.90	0.15	1.43		
		Dead END (W0965)										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	15.00			0.90	0.15	2.03		
30.00	35.70			1	5.70			0.90	0.15	0.77		
		Dasarahalli Main Road (M0022)										
		RHS										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	15.00			0.90	0.15	2.03		
30.00	45.00			1	15.00			0.90	0.15	2.03		
45.00	59.10			1	14.10			0.90	0.15	1.90		
		2nd Cross (W0983) Dead End										
0.00	12.90			1	12.90			0.90	0.15	1.74		
		Bhuvaneshwari Nagar										
		20th R Cross Road (W0961)										
		RHS										
0	15		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
15	30		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
30	45		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
45	47.5		Cum	1	2.50	0.95	0.95	0.95	0.15	0.36		
47.5	53	Culvert	Cum	1	0.00	0.95	0.95	0.95	0.15	0.00		
53	65		Cum	1	12.00	0.95	0.95	0.95	0.15	1.71		
65	80		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
80	95		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
95	99.7		Cum	1	4.70	0.95	0.95	0.95	0.15	0.67		
99.7	112		Cum	1	12.30	0.95	0.95	0.95	0.15	1.75		
112	125		Cum	1	13.00	0.95	0.95	0.95	0.15	1.85		
125	140		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
140	155		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
155	159.9		Cum	1	4.90	0.95	0.95	0.95	0.15	0.70		
		LHS										
0	15		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
15	30		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
30	40.5		Cum	1	10.50	0.95	0.95	0.95	0.15	1.50		
40.5	55		Cum	1	14.50	0.95	0.95	0.95	0.15	2.07		
55	65.5		Cum	1	10.50	0.95	0.95	0.95	0.15	1.50		
65.5	70.7	Culvert	Cum	1	0.00	0.95	0.95	0.95	0.15	0.00		
70.7	85		Cum	1	14.30	0.95	0.95	0.95	0.15	2.04		
85	100		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
100	111.8		Cum	1	11.80	0.95	0.95	0.95	0.15	1.68		
111.8	116.9	No Work	Cum	1	0.00	0.95	0.95	0.95	0.15	0.00		
116.9	130		Cum	1	13.10	0.95	0.95	0.95	0.15	1.87		
130	144.5		Cum	1	14.50	0.95	0.95	0.95	0.15	2.07		
144.5	148.7	No Work	Cum	1	0.00	0.95	0.95	0.95	0.15	0.00		
148.7	164.3		Cum	1	15.60	0.95	0.95	0.95	0.15	2.22		
		Dasarahalli Circle										
		West to East										
0.00	15.00		Cum	1	15.00	1.00	1.00	1.00	0.15	2.25		
15.00	27.70		Cum	1	12.70	1.00	1.00	1.00	0.15	1.91		
27.70	42.70		Cum	1	15.00	1.30	1.30	1.30	0.15	2.93		
42.70	57.70		Cum	1	15.00	1.30	1.30	1.30	0.15	2.93		
57.70	72.70		Cum	1	15.00	1.30	1.30	1.30	0.15	2.93		
72.70	87.70		Cum	1	15.00	1.30	1.30	1.30	0.15	2.93		
87.70	102.70		Cum	1	15.00	1.30	1.30	1.30	0.15	2.93		
102.70	117.70		Cum	1	15.00	1.30	1.30	1.30	0.15	2.93		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
117.70	132.70		Cum	1	15.00	1.30	1.30	1.30	0.15	2.93		
132.70	147.70		Cum	1	15.00	1.30	1.30	1.30	0.15	2.93		
147.70	155.00		Cum	1	7.30	1.30	1.30	1.30	0.15	1.42		
		For Culvert										
		Kuvempu Layout										
		2nd Main Road (W0616) CD1	Cum	1	5.75			1.40	0.15	1.21		
		1st Main 1st Cross Road (W0973) CD2		1	8.20			1.40	0.15	1.72		
		CD3		1	6.20			1.40	0.15	1.30		
		CD4		1	10.40			1.40	0.15	2.18		
		Dead End Road (W0965) CD5		1	8.10			1.40	0.15	1.70		
		21st Cross Road (W0969) CD6		1	7.40			1.40	0.15	1.55		
		Dasarahalli Main Road (M0022) CD7		1	7.00			1.40	0.15	1.47		
		1st Main Road (W0612) CD8		1	7.70			1.40	0.15	1.62		
		CD9		1	4.70			1.40	0.15	0.99		
		CD10		1	9.50			1.40	0.15	2.00		
		20th R Cross Road (W0961) CD11		1	7.00			1.40	0.15	1.47		
		18th A Cross Road (W0618) CD12		1	6.30			1.40	0.15	1.32		
		1st Main Road (W0612) CD13		1	5.50			1.40	0.15	1.16		
		Mariyanna Palya										
		Joseph House Road (W0884) CD14		1	5.60			1.70	0.15	1.43		
		Moto Works Oppo. (W1299) CD15		1	6.10			1.70	0.15	1.56		
		CD16		1	5.80			1.70	0.15	1.48		
		CD17		1	5.10			1.70	0.15	1.30		
		CD18		1	5.20			1.70	0.15	1.33		
		For Culvert Cross Road	Cum	1.00	5.80	1.70	1.70	1.70	0.15	1.48		
		For Kerb PCC										
		1st Main 3rd Cross Road										
		(South to North)	Cum									
0.00	7.20			1	7.20	0.20	0.20	0.20	0.10	0.14		
7.20	13.40	No Work		1	0.00	0.20	0.20	0.20	0.10	0.00		
13.40	19.00			1	5.60	0.20	0.20	0.20	0.10	0.11		
19.00	20.90	No Work		1	0.00	0.20	0.20	0.20	0.10	0.00		
20.90	30.40			1	9.50	0.20	0.20	0.20	0.10	0.19		
		Kailash House Road										
		(East to West)										
		LHS										
0.00	15.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	30.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
30.00	33.30			1	3.30	0.20	0.20	0.20	0.10	0.07		
33.30	37.00	No Work		1	0.00	0.20	0.20	0.20	0.10	0.00		
37.00	43.20			1	6.20	0.20	0.20	0.20	0.10	0.12		
43.20	46.50	No Work		1	0.00	0.20	0.20	0.20	0.10	0.00		
46.50	51.50			1	5.00	0.20	0.20	0.20	0.10	0.10		
		For Kerb										
		Mariyanna Palya										
		1st Main Road (W1307)										
		RHS										
0.00	15.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	21.30			1	6.30	0.20	0.20	0.20	0.10	0.13		
		Moto Works Oppo. (W1299)										
		LHS										
0.00	15.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	30.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
30.00	45.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
45.00	60.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
60.00	75.00			1	15.00	0.20	0.20	0.20	0.10	0.30		

BBMP (Ward No 06)

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
75.00	90.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
90.00	105.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
105.00	120.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
120.00	125.90			1	5.90	0.20	0.20	0.20	0.10	0.12		
		RHS										
0.00	15.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	17.60			1	2.60	0.20	0.20	0.20	0.10	0.05		
17.60	23.40	Culvert		1	0.00	0.20	0.20	0.20	0.10	0.00		
23.40	35.00			1	11.60	0.20	0.20	0.20	0.10	0.23		
35.00	50.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
50.00	55.20			1	5.20	0.20	0.20	0.20	0.10	0.10		
55.20	60.30	Culvert		1	0.00	0.20	0.20	0.20	0.10	0.00		
60.30	74.00			1	13.70	0.20	0.20	0.20	0.10	0.27		
74.00	77.30	Ramp		1	0.00	0.20	0.20	0.20	0.10	0.00		
77.30	86.30			1	9.00	0.20	0.20	0.20	0.10	0.18		
86.30	91.50	Culvert		1	0.00	0.20	0.20	0.20	0.10	0.00		
91.50	105.00			1	13.50	0.20	0.20	0.20	0.10	0.27		
105.00	117.20			1	12.20	0.20	0.20	0.20	0.10	0.24		
117.20	120.40	Ramp		1	0.00	0.20	0.20	0.20	0.10	0.00		
120.40	131.50			1	11.10	0.20	0.20	0.20	0.10	0.22		
		Kuvempu Layout										
		2nd Main road 2nd Cross Road (W0616)										
		LHS										
0.00	15.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	29.80			1	14.80	0.20	0.20	0.20	0.10	0.30		
		RHS										
0.00	15.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	30.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
		1st main 2nd Cross Road (W0983)										
		LHS										
0.00	15.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	30.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
30.00	45.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
45.00	63.10			1	18.10	0.20	0.20	0.20	0.10	0.36		
		RHS										
0.00	15.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	30.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
30.00	45.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
45.00	60.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
60.00	66.30			1	6.30	0.20	0.20	0.20	0.10	0.13		
		1st main 1st Cross Road (W0973)										
		RHS										
0.00	15.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	24.60			1	9.60	0.20	0.20	0.20	0.10	0.19		
24.60	27.80	Ramp		1	0.00	0.20	0.20	0.20	0.10	0.00		
27.80	45.00			1	17.20	0.20	0.20	0.20	0.10	0.34		
45.00	58.20			1	13.20	0.20	0.20	0.20	0.10	0.26		
		LHS										
0.00	15.00	Ramp		1	0.00	0.20	0.20	0.20	0.10	0.00		
15.00	25.60	Ramp		1	0.00	0.20	0.20	0.20	0.10	0.00		
25.60	41.40			1	15.80	0.20	0.20	0.20	0.10	0.32		
41.40	60.20			1	18.80	0.20	0.20	0.20	0.10	0.38		
		1st main Road (W0612)										
		RHS										
0.00	15.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	30.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
30.00	40.20			1	10.20	0.20	0.20	0.20	0.10	0.20		
0.00	15.00			1	15.00	0.20	0.20	0.20	0.10	0.30		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
15.00	30.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
30.00	45.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
45.00	54.30			1	9.30	0.20	0.20	0.20	0.10	0.19		
54.30	62.10	Road Break										
62.10	77.10			1	15.00	0.20	0.20	0.20	0.10	0.30		
77.10	92.10			1	15.00	0.20	0.20	0.20	0.10	0.30		
92.10	107.10			1	15.00	0.20	0.20	0.20	0.10	0.30		
107.10	122.10			1	15.00	0.20	0.20	0.20	0.10	0.30		
122.10	126.80			1	4.70	0.20	0.20	0.20	0.10	0.09		
		LHS										
0.00	15.00	No work		1	0.00	0.20	0.20	0.20	0.10	0.00		
15.00	30.00	No work		1	0.00	0.20	0.20	0.20	0.10	0.00		
30.00	45.00	No work		1	0.00	0.20	0.20	0.20	0.10	0.00		
45.00	50.00	No work		1	0.00	0.20	0.20	0.20	0.10	0.00		
50.00	65.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
65.00	80.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
80.00	95.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
95.00	110.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
110.00	125.30			1	15.30	0.20	0.20	0.20	0.10	0.31		
0.00	15.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	30.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
30.00	45.40			1	15.40	0.20	0.20	0.20	0.10	0.31		
45.40	50.30	No Work		1	0.00	0.20	0.20	0.20	0.10	0.00		
50.30	65.30			1	15.00	0.20	0.20	0.20	0.10	0.30		
65.30	74.80			1	9.50	0.20	0.20	0.20	0.10	0.19		
		1st Main 3rd Cross Road (W0989)										
		LHS										
0.00	15.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	30.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
30.00	45.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
45.00	61.80			1	16.80	0.20	0.20	0.20	0.10	0.34		
		2nd Main Road (W0616)										
		LHS										
0.00	15.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	21.20			1	6.20	0.20	0.20	0.20	0.10	0.12		
		RHS										
0.00	15.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	30.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
30.00	45.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
45.00	60.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
60.00	74.00			1	14.00	0.20	0.20	0.20	0.10	0.28		
0.00	15.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	30.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
30.00	45.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
45.00	60.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
60.00	75.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
75.00	90.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
90.00	105.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
105.00	120.80			1	15.80	0.20	0.20	0.20	0.10	0.32		
		21th Cross Road (W0969)										
		RHS										
0.00	15.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	29.20			1	5.20	0.20	0.20	0.20	0.10	0.10		
29.20	33.00	No Work										
33.00	48.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
48.00	63.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
63.00	68.40			1	5.40	0.20	0.20	0.20	0.10	0.11		
68.40	74.60	No Work										
74.60	89.60			1	15.00	0.20	0.20	0.20	0.10	0.30		
89.60	104.60			1	15.00	0.20	0.20	0.20	0.10	0.30		
104.60	119.60			1	15.00	0.20	0.20	0.20	0.10	0.30		
119.60	129.50			1	9.90	0.20	0.20	0.20	0.10	0.20		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		LHS										
0.00	13.60			1	13.60	0.20	0.20	0.20	0.10	0.27		
		Connecting Road-1 (W0608)										
		LHS										
0.00	15.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	25.40			1	10.40	0.20	0.20	0.20	0.10	0.21		
		RHS										
0.00	15.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	23.80			1	8.80	0.20	0.20	0.20	0.10	0.18		
		Dead End Road (W0965)										
		LHS										
0.00	15.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	17.00			1	2.00	0.20	0.20	0.20	0.10	0.04		
		Connecting Road -2										
		LHS										
0.00	15.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	20.50			1	5.50	0.20	0.20	0.20	0.10	0.11		
		RHS										
0.00	15.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	23.90			1	8.90	0.20	0.20	0.20	0.10	0.18		
		1st A Cross Road (W0975)										
		LHS										
0.00	15.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	30.50			1	15.50	0.20	0.20	0.20	0.10	0.31		
		2nd Main Road (W0616)										
0.00	15.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	24.80			1	9.80	0.20	0.20	0.20	0.10	0.20		
		18th A Cross Road (W0618)										
		LHS										
0.00	15.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	25.00			1	10.00	0.20	0.20	0.20	0.10	0.20		
25.00	34.80	Ramp		1	0.00	0.20	0.20	0.20	0.10	0.00		
34.80	49.80			1	15.00	0.20	0.20	0.20	0.10	0.30		
49.80	54.00			1	4.20	0.20	0.20	0.20	0.10	0.08		
54.00	69.00	Ramp		1	0.00	0.20	0.20	0.20	0.10	0.00		
69.00	72.30	Ramp		1	0.00	0.20	0.20	0.20	0.10	0.00		
		2nd A Cross Road (W0616)										
		LHS										
0.00	7.40	Ramp		1	0.00	0.20	0.20	0.20	0.10	0.00		
7.40	25.10			1	17.70	0.20	0.20	0.20	0.10	0.35		
25.10	40.50	Ramp		1	0.00	0.20	0.20	0.20	0.10	0.00		
40.50	55.50			1	15.00	0.20	0.20	0.20	0.10	0.30		
55.50	69.90			1	14.40	0.20	0.20	0.20	0.10	0.29		
69.90	83.10	No Work		1	0.00	0.20	0.20	0.20	0.10	0.00		
		2nd Main Road (W0616)										
		LHS										
0.00	8.00			1	8.00	0.20	0.20	0.20	0.10	0.16		
8.00	9.80	No Work		0	0.00	0.20	0.20	0.20	0.10	0.00		
9.80	24.80			1	15.00	0.20	0.20	0.20	0.10	0.30		
24.80	36.10			1	11.30	0.20	0.20	0.20	0.10	0.23		
		Mariyannana Palya										
		1st Main Road (W0973)										
		LHS										
0.00	15.00			1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	29.80			1	14.80	0.20	0.20	0.20	0.10	0.30		
29.80	37.40	Culvert		1	0.00	0.20	0.20	0.20	0.10	0.00		
37.40	52.40			1	15.00	0.20	0.20	0.20	0.10	0.30		
52.40	67.40			1	15.00	0.20	0.20	0.20	0.10	0.30		
67.40	82.40			1	15.00	0.20	0.20	0.20	0.10	0.30		
82.40	94.80			1	12.40	0.20	0.20	0.20	0.10	0.25		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
94.80	103.80	Culvert		1	0.00	0.20	0.20	0.20	0.10	0.00		
103.80	118.80			1	15.00	0.20	0.20	0.20	0.10	0.30		
118.80	128.00			1	9.20	0.20	0.20	0.20	0.10	0.18		
128.00	135.00	Culvert		1	0.00	0.20	0.20	0.20	0.10	0.00		
135.00	147.40			1	12.40	0.20	0.20	0.20	0.10	0.25		
147.40	152.60	No Work		1	0.00	0.20	0.20	0.20	0.10	0.00		
152.60	161.50			1	8.90	0.20	0.20	0.20	0.10	0.18		
161.50	177.00	No Work		1	0.00	0.20	0.20	0.20	0.10	0.00		
177.00	191.70			1	14.70	0.20	0.20	0.20	0.10	0.29		
		For Flagging Coarse										
		Mariyanna Palya										
		St. Anthony Church Road (10794)										
			Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
0.00	15.00			2	15.00	0.20	0.20	0.20	0.10	0.60		
15.00	30.00			0	0.00	0.20	0.20	0.20	0.10	0.00		
30.00	37.50	Culvert		2	12.50	0.20	0.20	0.20	0.10	0.50		
37.50	50.00			2	15.00	0.20	0.20	0.20	0.10	0.60		
50.00	65.00			2	15.00	0.20	0.20	0.20	0.10	0.60		
65.00	80.00			2	14.80	0.20	0.20	0.20	0.10	0.59		
80.00	94.80			0	0.00	0.20	0.20	0.20	0.10	0.00		
94.80	103.80	Culvert		2	11.20	0.20	0.20	0.20	0.10	0.45		
103.80	115.00			2	13.10	0.20	0.20	0.20	0.10	0.52		
115.00	128.10			0	0.00	0.20	0.20	0.20	0.10	0.00		
128.10	135.00	Culvert		2	12.30	0.20	0.20	0.20	0.10	0.49		
135.00	147.30			2	5.20	0.20	0.20	0.20	0.10	0.21		
147.30	152.50			2	9.50	0.20	0.20	0.20	0.10	0.38		
152.50	162.00			2	15.00	0.20	0.20	0.20	0.10	0.60		
162.00	177.00			2	14.50	0.20	0.20	0.20	0.10	0.58		
177.00	191.50			2	0.00	0.20	0.20	0.20	0.10	0.00		
191.50	200.00	No work		2	0.00	0.20	0.20	0.20	0.10	0.00		
200.00	215.00	No work		2	0.00	0.20	0.20	0.20	0.10	0.00		
215.00	228.00	No work		2	0.00	0.20	0.20	0.20	0.10	0.00		
228.00	240.00	No work		2	0.00	0.20	0.20	0.20	0.10	0.00		
240.00	244.50	No work		2	0.00	0.20	0.20	0.20	0.10	0.00		
										Total Executed Quantity	**514.64**	**6500.00**	**3345157.00**
										Tender Quantity	**519.33**		

Item no.05

Providing laying plain/ reinforced cement concrete for side Drains Using M20 nominal mix Concrete with OPC at 300kgs.With 20mm and Down size granite metal coarse aggregate at 0.69cum and fine aggregate at 0.43cum Machne mixed, well compacted for wall and Bottom including centering shuttering,cost of materials,HOM of Machinery,Curing Etc.,Complete Excluding cost of Steel as per morth MORTH specification and as per the directions of the Engineer-in-charge of the work

		Bottom Raft										
		Kaveri Layout										
		Krishna Nivas House (W1309)										
		LHS										
		South to North										
			Cum	1	2.50			0.90	0.15	0.34		
0.00	2.50			1	12.50			0.90	0.15	1.69		
2.50	15.00			1	3.40			0.90	0.15	0.46		
15.00	18.40			1	6.00			0.90	0.15	0.81		
18.40	24.40			1	10.60			0.90	0.15	1.43		
24.40	35.00			1	15.00			0.90	0.15	2.03		
35.00	50.00			1	14.10			0.90	0.15	1.90		
50.00	64.10			1	10.90			0.90	0.15	1.47		
64.10	75.00			1	12.80			0.90	0.15	1.73		
75.00	87.80			1	3.40			0.90	0.15	0.46		
87.80	91.20											
		RHS										
		North to South										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	19.40			1	4.40			0.90	0.15	0.59		
19.40	28.20			1	8.80			0.90	0.15	1.19		
28.20	33.50			1	5.30			0.90	0.15	0.72		
33.50	42.50			1	9.00			0.90	0.15	1.22		
42.50	54.90			1	12.40			0.90	0.15	1.67		
54.90	65.70			1	10.80			0.90	0.15	1.46		
65.70	74.10			1	8.40			0.90	0.15	1.13		
74.10	85.00			1	10.90			0.90	0.15	1.47		
85.00	92.60			1	7.60			0.90	0.15	1.03		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Joseph House Road (W0884)										
		RHS										
		West to East										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	15.00			0.90	0.15	2.03		
30.00	36.40			1	6.40			0.90	0.15	0.86		
36.40	48.10			1	11.70			0.90	0.15	1.58		
		LHS										
		West to East										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	27.20			1	12.20			0.90	0.15	1.65		
		1st Main Road (W1307)										
		LHS										
		North to South										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	21.30			1	6.30			0.90	0.15	0.85		
		Moto Works Oppo. (W1299)										
		RHS										
		North to South										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	17.60			1	2.60			0.90	0.15	0.35		
17.60	23.40	Culvert		1	0.00			0.90	0.15	0.00		
23.40	30.00			1	6.60			0.90	0.15	0.89		
30.00	45.00			1	15.00			0.90	0.15	2.03		
45.00	55.20			1	10.20			0.90	0.15	1.38		
55.20	60.30	Culvert		1	0.00			0.90	0.15	0.00		
60.30	75.00			1	14.70			0.90	0.15	1.98		
75.00	86.30			1	11.30			0.90	0.15	1.53		
86.30	91.50	Culvert		1	0.00			0.90	0.15	0.00		
91.50	105.00			1	13.50			0.90	0.15	1.82		
105.00	120.00			1	15.00			0.90	0.15	2.03		
120.00	129.60			1	9.60			0.90	0.15	1.30		
		LHS										
		South to North										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	19.20			1	4.20			0.90	0.15	0.57		
19.20	25.50			1	6.30			0.90	0.15	0.85		
25.50	30.00			1	4.50			0.90	0.15	0.61		
30.00	45.00			1	15.00			0.90	0.15	2.03		
45.00	60.00			1	15.00			0.90	0.15	2.03		
60.00	75.00			1	15.00			0.90	0.15	2.03		
75.00	90.00			1	15.00			0.90	0.15	2.03		
90.00	105.00			1	15.00			0.90	0.15	2.03		
105.00	120.00			1	15.00			0.90	0.15	2.03		
120.00	125.70			1	5.70			0.90	0.15	0.77		
		Cross Road 1 (W0870)										
		East to West										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	26.10			1	11.10			0.90	0.15	1.50		
		Cross Road 2 (W0862)										
		East to West										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	15.00			0.90	0.15	2.03		
30.00	33.00			1	3.00			0.90	0.15	0.41		
		Cross Road 3										
		East to West										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	15.00			0.90	0.15	2.03		
30.00	37.40			1	7.40			0.90	0.15	1.00		
		Cross Road (W1297)										
		LHS										

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		South to North										
0.00	15.00			1	15.00			1.10	0.15	2.48		
15.00	30.00			1	15.00			1.10	0.15	2.48		
30.00	45.00			1	15.00			1.10	0.15	2.48		
45.00	60.00			1	15.00			1.10	0.15	2.48		
60.00	75.00			1	15.00			1.10	0.15	2.48		
75.00	90.00			1	15.00			1.10	0.15	2.48		
90.00	105.00			1	15.00			1.10	0.15	2.48		
105.00	106.60			1	1.60			1.10	0.15	0.26		
		RHS										
		North to South										
0.00	15.00			1	15.00			1.10	0.15	2.48		
15.00	30.00			1	15.00			1.10	0.15	2.48		
30.00	45.00			1	15.00			1.10	0.15	2.48		
45.00	60.00			1	15.00			1.10	0.15	2.48		
60.00	75.00			1	15.00			1.10	0.15	2.48		
75.00	90.00			1	15.00			1.10	0.15	2.48		
90.00	105.00			1	15.00			1.10	0.15	2.48		
105.00	107.20			1	2.20			1.10	0.15	0.36		
		Kuvempu Layout										
		2nd Main, 2nd Cross (W0616)										
		RHS										
		North to South										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	15.00			0.90	0.15	2.03		
		LHS										
		South to North										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	29.80			1	14.80			0.90	0.15	2.00		
		1st Main, 3rd Cross (W0989)										
		RHS										
		North to South										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	15.00			0.90	0.15	2.03		
30.00	45.00			1	15.00			0.90	0.15	2.03		
45.00	60.00			1	15.00			0.90	0.15	2.03		
60.00	61.80			1	1.80			0.90	0.15	0.24		
		LHS										
		South to North										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	15.00			0.90	0.15	2.03		
30.00	45.00			1	15.00			0.90	0.15	2.03		
45.00	60.00			1	15.00			0.90	0.15	2.03		
60.00	66.90			1	6.90			0.90	0.15	0.93		
		Dead END										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	16.80			1	1.80			0.90	0.15	0.24		
		1st Main, 2nd Cross (W0983)										
		RHS										
		North to South										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	15.00			0.90	0.15	2.03		
30.00	45.00			1	15.00			0.90	0.15	2.03		
45.00	60.00			1	15.00			0.90	0.15	2.03		
60.00	63.10			1	3.10			0.90	0.15	0.42		
		LHS										
		South to North										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	15.00			0.90	0.15	2.03		
30.00	45.00			1	15.00			0.90	0.15	2.03		
45.00	60.00			1	15.00			0.90	0.15	2.03		
60.00	66.30			1	6.30			0.90	0.15	0.85		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Dead END										
0.00	5.00			1	5.00			0.90	0.15	0.68		
		1st Main, 1st Cross (W0973)										
		RHS										
		North to South										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	15.00			0.90	0.15	2.03		
30.00	45.00			1	15.00			0.90	0.15	2.03		
45.00	45.80			1	0.80			0.90	0.15	0.11		
45.80	59.20			1	13.40			0.90	0.15	1.81		
		LHS										
		South to North										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	27.00			1	12.00			0.90	0.15	1.62		
27.00	41.80			1	14.80			0.90	0.15	2.00		
41.80	55.00			1	13.20			0.90	0.15	1.78		
55.00	60.20			1	5.20			0.90	0.15	0.70		
		Dead END										
0.00	7.30			1	7.30			0.90	0.15	0.99		
		1st Main Road (W0612)										
		LHS										
		East To West										
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	15.00			0.90	0.15	2.03		
30.00	36.60			1	6.60			0.90	0.15	0.89		
0.00	15.00			1	15.00			1.10	0.15	2.48		
15.00	30.00			1	15.00			1.10	0.15	2.48		
30.00	45.00			1	15.00			1.10	0.15	2.48		
45.00	53.30			1	8.30			1.10	0.15	1.37		
53.30	61.10	Road Break		1	0.00			1.10	0.15	0.00		
61.10	70.70			1	9.60			1.10	0.15	1.58		
70.70	85.00			1	14.30			1.10	0.15	2.36		
85.00	100.00			1	15.00			1.10	0.15	2.48		
100.00	115.00			1	15.00			1.10	0.15	2.48		
115.00	125.80			1	10.80			1.10	0.15	1.78		
		RHS										
		West To East										
0.00	15.00			1	15.00			1.10	0.15	2.48		
15.00	30.00			1	15.00			1.10	0.15	2.48		
30.00	45.00			1	15.00			1.10	0.15	2.48		
45.00	48.80			1	3.80			1.10	0.15	0.63		
48.80	63.80			1	15.00			1.10	0.15	2.48		
0.00	15.00			1	15.00			1.10	0.15	2.48		
15.00	30.00			1	15.00			1.10	0.15	2.48		
30.00	45.00			1	15.00			1.10	0.15	2.48		
45.00	60.00			1	15.00			1.10	0.15	2.48		
60.00	74.20			1	14.20			1.10	0.15	2.34		
		21st Cross Road (W0969)										
		RHS										
		North to South										
0.00	15.00			1	15.00			1.10	0.15	2.48		
15.00	20.20			1	5.20			1.10	0.15	0.86		
20.20	33.00	No Work		1	0.00			1.10	0.15	0.00		
33.00	45.00			1	12.00			1.10	0.15	1.98		
45.00	60.00			1	15.00			1.10	0.15	2.48		
60.00	68.40			1	8.40			1.10	0.15	1.39		
68.40	74.60			1	6.20			1.10	0.15	1.02		
74.60	85.00			1	10.40			1.10	0.15	1.72		

BBMP (Water No 06)

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in Rs	Amount in Rs
85.00	100.00			1	15.00			1.10	0.15	2.48		
100.00	115.00			1	15.00			1.10	0.15	2.48		
115.00	128.80			1	13.80			1.10	0.15	2.23		
		LHS										
		South to North										
				1	15.00			1.10	0.15	2.48		
0.00	15.00			1	2.60			1.10	0.15	0.43		
15.00	17.60			1	4.20			1.10	0.15	0.69		
17.00	21.80			1	4.70			1.10	0.15	0.78		
21.80	26.50			1	0.90			1.10	0.15	1.83		
26.50	36.40			1	10.40			1.10	0.15	1.72		
36.40	46.80			1	10.40			1.10	0.15	1.72		
46.80	57.20			1	12.80			1.10	0.15	2.11		
57.20	70.00			1	8.40			1.10	0.15	1.39		
70.00	78.40			1	0.00			1.10	0.15	0.00		
78.40	82.50	No Work		1	8.50			1.10	0.15	1.40		
82.50	91.00			1	4.30			1.10	0.15	0.71		
91.00	95.30			1	8.90			1.10	0.15	1.47		
95.30	104.20			1	9.20			1.10	0.15	1.52		
104.20	113.40			1	14.80			1.10	0.15	2.44		
113.40	128.20											
		Connecting Road 1 (W0608)										
		RHS										
				1	15.00			0.90	0.15	2.03		
0.00	15.00			1	8.80			0.90	0.15	1.19		
15.00	23.80											
		LHS		1	15.00			0.90	0.15	2.03		
0.00	15.00			1	10.40			0.90	0.15	1.40		
15.00	25.40											
		Dead END (W0965)		1	15.00			0.90	0.15	2.03		
0.00	15.00			1	2.70			0.90	0.15	0.36		
15.00	17.70											
		Connecting Road 2										
		RHS		1	15.00			0.90	0.15	2.03		
0.00	15.00			1	6.60			0.90	0.15	0.89		
15.00	21.60											
		LHS		1	15.00			0.90	0.15	2.03		
0.00	15.00			1	8.90			0.90	0.15	1.20		
15.00	23.90											
		1st Main, 1st A Cross (W0975)		1	15.00			1.10	0.15	2.48		
0.00	15.00			1	5.50			1.10	0.15	0.91		
15.00	20.50			1	9.80			1.10	0.15	1.62		
20.50	30.30											
		2nd Main Road (W0616)										
		RHS										
		North to South		1	15.00			0.90	0.15	2.03		
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	15.00			0.90	0.15	2.03		
30.00	45.00			1	15.00			0.90	0.15	2.03		
45.00	60.00			1	14.40			0.90	0.15	1.94		
60.00	74.40											
				1	10.70			1.10	0.15	1.77		
0.00	10.70			1	14.30			1.10	0.15	2.36		
10.70	25.00			1	7.50			1.10	0.15	1.24		
25.00	32.50			1	12.50			1.10	0.15	2.06		
32.50	45.00			1	15.00			1.10	0.15	2.48		
45.00	60.00			1	15.00			1.10	0.15	2.48		
60.00	75.00			1	15.00			1.10	0.15	2.48		
75.00	90.00			1	15.00			1.10	0.15	2.48		
90.00	105.00			1	15.00			1.10	0.15	2.48		
105.00	120.00			1	1.20			1.10	0.15	0.20		
120.00	121.20											
		LHS										
		South to North										

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Avg B	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
0.00	14.20			1	14.20			0.90	0.15	1.92		
		2nd A Main Road (W0616)										
		RHS						1.00	0.15	2.25		
				1	15.00			1.00	0.15	1.73		
0.00	15.00			1	11.50			1.00	0.15	1.38		
15.00	26.50			1	9.20			1.00	0.15	1.61		
26.50	35.70			1	10.70			1.00	0.15	1.74		
35.70	46.40			1	11.60			1.00	0.15	1.89		
46.40	58.00			1	12.60			1.00	0.15	1.91		
58.00	70.60			1	12.70							
70.60	83.30											
		18th A Cross Road (W0618)										
		LHS						0.90	0.15	2.03		
		South to North		1	15.00			0.90	0.15	1.65		
0.00	15.00			1	12.20			0.90	0.15	1.31		
15.00	27.20			1	9.70			0.90	0.15	1.01		
27.20	36.90			1	7.50			0.90	0.15	0.76		
36.90	44.40			1	5.60			0.90	0.15	2.03		
44.40	50.00			1	15.00			0.90	0.15	1.35		
50.00	65.00			1	10.00							
65.00	75.00							0.90	0.15	2.03		
				1	15.00			0.90	0.15	1.36		
0.00	15.00			1	10.10							
15.00	25.10											
		Munikempanna Layout										
		1st Cross Road (W0973)										
		RHS										
		North to South						0.90	0.15	2.03		
				1	15.00			0.90	0.15	2.03		
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	15.00			0.90	0.15	2.03		
30.00	45.00			1	15.00			0.90	0.15	2.03		
45.00	60.00			1	15.00			0.90	0.15	2.03		
60.00	75.00			1	10.60			0.90	0.15	1.43		
75.00	85.60											
		Dead END (W0965)										
				1	15.00			0.90	0.15	2.03		
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	5.70			0.90	0.15	0.77		
30.00	35.70											
		Dasarahalli Main Road (M0022)										
		RHS						0.90	0.15	2.03		
0.00	15.00			1	15.00			0.90	0.15	2.03		
15.00	30.00			1	15.00			0.90	0.15	2.03		
30.00	45.00			1	15.00			0.90	0.15	1.90		
45.00	59.10			1	14.10							
		2nd Cross (W0983) Dead End										
				1	12.90			0.90	0.15	1.74		
0.00	12.90											
		Bhuvaneshwari Nagar										
		20th R Cross Road (W0961)										
		RHS										
0.00	15.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
15.00	30.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
30.00	45.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
45.00	47.50		Cum	1	2.50	0.75	0.75	0.75	0.15	0.28		
47.50	53.00	Culvert	Cum	1	0.00	0.75	0.75	0.75	0.15	0.00		
53.00	65.00		Cum	1	12.00	0.75	0.75	0.75	0.15	1.35		
65.00	80.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
80.00	95.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
95.00	99.70		Cum	1	4.70	0.75	0.75	0.75	0.15	0.53		
99.70	112.00		Cum	1	12.30	0.75	0.75	0.75	0.15	1.38		
112.00	125.00		Cum	1	13.00	0.75	0.75	0.75	0.15	1.46		
125.00	140.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
140.00	155.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
155.00	159.90		Cum	1	4.90	0.75	0.75	0.75	0.15	0.55		

BBMP (Ward No 06)

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		LHS										
0.00	15.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
15.00	30.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
30.00	40.50		Cum	1	10.50	0.75	0.75	0.75	0.15	1.18		
40.50	55.00		Cum	1	14.50	0.75	0.75	0.75	0.15	1.63		
55.00	65.50		Cum	1	10.50	0.75	0.75	0.75	0.15	1.18		
65.50	70.70	Culvert	Cum	1	0.00	0.75	0.75	0.75	0.15	0.00		
70.70	85.00		Cum	1	14.30	0.75	0.75	0.75	0.15	1.61		
85.00	100.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
100.00	111.80		Cum	1	11.80	0.75	0.75	0.75	0.15	1.33		
111.80	116.90	No Work	Cum	1	0.00	0.75	0.75	0.75	0.15	0.00		
116.90	130.00		Cum	1	13.10	0.75	0.75	0.75	0.15	1.47		
130.00	144.50		Cum	1	14.50	0.75	0.75	0.75	0.15	1.63		
144.50	148.70	No Work	Cum	1	0.00	0.75	0.75	0.75	0.15	0.00		
148.70	164.30		Cum	1	15.60	0.75	0.75	0.75	0.15	1.76		
		Dasarahalli Circle										
		West to East										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.20	2.70		
15	27.7		Cum	1	12.70	0.90	0.90	0.90	0.20	2.29		
27.7	42.7		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
42.7	57.7		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
57.7	72.7		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
72.7	87.7		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
87.7	102.7		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
102.7	117.7		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
117.7	132.7		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
132.7	147.7		Cum	1	15.00	1.20	1.20	1.20	0.20	3.60		
147.7	155		Cum	1	7.30	1.20	1.20	1.20	0.20	1.75		
		Side Wall										
		Kaveri Layout										
		Krishna Nivas House (W1309)										
		LHS										
		South to North										
0.00	2.50		Cum	2	2.50			0.15	0.60	0.45		
2.50	15.00			2	12.50			0.15	0.60	2.25		
15.00	18.40			2	3.40			0.15	0.60	0.61		
18.40	24.40			2	6.00			0.15	0.60	1.08		
24.40	35.00			2	10.60			0.15	0.60	1.91		
35.00	50.00			2	15.00			0.15	0.60	2.70		
50.00	64.10			2	14.10			0.15	0.60	2.54		
64.10	75.00			2	10.90			0.15	0.60	1.96		
75.00	87.80			2	12.80			0.15	0.60	2.30		
87.80	91.20			2	3.40			0.15	0.60	0.61		
		RHS										
		North to South										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	19.40			2	4.40			0.15	0.60	0.79		
19.40	28.20			2	8.80			0.15	0.60	1.58		
28.20	33.50			2	5.30			0.15	0.60	0.95		
33.50	42.50			2	9.00			0.15	0.60	1.62		
42.50	54.90			2	12.40			0.15	0.60	2.23		
54.90	65.70			2	10.80			0.15	0.60	1.94		
65.70	74.10			2	8.40			0.15	0.60	1.51		
74.10	85.00			2	10.90			0.15	0.60	1.96		
85.00	92.60			2	7.60			0.15	0.60	1.37		
		Joseph House Road (W0884)										
		RHS										
		West to East										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	30.00			2	15.00			0.15	0.60	2.70		
30.00	36.40			2	6.40			0.15	0.60	1.15		
36.40	48.10			2	11.70			0.15	0.60	2.11		
		LHS										
		West to East										

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	27.20			2	12.20			0.15	0.60	2.20		
		1st Main Road (W1307)										
		LHS										
		North to South										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	21.30			2	6.30			0.15	0.60	1.13		
		Moto Works Oppo. (W1299)										
		RHS										
		North to South										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	17.60			2	2.60			0.15	0.60	0.47		
17.60	23.40	Culvert		2	0.00			0.15	0.60	0.00		
23.40	30.00			2	6.60			0.15	0.60	1.19		
30.00	45.00			2	15.00			0.15	0.60	2.70		
45.00	55.20			2	10.20			0.15	0.60	1.84		
55.20	60.30	Culvert		2	0.00			0.15	0.60	0.00		
60.30	75.00			2	14.70			0.15	0.60	2.65		
75.00	86.30			2	11.30			0.15	0.60	2.03		
86.30	91.50	Culvert		2	0.00			0.15	0.60	0.00		
91.50	105.00			2	13.50			0.15	0.60	2.43		
105.00	120.00			2	15.00			0.15	0.60	2.70		
120.00	129.60			2	9.60			0.15	0.60	1.73		
		LHS										
		South to North										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	19.20			2	4.20			0.15	0.60	0.76		
19.20	25.50			2	6.30			0.15	0.60	1.13		
25.50	30.00			2	4.50			0.15	0.60	0.81		
30.00	45.00			2	15.00			0.15	0.60	2.70		
45.00	60.00			2	15.00			0.15	0.60	2.70		
60.00	75.00			2	15.00			0.15	0.60	2.70		
75.00	90.00			2	15.00			0.15	0.60	2.70		
90.00	105.00			2	15.00			0.15	0.60	2.70		
105.00	120.00			2	15.00			0.15	0.60	2.70		
120.00	125.70			2	5.70			0.15	0.60	1.03		
		Cross Road 1 (W0870)										
		East to West										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	26.10			2	11.10			0.15	0.60	2.00		
		Cross Road 2 (W0862)										
		East to West										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	30.00			2	15.00			0.15	0.60	2.70		
30.00	33.00			2	3.00			0.15	0.60	0.54		
		Cross Road 3										
		East to West										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	30.00			2	15.00			0.15	0.60	2.70		
30.00	37.40			2	7.40			0.15	0.60	1.33		
		Cross Road (W1297)										
		LHS										
		South to North										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	30.00			2	15.00			0.15	0.60	2.70		
30.00	45.00			2	15.00			0.15	0.60	2.70		
45.00	60.00			2	15.00			0.15	0.60	2.70		
60.00	75.00			2	15.00			0.15	0.60	2.70		
75.00	90.00			2	15.00			0.15	0.60	2.70		
90.00	105.00			2	15.00			0.15	0.60	2.70		
105.00	106.60			2	1.60			0.15	0.60	0.29		
		RHS										

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		North to South										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	30.00			2	15.00			0.15	0.60	2.70		
30.00	45.00			2	15.00			0.15	0.60	2.70		
45.00	60.00			2	15.00			0.15	0.60	2.70		
60.00	75.00			2	15.00			0.15	0.60	2.70		
75.00	90.00			2	15.00			0.15	0.60	2.70		
90.00	105.00			2	15.00			0.15	0.60	2.70		
105.00	107.20			2	2.20			0.15	0.60	0.40		
		Kuvempu Layout										
		2nd Main, 2nd Cross (W0616)										
		RHS										
		North to South										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	30.00			2	15.00			0.15	0.60	2.70		
		LHS										
		South to North										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	29.80			2	14.80			0.15	0.60	2.66		
		1st Main, 3rd Cross (W0989)										
		RHS										
		North to South										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	30.00			2	15.00			0.15	0.60	2.70		
30.00	45.00			2	15.00			0.15	0.60	2.70		
45.00	60.00			2	15.00			0.15	0.60	2.70		
60.00	61.80			2	1.80			0.15	0.60	0.32		
		LHS										
		South to North										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	30.00			2	15.00			0.15	0.60	2.70		
30.00	45.00			2	15.00			0.15	0.60	2.70		
45.00	60.00			2	15.00			0.15	0.60	2.70		
60.00	66.90			2	6.90			0.15	0.60	1.24		
		Dead END										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	16.80			2	1.80			0.15	0.60	0.32		
		1st Main, 2nd Cross (W0983)										
		RHS										
		North to South										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	30.00			2	15.00			0.15	0.60	2.70		
30.00	45.00			2	15.00			0.15	0.60	2.70		
45.00	60.00			2	15.00			0.15	0.60	2.70		
60.00	63.10			2	3.10			0.15	0.60	0.56		
		LHS										
		South to North										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	30.00			2	15.00			0.15	0.60	2.70		
30.00	45.00			2	15.00			0.15	0.60	2.70		
45.00	60.00			2	15.00			0.15	0.60	2.70		
60.00	66.30			2	6.30			0.15	0.60	1.13		
		Dead END										
0.00	5.00			2	5.00			0.15	0.60	0.90		
		1st Main, 1st Cross (W0973)										
		RHS										
		North to South										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	30.00			2	15.00			0.15	0.60	2.70		
30.00	45.00			2	15.00			0.15	0.60	2.70		
45.00	45.80			2	0.80			0.15	0.60	0.14		
45.80	59.20			2	13.40			0.15	0.60	2.41		
		LHS										

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		South to North										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	27.00			2	12.00			0.15	0.60	2.16		
27.00	41.80			2	14.80			0.15	0.60	2.66		
41.80	55.00			2	13.20			0.15	0.60	2.38		
55.00	60.20			2	5.20			0.15	0.60	0.94		
		Dead END										
0.00	7.30			2	7.30			0.15	0.60	1.31		
		1st Main Road (W0612)										
		LHS										
		East To West										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	30.00			2	15.00			0.15	0.60	2.70		
30.00	36.60			2	6.60			0.15	0.60	1.19		
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	30.00			2	15.00			0.15	0.60	2.70		
30.00	45.00			2	15.00			0.15	0.60	2.70		
45.00	53.30			2	8.30			0.15	0.60	1.49		
53.30	61.10	Road Break		2	0.00			0.15	0.60	0.00		
61.10	70.70			2	9.60			0.15	0.60	1.73		
70.70	85.00			2	14.30			0.15	0.60	2.57		
85.00	100.00			2	15.00			0.15	0.60	2.70		
100.00	115.00			2	15.00			0.15	0.60	2.70		
115.00	125.80			2	10.80			0.15	0.60	1.94		
		RHS										
		West To East										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	30.00			2	15.00			0.15	0.60	2.70		
30.00	45.00			2	15.00			0.15	0.60	2.70		
45.00	48.80			2	3.80			0.15	0.60	0.68		
48.80	63.80			2	15.00			0.15	0.60	2.70		
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	30.00			2	15.00			0.15	0.60	2.70		
30.00	45.00			2	15.00			0.15	0.60	2.70		
45.00	60.00			2	15.00			0.15	0.60	2.70		
60.00	74.20			2	14.20			0.15	0.60	2.56		
		21st Cross Road (W0969)										
		RHS										
		North to South										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	20.20			2	5.20			0.15	0.60	0.94		
20.20	33.00	No Work		2	0.00			0.15	0.60	0.00		
33.00	45.00			2	12.00			0.15	0.60	2.16		
45.00	60.00			2	15.00			0.15	0.60	2.70		
60.00	68.40			2	8.40			0.15	0.60	1.51		
68.40	74.60			2	6.20			0.15	0.60	1.12		
74.60	85.00			2	10.40			0.15	0.60	1.87		
85.00	100.00			2	15.00			0.15	0.60	2.70		
100.00	115.00			2	15.00			0.15	0.60	2.70		
115.00	128.50			2	13.50			0.15	0.60	2.43		
		LHS										
		South to North										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	17.60			2	2.60			0.15	0.60	0.47		
17.60	21.80			2	4.20			0.15	0.60	0.76		
21.80	26.50			2	4.70			0.15	0.60	0.85		
26.50	36.40			2	9.90			0.15	0.60	1.78		
36.40	46.80			2	10.40			0.15	0.60	1.87		
46.80	57.20			2	10.40			0.15	0.60	1.87		
57.20	70.00			2	12.80			0.15	0.60	2.30		
70.00	78.40			2	8.40			0.15	0.60	1.51		
78.40	82.50	No Work		2	0.00			0.15	0.60	0.00		
82.50	91.00			2	8.50			0.15	0.60	1.53		
91.00	95.30			2	4.30			0.15	0.60	0.77		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
85.30	101.20			2	8.90			0.15	0.60	1.60		
101.20	113.40			2	9.20			0.15	0.60	1.66		
113.40	128.20			2	14.80			0.15	0.60	2.66		
		Connecting Road 1 (W0608)										
		RHS										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	23.80			2	8.80			0.15	0.60	1.58		
		LHS										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	25.40			2	10.40			0.15	0.60	1.87		
		Dead END (W0965)										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	17.70			2	2.70			0.15	0.60	0.49		
		Connecting Road 2										
		RHS										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	21.60			2	6.60			0.15	0.60	1.19		
		LHS										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	23.90			2	8.90			0.15	0.60	1.60		
		1st Main, 1st A Cross (W0975)										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	20.50			2	5.50			0.15	0.60	0.99		
20.50	30.30			2	9.80			0.15	0.60	1.76		
		2nd Main Road (W0616)										
		RHS										
		North to South										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	30.00			2	15.00			0.15	0.60	2.70		
30.00	45.00			2	15.00			0.15	0.60	2.70		
45.00	60.00			2	15.00			0.15	0.60	2.70		
60.00	74.40			2	14.40			0.15	0.60	2.59		
0.00	10.70			2	10.70			0.15	0.60	1.93		
10.70	25.00			2	14.30			0.15	0.60	2.57		
25.00	32.50			2	7.50			0.15	0.60	1.35		
32.50	45.00			2	12.50			0.15	0.60	2.25		
45.00	60.00			2	15.00			0.15	0.60	2.70		
60.00	75.00			2	15.00			0.15	0.60	2.70		
75.00	90.00			2	15.00			0.15	0.60	2.70		
90.00	105.00			2	15.00			0.15	0.60	2.70		
105.00	120.00			2	15.00			0.15	0.60	2.70		
120.00	121.20			2	1.20			0.15	0.60	0.22		
		LHS										
		South to North										
0.00	14.20			2	14.20			0.15	0.60	2.56		
		2nd A Main Road (W0616)										
		RHS										
0.00	15.00			2	15.00			0.15	0.60	2.70		
15.00	26.50			2	11.50			0.15	0.60	2.07		
26.50	35.70			2	9.20			0.15	0.60	1.66		
35.70	46.40			2	10.70			0.15	0.60	1.93		
46.40	58.00			2	11.60			0.15	0.60	2.09		
58.00	70.60			2	12.60			0.15	0.60	2.27		
70.60	83.30			2	12.70			0.15	0.60	2.29		
		18th A Cross Road (W0618)										
		LHS										
		South to North										
0.00	15.00			2	15.00			0.15	0.60	2.70		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
0.00	12.20			2	12.200			0.15	0.60	2.20		
12.20	17.70			2	9.700			0.15	0.60	1.75		
17.70	30.40			2	7.500			0.15	0.60	1.35		
30.40	44.40			2	5.600			0.15	0.60	1.01		
44.40	51.70			2	15.000			0.15	0.60	2.70		
51.70	65.70			2	11.000			0.15	0.60	1.98		
65.70	75.70											
0.00	15.00			2	15.000			0.15	0.60	2.70		
15.00	25.00			2	10.100			0.15	0.60	1.82		
		Munikempanna Layout										
		1st Cross Road (W1973)										
		RHS										
		North to South										
0.00	15.00			2	15.000			0.15	0.60	2.70		
15.00	30.00			2	15.000			0.15	0.60	2.70		
30.00	45.00			2	15.000			0.15	0.60	2.70		
45.00	60.00			2	15.000			0.15	0.60	2.70		
60.00	75.00			2	15.000			0.15	0.60	2.70		
75.00	85.50			2	10.550			0.15	0.60	1.91		
		Dead END (W2965)										
0.00	15.00			2	15.000			0.15	0.60	2.70		
15.00	30.00			2	15.000			0.15	0.60	2.70		
30.00	35.70			2	5.700			0.15	0.60	1.03		
		Dasarahalli Main Road (MR22)										
		RHS										
0.00	15.00			2	15.000			0.15	0.60	2.70		
15.00	30.00			2	15.000			0.15	0.60	2.70		
30.00	45.00			2	15.000			0.15	0.60	2.70		
45.00	59.10			2	14.100			0.15	0.60	2.54		
		2nd Cross (W2985) Dead End										
0.00	12.90			2	12.900			0.15	0.60	2.32		
		Bhuvaneshwari Nagar										
		20th R Cross Road (W2961)										
		RHS										
0.00	15.00		Cum	2	15.000	0.15	0.15	0.15	0.60	2.70		
15.00	30.00		Cum	2	15.000	0.15	0.15	0.15	0.60	2.70		
30.00	45.00		Cum	2	15.000	0.15	0.15	0.15	0.60	2.70		
45.00	47.50		Cum	2	2.500	0.15	0.15	0.15	0.60	0.45		
47.50	53.00	Culvert	Cum	2	0.000	0.15	0.15	0.15	0.60	0.00		
53.00	65.00		Cum	2	12.000	0.15	0.15	0.15	0.60	2.16		
65.00	80.00		Cum	2	15.000	0.15	0.15	0.15	0.60	2.70		
80.00	95.00		Cum	2	15.000	0.15	0.15	0.15	0.60	2.70		
95.00	99.70		Cum	2	4.700	0.15	0.15	0.15	0.60	0.85		
99.70	112.00		Cum	2	12.300	0.15	0.15	0.15	0.60	2.21		
112.00	125.00		Cum	2	13.000	0.15	0.15	0.15	0.60	2.34		
125.00	140.00		Cum	2	15.000	0.15	0.15	0.15	0.60	2.70		
140.00	155.00		Cum	2	15.000	0.15	0.15	0.15	0.60	2.70		
155.00	159.90		Cum	2	4.900	0.15	0.15	0.15	0.60	0.88		
		LHS										
0.00	15.00		Cum	2	15.000	0.15	0.15	0.15	0.60	2.70		
15.00	30.00		Cum	2	15.000	0.15	0.15	0.15	0.60	2.70		
30.00	40.50		Cum	2	10.500	0.15	0.15	0.15	0.60	1.89		
40.50	55.00		Cum	2	14.500	0.15	0.15	0.15	0.60	2.61		
55.00	65.50		Cum	2	10.500	0.15	0.15	0.15	0.60	1.89		
65.50	70.70	Culvert	Cum	2	0.000	0.15	0.15	0.15	0.60	0.00		
70.70	85.00		Cum	2	14.300	0.15	0.15	0.15	0.60	2.57		
85.00	100.00		Cum	2	15.000	0.15	0.15	0.15	0.60	2.70		
100.00	111.80		Cum	2	11.800	0.15	0.15	0.15	0.60	2.12		
111.80	116.90	No Work	Cum	2	0.000	0.15	0.15	0.15	0.60	0.00		
116.90	130.00		Cum	2	13.100	0.15	0.15	0.15	0.60	2.36		
130.00	144.50		Cum	2	14.500	0.15	0.15	0.15	0.60	2.61		
144.50	148.70	No Work	Cum	2	0.000	0.15	0.15	0.15	0.60	0.00		
148.70	164.30		Cum	2	15.600	0.15	0.15	0.15	0.60	2.81		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Dasarahalli Circle										
		West to East										
0.00	15.00		Cum	2	15.00	0.20	0.20	0.20	0.90	5.40		
15.00	27.70		Cum	2	12.70	0.20	0.20	0.20	0.90	4.57		
27.70	42.70		Cum	2	15.00	0.20	0.20	0.20	0.90	5.40		
42.70	57.70		Cum	2	15.00	0.20	0.20	0.20	0.90	5.40		
57.70	72.70		Cum	2	15.00	0.20	0.20	0.20	0.90	5.40		
72.70	87.70		Cum	2	15.00	0.20	0.20	0.20	0.90	5.40		
87.70	102.70		Cum	2	15.00	0.20	0.20	0.20	0.90	5.40		
102.70	117.70		Cum	2	15.00	0.20	0.20	0.20	0.90	5.40		
117.70	132.70		Cum	2	15.00	0.20	0.20	0.20	0.90	5.40		
132.70	147.70		Cum	2	15.00	0.20	0.20	0.20	0.90	5.40		
147.70	155.00		Cum	2	7.30	0.20	0.20	0.20	0.90	2.63		
									Sub Total	1013.14		
		Culvert										
		Bottom Raft										
		Kuvempu Layout										
		2nd Main Road (W0616) CD1	Cum	1	5.75			1.40	0.20	1.61		
		1st Main 1st Cross Road (W0973) CD2		1	8.20			1.40	0.20	2.30		
		CD3		1	6.20			1.40	0.20	1.74		
		CD4		1	10.40			1.40	0.20	2.91		
		Dead End Road (W0965) CD5		1	8.10			1.40	0.20	2.27		
		21st Cross Road (W0969) CD6		1	7.40			1.40	0.20	2.07		
		Dasarahalli Main Road (M0022) CD7		1	7.00			1.40	0.20	1.96		
		1st Main Road (W0612) CD8		1	7.70			1.40	0.20	2.16		
		CD9		1	4.70			1.40	0.20	1.32		
		CD10		1	9.50			1.40	0.20	2.66		
		20th R Cross Road (W0961) CD11		1	7.00			1.40	0.20	1.96		
		18th A Cross Road (W0618) CD12		1	6.30			1.40	0.20	1.76		
		1st Main Road (W0612) CD13		1	5.50			1.40	0.20	1.54		
		Mariyanna Palya										
		Joseph House Road (W0884) CD14		1	5.60			1.70	0.20	1.90		
		Moto Works Oppo. (W1299) CD15		1	6.10			1.70	0.20	2.07		
		CD16		1	5.80			1.70	0.20	1.97		
		CD17		1	5.10			1.70	0.20	1.73		
		CD18		1	5.20			1.70	0.20	1.77		
		Cross Road	Cum	1	5.80	1.50	1.50	1.50	0.20	1.74		
		Side Wall										
		Kuvempu Layout										
		2nd Main Road (W0616) CD1		2	5.75			0.23	0.50	1.32		
		1st Main 1st Cross Road (W0973) CD2		2	8.20			0.23	0.50	1.89		
		CD3		2	6.20			0.23	0.50	1.43		
		CD4		2	10.40			0.23	0.50	2.39		
		Dead End Road (W0965) CD5		2	8.10			0.23	0.50	1.86		
		21st Cross Road (W0969) CD6		2	7.40			0.23	0.50	1.70		
		Dasarahalli Main Road (M0022) CD7		2	7.00			0.23	0.50	1.61		
		1st Main Road (W0612) CD8		2	7.70			0.23	0.50	1.77		
				2	4.70			0.23	0.50	1.08		
				2	9.50			0.23	0.50	2.19		
		20th R Cross Road (W0961) CD11		2	7.00			0.23	0.50	1.61		
		18th A Cross Road (W0618) CD12		2	6.30			0.23	0.50	1.45		
		1st Main Road (W0612) CD13		2	5.50			0.23	0.50	1.27		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Mariyamma Palya										
		Joseph House Road (W0884)										
		CD14		2	5.60			0.23	0.50	1.29		
		Moto Works Oppo (W1299)										
		CD15		2	6.10			0.23	0.50	1.40		
		CD16		2	5.80			0.23	0.50	1.33		
		CD17		2	5.10			0.23	0.50	1.17		
		CD18		2	5.20			0.23	0.50	1.20		
		Cross Road	Cum	2	5.80	0.23	0.23	0.23	0.60	1.60		
									Sub Total	67.09		
		Bed Concrete										
		Mariyanna Palya										
		St. Anthony Church Road (10794)										
			Cum	1	15.00			0.75	0.10	1.13		
0.00	15.00			1	15.00			0.75	0.10	1.13		
15.00	30.00			0	0.00			0.75	0.10	0.00		
30.00	37.50	**Culvert**		1	12.50			0.75	0.10	0.94		
37.50	50.00			1	15.00			0.75	0.10	1.13		
50.00	65.00			1	15.00			0.75	0.10	1.13		
65.00	80.00			1	14.80			0.75	0.10	1.11		
80.00	94.80			0	0.00			0.00	0.10	0.00		
94.80	103.80	**Culvert**		1	11.20			0.75	0.10	0.84		
103.80	115.00			1	13.10			0.75	0.10	0.98		
115.00	128.10			0	0.00			0.75	0.10	0.00		
128.10	135.00	**Culvert**		1	12.30			0.75	0.10	0.92		
135.00	147.30			1	5.20			0.75	0.10	0.39		
147.30	152.50			1	9.50			0.75	0.10	0.71		
152.50	162.00			1	15.00			0.75	0.10	1.13		
162.00	177.00			1	14.50			0.75	0.10	1.09		
177.00	191.50			1	8.50			0.75	0.10	0.64		
191.50	200.00			1	15.00			0.75	0.10	1.13		
200.00	215.00			1	13.00			0.75	0.10	0.98		
215.00	228.00			1	12.00			0.75	0.10	0.90		
228.00	240.00			1	4.50			0.75	0.10	0.34		
240.00	244.50								Sub Total	16.58		
									Total Executed Quantity	1096.72	8000.00	8774755.00
									Tender Quantity	1147.54		
Item no.06		Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications, and as per the directions of the Engineer-in-charge of the work										
		For Drain	Tonne		1013.14			0.075		76.47		
		For Culvert	Tonne		67.00			0.095		6.37		
									Total Executed Qty	82.84	91000.00	7538362.00
									Tender Quantity	84.27		
Item no.07		Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete and as per the directions of the Engineer-in-charge of the work										
		Kaveri Layout										
		Krishna Nivas House (W1309)										
		LHS										
		South to North										
			Sqm	1	2.50			0.75		1.88		
0.00	2.50			1	12.50			0.75		9.38		
2.50	15.00			1	3.40			0.75		2.55		
15.00	18.40			1	0.00			0.75		0.00		
18.40	24.40	**B S Slab**		1	10.60			0.75		7.95		
24.40	35.00			1	15.00			0.75		11.25		
35.00	50.00			1	14.10			0.75		10.58		
50.00	64.10			1	10.90			0.75		8.18		
64.10	75.00			1	0.00			0.75		0.00		
75.00	87.80	**B S Slab**		1	3.40			0.75		2.55		
87.80	91.20											
		RHS										
		North to South										
0.00	15.00	**B S Slab**		1	0.00			0.75		0.00		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
15.30	19.40	B S Slab		1	1.00			1.75		1.80		
19.40	28.25			1	8.80			1.75		8.60		
28.25	33.50	B S Slab		1	1.00			1.75		1.80		
33.50	42.50			1	9.00			1.75		8.75		
42.50	54.90	B S Slab		1	1.00			1.75		1.00		
54.90	65.70			1	10.80			1.75		8.00		
65.70	74.10	B S Slab		1	1.00			1.75		1.00		
74.10	85.00			1	10.90			1.75		8.88		
85.00	92.60			1	7.60			1.75		5.70		
		Joseph House Road (W1834)										
		RHS										
		West to East										
0.00	15.00			1	15.00			1.75		11.25		
15.00	30.00			1	15.00			1.75		11.25		
30.00	36.40			1	6.40			1.75		4.80		
36.40	48.10	B S Slab		1	1.00			1.75		1.00		
		LHS										
		West to East										
0.00	15.00			1	15.00			1.75		11.25		
15.00	27.20			1	12.20			1.75		9.15		
		1st Main Road (W1307)										
		LHS										
		North to South										
0.00	15.00			1	15.00			1.75		11.25		
15.00	21.30			1	6.30			1.75		4.75		
		Moto Works Opps. (W1239)										
		RHS										
		North to South										
0.00	15.00			1	15.00			1.75		11.25		
15.00	17.60			1	2.60			1.75		1.95		
17.60	23.40	Culvert		1	0.00			1.75		0.00		
23.40	30.00			1	6.60			1.75		4.95		
30.00	45.00			1	15.00			1.75		11.25		
45.00	55.20			1	10.20			1.75		7.65		
55.20	60.30	Culvert		1	0.00			1.75		0.00		
60.30	75.00			1	14.70			1.75		11.03		
75.00	86.30	B S Slab		1	0.00			1.75		0.00		
86.30	91.50	Culvert		1	0.00			1.75		0.00		
91.50	105.00			1	13.50			1.75		10.13		
105.00	120.00			1	15.00			1.75		11.25		
120.00	129.60			1	9.60			1.75		7.20		
		LHS										
		South to North										
0.00	15.00			1	15.00			1.75		11.25		
15.00	19.20			1	4.20			1.75		3.15		
19.20	25.50	B S Slab		1	0.00			1.75		0.00		
25.50	30.00			1	4.50			1.75		3.38		
30.00	45.00			1	15.00			1.75		11.25		
45.00	60.00			1	15.00			1.75		11.25		
60.00	75.00			1	15.00			1.75		11.25		
75.00	90.00			1	15.00			1.75		11.25		
90.00	105.00			1	15.00			1.75		11.25		
105.00	120.00			1	15.00			1.75		11.25		
120.00	125.70			1	5.70			1.75		4.28		
		Cross Road 1 (W0870)										
		East to West										
0.00	15.00			1	15.00			1.75		11.25		
15.00	26.10			1	11.10			1.75		8.33		
		Cross Road 2 (W0862)										
		East to West										
0.00	15.00			1	15.00			1.75		11.25		
15.00	30.00			1	15.00			1.75		11.25		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
30.00	33.00			1	3.00			0.75		2.25		
		Cross Road 3										
		East to West										
0.00	15.00			1	15.00			0.75		11.25		
15.00	30.00			1	15.00			0.75		11.25		
30.00	37.40			1	7.40			0.75		5.55		
		Cross Road (W1297)										
		LHS										
		South to North										
0.00	15.00			1	15.00			0.90		13.50		
15.00	30.00			1	15.00			0.90		13.50		
30.00	45.00			1	15.00			0.90		13.50		
45.00	60.00			1	15.00			0.90		13.50		
60.00	75.00			1	15.00			0.90		13.50		
75.00	90.00			1	15.00			0.90		13.50		
90.00	105.00			1	15.00			0.90		13.50		
105.00	106.60			1	1.60			0.90		1.44		
		RHS										
		North to South										
0.00	15.00			1	15.00			0.90		13.50		
15.00	30.00			1	15.00			0.90		13.50		
30.00	45.00			1	15.00			0.90		13.50		
45.00	60.00			1	15.00			0.90		13.50		
60.00	75.00			1	15.00			0.90		13.50		
75.00	90.00			1	15.00			0.90		13.50		
90.00	105.00			1	15.00			0.90		13.50		
105.00	107.20			1	2.20			0.90		1.98		
		Kuvempu Layout										
		2nd Main, 2nd Cross (W0616)										
		RHS										
		North to South										
0.00	15.00			1	15.00			0.75		11.25		
15.00	30.00			1	15.00			0.75		11.25		
		LHS										
		South to North										
0.00	15.00			1	15.00			0.75		11.25		
15.00	29.80			1	14.80			0.75		11.10		
		1st Main, 3rd Cross (W0989)										
		RHS										
		North to South										
0.00	15.00			1	15.00			0.75		11.25		
15.00	30.00			1	15.00			0.75		11.25		
30.00	45.00			1	15.00			0.75		11.25		
45.00	60.00			1	15.00			0.75		11.25		
60.00	61.80			1	1.80			0.75		1.35		
		LHS										
		South to North										
0.00	15.00			1	15.00			0.75		11.25		
15.00	30.00			1	15.00			0.75		11.25		
30.00	45.00			1	15.00			0.75		11.25		
45.00	60.00			1	15.00			0.75		11.25		
60.00	66.90			1	6.90			0.75		5.18		
		Dead END										
0.00	15.00			1	15.00			0.75		11.25		
15.00	16.80			1	1.80			0.75		1.35		
		1st Main, 2nd Cross (W0983)										
		RHS										
		North to South										
0.00	15.00			1	15.00			0.75		11.25		
15.00	30.00			1	15.00			0.75		11.25		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS	Amount in RS
0.00	45.00			1	45.00			0.75		11.25		
45.00	90.00			1	45.00			0.75		11.25		
90.00	95.00			1	5.00			0.75		2.33		
		LHS										
		South to North										
0.00	45.00			1	45.00			0.75		11.25		
45.00	90.00			1	45.00			0.75		11.25		
90.00	45.00			1	45.00			0.75		11.25		
45.00	90.00			1	45.00			0.75		11.25		
90.00	99.20			1	9.20			0.75		4.73		
		Dead END										
0.00	5.00			1	5.00			0.75		3.75		
		1st Main Rd Cross (WBT3)										
		RHS										
		North to South										
0.00	45.00			1	45.00			0.75		11.25		
45.00	90.00			1	45.00			0.75		11.25		
90.00	45.00			1	45.00			0.75		11.25		
45.00	45.80			1	0.80			0.75		0.60		
45.80	59.25			1	13.40			0.75		10.05		
		LHS										
		South to North										
0.00	5.00	BS Stair		1	0.00			0.75		0.00		
5.00	7.00	BS Stair		1	0.00			0.75		0.00		
7.00	47.80			1	34.80			0.75		11.10		
47.80	55.00	BS Stair		1	0.00			0.75		0.00		
55.00	59.25	BS Stair		1	0.00			0.75		0.00		
		Dead END										
0.00	7.30			1	7.30			0.75		5.48		
		1st Main Road (WBT2)										
		LHS										
		East To West										
0.00	15.00			1	15.00			0.75		11.25		
15.00	30.00			1	15.00			0.75		11.25		
30.00	34.95			1	4.95			0.75		4.95		
0.00	15.00			1	15.00			0.90		13.50		
15.00	30.00			1	15.00			0.90		13.50		
30.00	45.00			1	15.00			0.90		13.50		
45.00	53.30			1	8.30			0.90		7.47		
53.30	70.00	Road Break		1	0.00			0.90		0.00		
70.00	70.70	BS Stair		1	0.00			0.90		0.00		
70.70	85.00			1	14.30			0.90		12.87		
85.00	100.00			1	15.00			0.90		13.50		
100.00	115.00			1	15.00			0.90		13.50		
115.00	125.80			1	10.80			0.90		9.72		
		RHS										
		West To East										
0.00	15.00	BS Stair		1	0.00			0.90		0.00		
15.00	30.00	BS Stair		1	0.00			0.90		0.00		
30.00	45.00	BS Stair		1	0.00			0.90		0.00		
45.00	48.80	BS Stair		1	0.00			0.90		0.00		
48.80	63.80			1	15.00			0.90		13.50		
0.00	15.00			1	15.00			0.90		13.50		
15.00	30.00			1	15.00			0.90		13.50		
30.00	45.00			1	15.00			0.90		13.50		
45.00	60.00			1	15.00			0.90		13.50		
60.00	74.20			1	14.20			0.90		12.78		
		2Nd Cross Road (WBT3)										
		RHS										

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		North to South										
0.00	15.00			1	15.00			0.90		13.50		
15.00	20.20			1	5.20			0.90		4.68		
20.20	33.00	No Work		1	0.00			0.90		0.00		
33.00	45.00			1	12.00			0.90		10.80		
45.00	60.00			1	15.00			0.90		13.50		
60.00	68.40			1	8.40			0.90		7.56		
68.40	68.60			1	0.20			0.90		5.58		
68.60	84.00			1	10.40			0.90		9.36		
84.00	99.00			1	15.00			0.90		13.50		
99.00	114.00			1	15.00			0.90		13.50		
114.00	127.00			1	13.50			0.90		12.15		
127.00	138.50											
		LHS								13.50		
		South to North						0.90		2.34		
				1	15.00			0.90		0.00		
				1	2.60			0.90		4.23		
0.00	15.00			1	0.00			0.90		0.00		
15.00	17.90	BS Slab		1	4.70			0.90		9.36		
17.90	21.80			1	0.00			0.90		9.36		
21.80	26.80	BS Slab		1	10.40			0.90		11.52		
26.80	36.40			1	10.40			0.90		7.56		
36.40	46.80			1	12.80			0.90		0.00		
46.80	57.20			1	8.40			0.90		0.00		
57.20	70.00			1	0.00			0.90		3.87		
70.00	78.40	No Work		1	0.00			0.90		0.00		
78.40	82.80	BS Slab		1	4.30			0.90		8.28		
82.80	91.00			1	0.00			0.90		0.00		
91.00	95.80	BS Slab		1	9.20			0.90				
95.80	104.20			1	0.00							
104.20	113.40	BS Slab										
113.40	138.50											
		Connecting Road 1 (W0608)										
		RHS						0.75		11.25		
				1	15.00			0.75		0.60		
0.00	15.00			1	8.80							
15.00	25.80											
		LHS						0.75		11.25		
				1	15.00			0.75		7.80		
0.00	15.00			1	10.40							
15.00	25.40											
		Dead END (W0965)						0.75		11.25		
				1	15.00			0.75		2.03		
0.00	15.00			1	2.70							
15.00	17.70											
		Connecting Road 2										
		RHS						0.75		11.25		
				1	15.00			0.75		4.95		
0.00	15.00			1	6.60							
15.00	21.60											
		LHS						0.75		11.25		
				1	15.00			0.75		6.68		
0.00	15.00			1	8.90							
15.00	23.90											
		1st Main, 1st A Cross (W0975)										
				1	15.00			0.90		13.50		
0.00	15.00			1	5.50			0.90		4.95		
15.00	20.50			1	9.80			0.90		8.82		
20.50	30.30											
		2nd Main Road (W0616)										
		RHS										
		North to South										
0.00	15.00			1	15.00			0.75		11.25		
15.00	30.00			1	15.00			0.75		11.25		
30.00	45.00			1	15.00			0.75		11.25		
45.00	60.00			1	15.00			0.75		11.25		
60.00	74.40			1	14.40			0.75		10.80		
0.00	10.70			1	10.70			0.90		9.63		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
0.00	25.00	BS Slab		1	0.00			0.90		0.00		
25.00	32.50	BS Slab		1	0.00			0.90		0.00		
32.50	45.00			1	12.50			0.90		11.25		
45.00	60.00			1	15.00			0.90		13.50		
60.00	75.00			1	15.00			0.90		13.50		
75.00	90.00			1	15.00			0.90		13.50		
90.00	105.00			1	15.00			0.90		13.50		
105.00	120.00			1	15.00			0.90		13.50		
120.00	121.20			1	1.20			0.90		1.08		
		LHS										
		South to North										
0.00	14.20			1	14.20			0.75		10.65		
		2nd A Main Road (W0616)										
		RHS										
0.00	15.00			1	15.00			0.90		13.50		
15.00	26.50			1	11.50			0.90		10.35		
26.50	35.70	BS Slab		1	0.00			0.90		0.00		
35.70	46.40	BS Slab		1	0.00			0.90		0.00		
46.40	58.00			1	11.60			0.90		10.44		
58.00	70.60			1	12.60			0.90		11.34		
70.60	83.30	BS Slab		1	0.00			0.90		0.00		
		18th A Cross Road (W0618)										
		LHS										
		South to North										
0.00	15.00			1	15.00			0.75		11.25		
15.00	27.20			1	12.20			0.75		9.15		
27.20	36.90	BS Slab		1	0.00			0.75		0.00		
36.90	44.40			1	7.50			0.75		5.63		
44.40	50.00	BS Slab		1	0.00			0.75		0.00		
50.00	65.00	BS Slab		1	0.00			0.75		0.00		
65.00	75.00	BS Slab		1	0.00			0.75		0.00		
0.00	15.00			1	15.00			0.90		13.50		
15.00	25.10			1	10.10			0.90		9.09		
		Munikempanna Layout										
		1st Cross Road (W0973)										
		RHS										
		North to South										
0.00	15.00			1	15.00			0.75		11.25		
15.00	30.00			1	15.00			0.75		11.25		
30.00	45.00			1	15.00			0.75		11.25		
45.00	60.00			1	15.00			0.75		11.25		
60.00	75.00			1	15.00			0.75		11.25		
75.00	85.60			1	10.60			0.75		7.95		
		Dead END (W0965)										
0.00	15.00			1	15.00			0.75		11.25		
15.00	30.00			1	15.00			0.75		11.25		
30.00	35.70			1	5.70			0.75		4.28		
		Dasarahalli Main Road (M0022)										
		RHS										
0.00	15.00			1	15.00			0.90		13.50		
15.00	30.00			1	15.00			0.90		13.50		
30.00	45.00			1	15.00			0.90		13.50		
45.00	59.10			1	14.10			0.90		12.69		
		2nd Cross (W0983) Dead End										
0.00	12.90			1	12.90			0.90		11.61		
		Mariyanna Palya										
		St. Anthony Church Road (I0794)										
0.00	15.00			1	15.00			1.20		18.00		
15.00	30.00			1	15.00			1.20		18.00		

BBMP (Ward No 06)

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
30.00	37.50	Culvert		0	0.00			1.20		0.00		
37.50	50.00			1	12.50			1.20		15.00		
50.00	65.00			1	15.00			1.20		18.00		
65.00	80.00			1	15.00			1.20		18.00		
80.00	94.80			1	14.80			1.20		17.76		
94.80	103.80	Culvert		0	0.00			1.20		0.00		
103.80	115.00			1	11.20			1.20		13.44		
115.00	128.10			1	13.10			1.20		15.72		
128.10	135.00	Culvert		0	0.00			1.20		0.00		
135.00	147.30	BS Slab		1	0.00			1.20		0.00		
147.30	152.50			1	5.20			1.20		6.24		
152.50	162.00			1	9.50			1.20		11.40		
162.00	177.00			1	15.00			1.20		18.00		
177.00	191.50			1	14.50			1.20		17.40		
191.50	200.00	BS Slab		1	0.00			1.20		0.00		
200.00	215.00	BS Slab		1	0.00			1.20		0.00		
215.00	228.00	BS Slab		1	0.00			1.20		0.00		
228.00	240.00	BS Slab		1	0.00			1.20		0.00		
240.00	244.50	BS Slab		1	0.00			1.20		0.00		
		Dasarahalli Circle	Sqm									
0.00	15.00			1	15.00	0.90	0.90	0.90		13.50		
15.00	27.70			1	12.70	0.90	0.90	0.90		11.43		
27.70	42.70			1	15.00	1.20	1.20	1.20		18.00		
42.70	57.70			1	15.00	1.20	1.20	1.20		18.00		
57.70	72.70			1	15.00	1.20	1.20	1.20		18.00		
72.70	87.70			1	15.00	1.20	1.20	1.20		18.00		
87.70	102.70			1	15.00	1.20	1.20	1.20		18.00		
102.70	117.70			1	15.00	1.20	1.20	1.20		18.00		
117.70	132.70			1	15.00	1.20	1.20	1.20		18.00		
132.70	147.70			1	15.00	1.20	1.20	1.20		18.00		
147.70	155.00			1	7.30	1.20	1.20	1.20		8.76		
		Bhuvaneshwari Nagar										
		20th R Cross Road (W0961)										
		RHS										
0.00	15.00			1	15.00	0.75	0.75	0.75		11.25		
15.00	30.00			1	15.00	0.75	0.75	0.75		11.25		
30.00	45.00			1	15.00	0.75	0.75	0.75		11.25		
45.00	47.50			1	2.50	0.75	0.75	0.75		1.88		
47.50	53.00	Culvert		1	0.00	0.75	0.75	0.75		0.00		
53.00	65.00			1	12.00	0.75	0.75	0.75		9.00		
65.00	80.00			1	15.00	0.75	0.75	0.75		11.25		
80.00	95.00			1	15.00	0.75	0.75	0.75		11.25		
95.00	99.70			1	4.70	0.75	0.75	0.75		3.53		
99.70	112.00			1	12.30	0.75	0.75	0.75		9.23		
112.00	125.00			1	13.00	0.75	0.75	0.75		9.75		
125.00	140.00			1	15.00	0.75	0.75	0.75		11.25		
140.00	155.00			1	15.00	0.75	0.75	0.75		11.25		
155.00	159.90			1	4.90	0.75	0.75	0.75		3.68		
		LHS										
0.00	15.00			1	15.00	0.75	0.75	0.75		11.25		
15.00	30.00			1	15.00	0.75	0.75	0.75		11.25		
30.00	40.50			1	10.50	0.75	0.75	0.75		7.88		
40.50	55.00			1	14.50	0.75	0.75	0.75		10.88		
55.00	65.50			1	10.50	0.75	0.75	0.75		7.88		
65.50	70.70	Culvert		1	0.00	0.75	0.75	0.75		0.00		
70.70	85.00			1	14.30	0.75	0.75	0.75		10.73		
85.00	100.00			1	15.00	0.75	0.75	0.75		11.25		
100.00	111.80			1	11.80	0.75	0.75	0.75		8.85		
111.80	116.90	No Work		1	0.00	0.75	0.75	0.75		0.00		
116.90	130.00			1	13.10	0.75	0.75	0.75		9.83		
130.00	144.50			1	14.50	0.75	0.75	0.75		10.88		
144.50	148.70	No Work		1	0.00	0.75	0.75	0.75		0.00		
148.70	164.30			1	15.60	0.75	0.75	0.75		11.70		
									Total Executed Quantity	**2389.79**	**1950.00**	**4660081.00**
									Tender Quantity	**2662.35**		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
Item no.08		Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift, transportation etc ,complete. and as per the directions of the Engineer-in-charge of the work										
		Kuvempu Layout										
		2nd Main Road (W0616) CD1	Sqm	1	5.75			1.20		6.90		
		1st Main 1st Cross Road (W0973) CD2		1	8.20			1.20		9.84		
		CD3		1	6.20			1.20		7.44		
		CD4		1	10.40			1.20		12.48		
		Dead End Road (W0965) CD5		1	8.10			1.20		9.72		
		21st Cross Road (W0969) CD6		1	7.40			1.20		8.88		
		Dasarahalli Main Road (M0022) CD7		1	7.00			1.20		8.40		
		1st Main Road (W0612) CD8		1	7.70			1.20		9.24		
		CD9		1	4.70			1.20		5.64		
		CD10		1	9.50			1.20		11.40		
		20th R Cross Road (W0961) CD11		1	7.00			1.20		8.40		
		18th A Cross Road (W0618) CD12		1	6.30			1.20		7.56		
		1st Main Road (W0612) CD13		1	5.50			1.20		6.60		
		Mariyanna Palya										
		Joseph House Road (W0884) CD14		1	5.60			1.50		8.40		
		Moto Works Oppo. (W1299) CD15		1	6.10			1.50		9.15		
		CD16		1	5.80			1.50		8.70		
		CD17		1	5.10			1.50		7.65		
		CD18		1	5.20			1.50		7.80		
		Cross Road	Sqm	1	5.80	1.50	1.50	1.50		8.70		
									Total Executed Quantity	**162.90**	**6000.00**	**977400.00**
									Tender Quantity	**202.92**		
Item no.09		Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding, curing, hire charges of machineries etc., complete as per specifications and directions of the Engineer in charge.										
		Mariyanna Palya										
		St. Anthony Church Road (I0794)										
0.00	15.00		Sqm	2	15.00				0.20	6.00		
15.00	30.00			2	15.00				0.20	6.00		
30.00	37.50	Culvert		0	0.00				0.20	0.00		
37.50	50.00			2	12.50				0.20	5.00		
50.00	65.00			2	15.00				0.20	6.00		
65.00	80.00			2	15.00				0.20	6.00		
80.00	94.80			2	14.80				0.20	5.92		
94.80	103.80	Culvert		0	0.00				0.20	0.00		
103.80	115.00			2	11.20				0.20	4.48		
115.00	128.10			2	13.10				0.20	5.24		
128.10	135.00	Culvert		0	0.00				0.20	0.00		
135.00	147.30	0.00		2	12.30				0.20	4.92		
147.30	152.50			2	5.20				0.20	2.08		
152.50	162.00			2	9.50				0.20	3.80		
162.00	177.00			2	15.00				0.20	6.00		
177.00	191.50			2	14.50				0.20	5.80		
191.50	200.00	No work		2	0.00				0.20	0.00		
200.00	215.00	No work		2	0.00				0.20	0.00		
215.00	228.00	No work		2	0.00				0.20	0.00		
228.00	240.00	No work		2	0.00				0.20	0.00		
240.00	244.50	No work		2	0.00				0.20	0.00		
									Total Executed Quantity	**67.24**	**1100.00**	**73964.00**
									Tender Quantity	**100.80**		
Item no.10		Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete. and as per the directions of the Engineer-in-charge of the work										
		Mariyanna Palya										

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		1st Main Road (W1307)										
		RHS										
0.00	15.00		m	1	15.00					15.00		
15.00	21.30			1	6.30					6.30		
		Moto Works Oppo (W1299)										
		LHS										
0.00	15.00			1	15.00					15.00		
15.00	30.00			1	15.00					15.00		
30.00	45.00			1	15.00					15.00		
45.00	60.00			1	15.00					15.00		
60.00	75.00			1	15.00					15.00		
75.00	90.00			1	15.00					15.00		
90.00	105.00			1	15.00					15.00		
105.00	120.00			1	15.00					15.00		
120.00	125.90			1	5.90					5.90		
		RHS										
0.00	15.00			1	15.00					15.00		
15.00	17.60			1	2.60					2.60		
17.60	23.40	Culvert		1	0.00					0.00		
23.40	35.00			1	11.60					11.60		
35.00	50.00			1	15.00					15.00		
50.00	55.20			1	5.20					5.20		
55.20	60.30	Culvert		1	0.00					0.00		
60.30	74.00			1	13.70					13.70		
74.00	77.30	Ramp		1	0.00					0.00		
77.30	86.30			1	9.00					9.00		
86.30	91.50	Culvert		1	0.00					0.00		
91.50	105.00			1	13.50					13.50		
105.00	117.20			1	12.20					12.20		
117.20	120.40	Ramp		1	0.00					0.00		
120.40	131.50			1	11.10					11.10		
		Kuvempu Layout										
		2nd Main road 2nd Cross Road (W0616)										
		LHS										
0.00	15.00			1	15.00					15.00		
15.00	29.80			1	14.80					14.80		
		RHS										
0.00	15.00			1	15.00					15.00		
15.00	30.00			1	15.00					15.00		
		1st main 2nd Cross Road (W0083)										
		LHS										
0.00	15.00			1	15.00					15.00		
15.00	30.00			1	15.00					15.00		
30.00	45.00			1	15.00					15.00		
45.00	63.10			1	18.10					18.10		
		RHS										
0.00	15.00			1	15.00					15.00		
15.00	30.00			1	15.00					15.00		
30.00	45.00			1	15.00					15.00		
45.00	60.00			1	15.00					15.00		
60.00	66.30			1	6.30					6.30		
		1st main 1st Cross Road (W0073)										
		RHS										
0.00	15.00			1	15.00					15.00		
15.00	24.60			1	9.60					9.60		
24.60	27.80	Ramp		1	0.00					0.00		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
27.80	45.00			1	17.20					17.20		
45.00	58.20			1	13.20					13.20		
		LHS										
0.00	15.00	Ramp		1	0.00					0.00		
15.00	25.60	Ramp		1	0.00					0.00		
25.60	41.40			1	15.80					15.80		
41.40	60.20			1	18.80					18.80		
		1st main Road (W0612)										
		RHS										
0.00	15.00			1	15.00					15.00		
15.00	30.00			1	15.00					15.00		
30.00	40.20			1	10.20					10.20		
0.00	15.00			1	15.00					15.00		
15.00	30.00			1	15.00					15.00		
30.00	45.00			1	15.00					15.00		
45.00	54.30			1	9.30					9.30		
54.30	62.10	Road Break		0	0.00					0.00		
62.10	77.10			1	15.00					15.00		
77.10	92.10			1	15.00					15.00		
92.10	107.10			1	15.00					15.00		
107.10	122.10			1	15.00					15.00		
122.10	126.80			1	4.70					4.70		
		LHS										
0.00	15.00	No work		1	0.00					0.00		
15.00	30.00	No work		1	0.00					0.00		
30.00	45.00	No work		1	0.00					0.00		
45.00	50.00	No work		1	0.00					0.00		
50.00	65.00			1	15.00					15.00		
65.00	80.00			1	15.00					15.00		
80.00	95.00			1	15.00					15.00		
95.00	110.00			1	15.00					15.00		
110.00	125.30			1	15.30					15.30		
0.00	15.00			1	15.00					15.00		
15.00	30.00			1	15.00					15.00		
30.00	45.40			1	15.40					15.40		
45.40	50.30	No Work		1	0.00					0.00		
50.30	65.30			1	15.00					15.00		
65.30	74.80			1	9.50					9.50		
		1st Main 3rd Cross Road (W0989)										
		LHS										
0.00	15.00			1	15.00					15.00		
15.00	30.00			1	15.00					15.00		
30.00	45.00			1	15.00					15.00		
45.00	61.80			1	16.80					16.80		
		2nd Main Road (W0616)										
		LHS										
0.00	15.00			1	15.00					15.00		
15.00	21.20			1	6.20					6.20		
		RHS										
0.00	15.00			1	15.00					15.00		
15.00	30.00			1	15.00					15.00		
30.00	45.00			1	15.00					15.00		
45.00	60.00			1	15.00					15.00		
60.00	74.00			1	14.00					14.00		
0.00	15.00			1	15.00					15.00		
15.00	30.00			1	15.00					15.00		
30.00	45.00			1	15.00					15.00		
45.00	60.00			1	15.00					15.00		
60.00	75.00			1	15.00					15.00		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
										15.00		
				1	15.00					15.00		
				1	15.00					15.80		
				1	15.80							
75.00	90.00											
90.00	105.00									15.00		
105.00	120.80									5.20		
		21th Cross Road (W0969)								0.00		
		RHS		1	15.00					15.00		
				1	5.20					15.00		
				0	0.00					5.40		
0.00	15.00			1	15.00					0.00		
15.00	20.20	No Work		1	15.00					15.00		
20.20	33.00			1	5.40					15.00		
33.00	48.00			0	6.20					15.00		
48.00	63.00			1	15.00					9.90		
63.00	68.40	No Work		1	15.00							
68.40	74.60			1	15.00					13.60		
74.60	89.60			1	9.90							
89.60	104.60											
104.60	119.60											
119.60	129.50											
		LHS		1	13.60							
0.00	13.60									15.00		
		Connecting Road-1 (W0608)								10.40		
		LHS		1	15.00							
				1	10.40							
0.00	15.00									15.00		
15.00	25.40									8.80		
		RHS		1	15.00							
				1	8.80							
0.00	15.00											
15.00	23.80											
										15.00		
		Dead End Road (W0965)								2.00		
		LHS		1	15.00							
				1	2.00							
0.00	15.00											
15.00	17.00											
		Connecting Road -2								15.00		
		LHS		1	15.00					5.50		
				1	5.50							
0.00	15.00											
15.00	20.50									15.00		
		RHS		1	15.00					8.90		
				1	8.90							
0.00	15.00											
15.00	23.90											
		1st A Cross Road (W0975)								15.00		
		LHS		1	15.00					15.30		
0.00	15.00			1	15.30							
15.00	30.30											
										15.00		
		2nd Main Road (W0616)		1	15.00					9.80		
0.00	15.00			1	9.80							
15.00	24.80											
		18th A Cross Road (W0618)										
		LHS		1	15.00					15.00		
0.00	15.00			1	10.00					10.00		
15.00	25.00			1	0.00					0.00		
25.00	34.80	Ramp		1	15.00					15.00		
34.80	49.80			1	4.20					4.20		
49.80	54.00			1	0.00					0.00		
54.00	69.00	Ramp		1	0.00					0.00		
69.00	72.30	Ramp										
		2nd A Cross Road (W0616)										
		LHS										
0.00	7.40	Ramp		1	0.00					0.00		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
7.40	25.10			1	17.70					17.70		
25.10	40.50	Ramp		1	0.00					0.00		
40.50	55.50			1	15.00					15.00		
55.50	69.90			1	14.40					14.40		
69.90	83.10	No Work		1	0.00					0.00		
		2nd Main Road (W0616)										
		LHS										
0.00	8.00			1	8.00					8.00		
8.00	9.80	No Work		0	0.00					0.00		
9.80	24.80			1	15.00					15.00		
24.80	36.10			1	11.30					11.30		
		Mariyannana Palya										
		1st Main Road (W0973)										
		LHS										
0.00	15.00			1	15.00					15.00		
15.00	29.80			1	14.80					14.80		
29.80	37.40	Culvert		1	0.00					0.00		
37.40	52.40			1	15.00					15.00		
52.40	67.40			1	15.00					15.00		
67.40	82.40			1	15.00					15.00		
82.40	94.80			1	12.40					12.40		
94.80	103.80	Culvert		1	0.00					0.00		
103.80	118.80			1	15.00					15.00		
118.80	128.00			1	9.20					9.20		
128.00	135.00	Culvert		1	0.00					0.00		
135.00	147.40			1	12.40					12.40		
147.40	152.60	No Work		1	0.00					0.00		
152.60	161.50			1	8.90					8.90		
161.50	177.00	No Work		1	0.00					0.00		
177.00	191.70			1	14.70					14.70		
		1st Main 3rd Cross Road										
		(South to North)	m									
0.00	7.20			1	7.20					7.20		
7.20	13.40	No Work		1	0.00					0.00		
13.40	19.00			1	5.60					5.60		
19.00	20.90	No Work		1	0.00					0.00		
20.90	30.40			1	9.50					9.50		
		Kailash House Road										
		(East to West)										
		LHS										
0.00	15.00			1	15.00					15.00		
15.00	30.00			1	15.00					15.00		
30.00	33.30			1	3.30					3.30		
33.30	37.00	No Work		1	0.00					0.00		
37.00	43.20			1	6.20					6.20		
43.20	46.50	No Work		1	0.00					0.00		
46.50	51.50			1	5.00					5.00		
									Total Length	**1746.70**		
			Nos						**Length/0.45**	**3882.00**		
									Total Executed Quantity	**3882.00**	**440.00**	**1708080.00**
									Tender Quantity	**5656.00**		
Item no.11		Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour Complete as per specifications and directions of the Engineer in charge.										
		Mariyanna Palya										
		1st Main Road (W1307)										
		RHS										
0.00	15.00		Sqm	1	15.00				0.40	6.00		
15.00	21.30			1	6.30				0.40	2.52		
		Moto Works Oppo. (W1299)										
		LHS										
0.00	15.00			1	15.00				0.40	6.00		
15.00	30.00			1	15.00				0.40	6.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
30.00	45.00			1	15.00				0.40	6.00		
45.00	60.00			1	15.00				0.40	6.00		
60.00	75.00			1	15.00				0.40	6.00		
75.00	90.00			1	15.00				0.40	6.00		
90.00	105.00			1	15.00				0.40	6.00		
105.00	120.00			1	15.00				0.40	6.00		
120.00	125.90			1	5.90				0.40	2.36		
		RHS										
0.00	15.00			1	15.00				0.40	6.00		
15.00	17.60			1	2.60				0.40	1.04		
17.60	23.40	Culvert		1	0.00				0.40	0.00		
23.40	35.00			1	11.60				0.40	4.64		
35.00	50.00			1	15.00				0.40	6.00		
50.00	55.20			1	5.20				0.40	2.08		
55.20	60.30	Culvert		1	0.00				0.40	0.00		
60.30	74.00			1	13.70				0.40	5.48		
74.00	77.30	Ramp		1	0.00				0.40	0.00		
77.30	86.30			1	9.00				0.40	3.60		
86.30	91.50	Culvert		1	0.00				0.40	0.00		
91.50	105.00			1	13.50				0.40	5.40		
105.00	117.20			1	12.20				0.40	4.88		
117.20	120.40	Ramp		1	0.00				0.40	0.00		
120.40	131.50			1	11.10				0.40	4.44		
		Kuvempu Layout										
		2nd Main road 2nd Cross Road (W0616)										
		LHS										
0.00	15.00			1	15.00				0.40	6.00		
15.00	29.80			1	14.80				0.40	5.92		
		RHS										
0.00	15.00			1	15.00				0.40	6.00		
15.00	30.00			1	15.00				0.40	6.00		
		1st main 2nd Cross Road (W0983)										
		LHS										
0.00	15.00			1	15.00				0.40	6.00		
15.00	30.00			1	15.00				0.40	6.00		
30.00	45.00			1	15.00				0.40	6.00		
45.00	63.10			1	18.10				0.40	7.24		
		RHS										
0.00	15.00			1	15.00				0.40	6.00		
15.00	30.00			1	15.00				0.40	6.00		
30.00	45.00			1	15.00				0.40	6.00		
45.00	60.00			1	15.00				0.40	6.00		
60.00	66.30			1	6.30				0.40	2.52		
		1st main 1st Cross Road (W0973)										
		RHS										
0.00	15.00			1	15.00				0.40	6.00		
15.00	24.60			1	9.60				0.40	3.84		
24.60	27.80	Ramp		1	0.00				0.40	0.00		
27.80	45.00			1	17.20				0.40	6.88		
45.00	58.20			1	13.20				0.40	5.28		
		LHS										
0.00	15.00	Ramp		1	0.00				0.40	0.00		
15.00	25.60	Ramp		1	0.00				0.40	0.00		
25.60	41.40			1	15.80				0.40	6.32		
41.40	60.20			1	18.80				0.40	7.52		
		1st main Road (W0612)										
		RHS										
0.00	15.00			1	15.00				0.40	6.00		
15.00	30.00			1	15.00				0.40	6.00		
30.00	40.20			1	10.20				0.40	4.08		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
0.00	15.00			01	25.00				0.40	2.00		
15.00	30.00			01	25.00				0.40	2.00		
30.00	45.00			01	25.00				0.40	2.00		
45.00	56.30			01	9.30				0.40	3.72		
56.30	65.10	Road Break.										
65.10	77.10			01	25.00				0.40	2.00		
77.10	87.10			01	25.00				0.40	2.00		
87.10	97.10			01	25.00				0.40	2.00		
97.10	102.10			01	25.00				0.40	2.00		
102.10	126.80			01	4.70				0.40	1.88		
		LHS										
0.00	15.00	No work.		01	7.00				0.40	2.00		
15.00	30.00	No work.		01	7.00				0.40	2.00		
30.00	45.00	No work.		01	7.00				0.40	2.00		
45.00	51.00	No work.		01	7.00				0.40	2.00		
51.00	66.00			01	25.00				0.40	2.00		
66.00	81.00			01	25.00				0.40	2.00		
81.00	96.00			01	25.00				0.40	2.00		
96.00	111.00			01	25.00				0.40	2.00		
111.00	126.30			01	25.30				0.40	2.12		
0.00	15.00			01	25.00				0.40	2.00		
15.00	30.00			01	25.00				0.40	2.00		
30.00	45.40			01	25.40				0.40	2.16		
45.40	51.30	No Work.		01	7.00				0.40	2.00		
51.30	66.30			01	25.00				0.40	2.00		
66.30	76.80			01	9.50				0.40	3.80		
		1st Main Int. Cross Road (M1585)										
		LHS										
0.00	15.00			01	25.00				0.40	2.00		
15.00	30.00			01	25.00				0.40	2.00		
30.00	45.00			01	25.00				0.40	2.00		
45.00	61.80			01	16.80				0.40	2.72		
		2nd Main Road (M1615)										
		LHS										
0.00	15.00			01	25.00				0.40	2.00		
15.00	21.20			01	6.20				0.40	2.48		
		RHS										
0.00	15.00			01	15.00				0.40	2.00		
15.00	30.00			01	15.00				0.40	2.00		
30.00	45.00			01	15.00				0.40	2.00		
45.00	60.00			01	15.00				0.40	2.00		
60.00	74.00			01	14.00				0.40	5.60		
0.00	15.00			01	15.00				0.40	2.00		
15.00	30.00			01	15.00				0.40	2.00		
30.00	45.00			01	15.00				0.40	2.00		
45.00	60.00			01	15.00				0.40	2.00		
60.00	75.00			01	15.00				0.40	2.00		
75.00	90.00			01	15.00				0.40	2.00		
90.00	105.00			01	15.00				0.40	2.00		
105.00	120.80			01	15.80				0.40	2.32		
		2nd Cross Road (M1693)										
		RHS										
0.00	15.00			01	15.00				0.40	2.00		
15.00	20.20			01	5.20				0.40	2.08		
20.20	35.00	No Work.										
35.00	50.00			01	15.00				0.40	2.00		
50.00	65.00			01	15.00				0.40	2.00		
65.00	70.40			01	5.40				0.40	2.16		
70.40	74.00	No Work.										
74.00	89.00			01	15.00				0.40	6.00		
89.00	104.00			01	15.00				0.40	6.00		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	B1	Breadth B2	Avg B	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
[illegible]	119.60			1	15.99				0.49	6.99		
119.60	129.50			1	9.99				0.49	4.96		
		LHS										
0.00	13.60			1	13.60				0.49	5.44		
		Connecting Road-1 (3/0608)										
		LHS										
0.00	15.00			1	15.00				0.49	6.99		
15.00	25.40			1	10.40				0.49	4.16		
		RHS										
0.00	15.00			1	15.00				0.49	6.99		
15.00	23.80			1	8.80				0.49	3.52		
		Dead End Road (3/0965)										
		LHS										
0.00	15.00			1	15.00				0.49	6.99		
15.00	17.00			1	2.00				0.49	0.80		
		Connecting Road-2										
		LHS										
0.00	15.00			1	15.00				0.49	6.99		
15.00	20.50			1	5.50				0.49	2.20		
		RHS										
0.00	15.00			1	15.00				0.49	6.99		
15.00	23.90			1	8.90				0.49	3.56		
		1st Cross Road (3/0975)										
		LHS										
0.00	15.00			1	15.00				0.49	6.99		
15.00	30.30			1	15.30				0.49	6.12		
		2nd Main Road (3/0616)										
0.00	15.00			1	15.00				0.49	6.99		
15.00	24.80			1	9.80				0.49	3.92		
		18th Cross Road (3/0618)										
		LHS										
0.00	15.00			1	15.00				0.49	6.99		
15.00	25.00			1	19.00				0.49	4.99		
25.00	34.80	Ramp		1	9.00				0.49	9.99		
34.80	40.80			1	15.00				0.49	6.99		
40.80	54.00			1	4.20				0.49	1.68		
54.00	60.00	Ramp		1	9.00				0.49	9.99		
60.00	72.30	Ramp		1	9.00				0.49	9.99		
		2nd Cross Road (3/0616)										
		LHS										
0.00	7.40	Ramp		1	9.00				0.49	9.99		
7.40	25.10			1	17.70				0.49	7.98		
25.10	40.50	Ramp		1	9.00				0.49	9.99		
40.50	55.50			1	15.00				0.49	6.99		
55.50	69.90			1	14.40				0.49	5.76		
69.90	83.10	No Work		1	9.00				0.49	9.99		
		2nd Main Road (3/0616)										
		LHS										
0.00	8.00			1	8.00				0.49	3.29		
8.00	9.80	No Work		0	9.00				0.49	9.99		
9.80	24.80			1	15.00				0.49	6.99		
24.80	36.10			1	11.30				0.49	4.52		
		Mariyannana Palya										
		1st Main Road (3/0973)										
		LHS										
0.00	15.00			1	15.00				0.49	6.99		
15.00	29.80			1	14.80				0.49	5.92		
29.80	37.40	Culvert		1	9.00				0.49	9.99		
37.40	52.40			1	15.00				0.49	6.99		
52.40	67.40			1	15.00				0.49	6.99		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
0.00	82.40			1	15.00				0.40	6.00		
82.40	94.80			1	12.40				0.40	4.96		
94.80	113.80	Culvert		1	0.00				0.40	0.00		
113.80	128.80			1	15.00				0.40	6.00		
128.80	138.00			1	9.20				0.40	3.68		
138.00	155.00	Culvert		1	0.00				0.40	0.00		
155.00	167.40			1	12.40				0.40	4.96		
167.40	182.60	No Work		1	0.00				0.40	0.00		
182.60	191.50			1	8.90				0.40	3.56		
191.50	197.00	No Work		1	0.00				0.40	0.00		
197.00	211.70			1	14.70				0.40	5.88		
		1st Main 3rd Cross Road (South to North)	Sum									
0.00	7.20			1	7.20				0.40	2.88		
7.20	13.40	No Work		1	0.00				0.40	0.00		
13.40	19.00			1	5.60				0.40	2.24		
19.00	21.90	No Work		1	0.00				0.40	0.00		
21.90	30.40			1	9.50				0.40	3.80		
		Kailash House Road (East to West) LHS										
0.00	15.00			1	15.00				0.40	6.00		
15.00	30.00			1	15.00				0.40	6.00		
30.00	33.30			1	3.30				0.40	1.32		
33.30	37.00	No Work		1	0.00				0.40	0.00		
37.00	43.20			1	6.20				0.40	2.48		
43.20	46.50	No Work		1	0.00				0.40	0.00		
46.50	51.50			1	5.00				0.40	2.00		
								Total Executed Quantity		698.68	85.00	59388.00
								Tender Quantity		1018.00		
Item no.12		Excavation for roadwork in all types of soil by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and complete as per specifications and directions of the Engineer in charge.										
		For Asphalt Road										
		Kuvempu Layout										
		2nd Main Road 1st Cross Road (W2977)										
0.00	15.00		Cum	1	15.00	7.50	6.65	7.08	0.35	37.14		
15.00	23.80			1	8.80	6.65	6.65	6.65	0.35	20.48		
23.80	34.40	No work		1	0.00	0.00	0.00	0.00	0.35	0.00		
34.40	45.00			1	10.60	6.45	5.50	5.98	0.35	22.17		
45.00	57.90			1	12.90	5.60	6.25	5.93	0.35	26.75		
		2nd Main Road 2nd Cross Road (W9616)										
0.00	15.00			1	15.00	4.90	5.20	5.05	0.35	26.51		
15.00	29.80			1	14.80	5.20	5.60	5.40	0.35	27.97		
		1st Main Road 2nd Cross Road (W9983)										
0.00	15.00			1	15.00	6.40	6.20	6.30	0.35	33.08		
15.00	30.00			1	15.00	6.20	6.30	6.25	0.35	32.81		
30.00	45.00			1	15.00	6.30	6.40	6.35	0.35	33.34		
45.00	62.50			1	17.50	6.40	5.45	5.93	0.35	36.29		
		1st Main Road 1st Cross Road (W2973)										
0.00	15.00			1	15.00	6.40	6.20	6.30	0.35	33.08		
15.00	30.00			1	15.00	6.20	6.30	6.25	0.35	32.81		
30.00	45.00			1	15.00	6.30	6.40	6.35	0.35	33.34		
45.00	58.20			1	13.20	6.40	5.45	5.93	0.35	27.37		
		1st Main Road (W9612)										
0.00	15.00			1	15.00	5.25	5.35	5.30	0.35	27.83		
15.00	30.00			1	15.00	5.35	6.60	5.98	0.35	31.37		
30.00	45.00			1	15.00	6.60	6.20	6.40	0.35	33.60		
45.00	60.00			1	15.00	6.20	6.05	6.13	0.35	32.16		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
75.00	90.00			1	15.00	6.05	5.70	5.88	0.35	30.84		
90.00	105.00			1	15.00	5.70	5.90	5.80	0.35	30.45		
105.00	111.60			1	5.60	6.00	7.50	6.75	0.35	13.23		
111.60	121.00			1	9.40	7.50	7.30	7.40	0.35	24.35		
121.00	136.00			1	15.00	7.30	7.30	7.30	0.35	38.33		
136.00	140.00			1	4.00	7.30	8.20	7.75	0.35	10.85		
140.00	142.40			1	2.40	8.20	12.20	10.20	0.35	8.57		
142.40	151.00			1	8.60	12.20	12.30	12.25	0.35	36.87		
151.00	162.20			1	11.20	11.10	8.20	9.65	0.35	37.83		
162.20	176.00			1	13.80	8.20	8.70	8.45	0.35	40.81		
176.00	181.20			1	5.20	8.70	5.80	7.25	0.35	13.20		
181.20	196.00			1	14.80	5.80	6.15	5.98	0.35	30.95		
196.00	211.00			1	15.00	6.15	6.20	6.18	0.35	32.42		
211.00	217.40			1	6.40	6.20	6.50	6.35	0.35	14.22		
217.40	221.10			1	3.70	6.50	3.70	5.10	0.35	6.60		
221.10	223.50			1	2.40	3.70	1.60	2.65	0.35	2.23		
		1st Main 3rd Cross (W0989)										
0.00	15.00			1	15.00	5.65	5.60	5.63	0.35	29.53		
15.00	30.00			1	15.00	5.60	5.65	5.63	0.35	29.53		
30.00	45.00			1	15.00	5.65	5.45	5.55	0.35	29.14		
45.00	61.20			1	16.20	5.45	5.20	5.33	0.35	30.19		
		2nd Main Road (W0616)										
0.00	1.30			1	1.30	4.45	4.45	4.45	0.35	2.02		
15.00	16.70			1	1.70	6.60	6.85	6.73	0.35	4.00		
16.70	18.00	No Work		1	0.00	0.00	0.00	0.00	0.35	0.00		
18.00	30.00			1	12.00	5.20	5.40	5.30	0.35	22.26		
30.00	45.00			1	15.00	5.40	5.60	5.50	0.35	28.88		
45.00	60.00			1	15.00	5.60	5.50	5.55	0.35	29.14		
60.00	75.00			1	15.00	5.50	5.30	5.40	0.35	28.35		
75.00	90.00			1	15.00	5.30	5.65	5.48	0.35	28.74		
90.00	105.00			1	15.00	5.50	5.30	5.40	0.35	28.35		
105.00	120.00			1	15.00	5.30	6.70	6.00	0.35	31.50		
120.00	135.00			1	15.00	6.70	6.70	6.70	0.35	35.18		
135.00	150.00			1	15.00	6.70	6.70	6.70	0.35	35.18		
150.00	164.00			1	14.00	6.40	5.20	5.80	0.35	28.42		
164.00	180.00			1	16.00	5.20	6.20	5.70	0.35	31.92		
180.00	195.00			1	15.00	6.20	5.40	5.80	0.35	30.45		
195.00	210.00			1	15.00	5.40	6.70	6.05	0.35	31.76		
210.00	218.00			1	8.00	6.70	6.40	6.55	0.35	18.34		
218.00	219.50	No Work		1	0.00	0.00	0.00	0.00	0.35	0.00		
219.50	230.00			1	10.50	5.80	6.00	5.90	0.35	21.68		
230.00	245.00			1	15.00	6.00	5.00	5.50	0.35	28.88		
245.00	260.00			1	15.00	5.00	6.20	5.60	0.35	29.40		
260.00	275.00			1	15.00	6.20	5.20	5.70	0.35	29.93		
275.00	284.80			1	9.80	5.20	5.50	5.35	0.35	18.35		
		21th Cross Road (W0969)										
0.00	15.00			1	15.00	7.90	6.20	7.05	0.35	37.01		
15.00	20.20			1	5.20	6.05	5.50	5.78	0.35	10.51		
20.20	33.00			1	12.80	5.60	6.00	5.80	0.35	25.98		
33.00	45.00			1	12.00	6.00	6.80	6.40	0.35	26.88		
45.00	60.00			1	15.00	5.60	6.60	6.10	0.35	32.03		
60.00	75.00			1	15.00	6.60	6.70	6.65	0.35	34.91		
75.00	90.00			1	15.00	6.70	6.65	6.68	0.35	35.04		
90.00	105.00			1	15.00	6.65	6.70	6.68	0.35	35.04		
105.00	120.00			1	15.00	6.70	6.70	6.70	0.35	35.18		
120.00	130.00			1	10.00	6.70	6.70	6.70	0.35	23.45		
		Connecting Road-1 (W0618)										
0.00	3.90			1	3.90	7.20	6.95	7.08	0.35	9.66		
3.90	15.00			1	11.10	9.00	8.00	8.50	0.35	33.02		
15.00	23.80			1	8.80	8.00	7.60	7.80	0.35	24.02		
		Dead End (W0845)										
0.00	15.00			1	15.00	5.95	6.40	6.18	0.35	32.42		
15.00	25.40			1	10.40	6.40	6.40	6.40	0.35	23.30		
		Connecting Road-2										
0.00	15.00			1	15.00	5.90	5.90	5.90	0.35	30.98		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
				1	9.00	5.90	5.90	5.90	0.35	18.59		
15.00	24.00											
		1st A Cross Road (W0975)										
0.00	15.00			1	15.00	7.70	7.90	7.80	0.35	40.95		
15.00	31.30			1	16.30	7.90	8.00	7.95	0.35	45.35		
		18th A Cross Road (W0618)										
0.00	15.00			1	15.00	5.80	5.60	5.70	0.35	29.93		
15.00	30.00			1	15.00	5.60	5.60	5.60	0.35	29.40		
30.00	45.00			1	15.00	5.60	5.50	5.55	0.35	29.14		
45.00	60.00			1	15.00	5.50	4.90	5.20	0.35	27.30		
60.00	74.20			1	14.20	5.60	4.90	5.25	0.35	26.09		
		Munikemmpama Layout										
		1st Cross Road (W0973)										
		From South to North										
0.00	15.00		Cum	1	15.00	5.30	6.00	5.65	0.35	29.66		
15.00	30.00		Cum	1	15.00	6.00	5.70	5.85	0.35	30.71		
30.00	45.00		Cum	1	15.00	5.70	5.85	5.78	0.35	30.32		
45.00	60.00		Cum	1	15.00	5.85	5.45	5.65	0.35	29.66		
60.00	73.10		Cum	1	13.10	5.45	5.95	5.70	0.35	26.13		
		For CC Road										
		Kaveri Layout										
		Krishna Nivas House (W1309)										
		South to North										
0.00	15.00			1	15.00	5.30	4.95	5.13	0.45	34.59		
15.00	30.00			1	15.00	4.95	5.20	5.08	0.45	34.26		
30.00	45.00			1	15.00	5.20	5.15	5.18	0.45	34.93		
45.00	60.00			1	15.00	5.15	5.15	5.15	0.45	34.76		
60.00	75.00			1	15.00	5.15	5.20	5.18	0.45	34.93		
75.00	90.00			1	15.00	5.20	3.90	4.55	0.45	30.71		
90.00	91.10			1	1.10	3.90	3.90	3.90	0.45	1.93		
		Joseph House Road (W0884)										
		West to East										
0.00	15.00			1	15.00	4.90	5.15	5.03	0.45	33.92		
15.00	30.00			1	15.00	5.15	4.90	5.03	0.45	33.92		
30.00	45.00			1	15.00	4.90	5.80	5.35	0.45	36.11		
45.00	46.20			1	1.20	5.80	5.85	5.83	0.45	3.15		
		Moto Works Oppo. (W1299)										
		South to North										
0.00	15.00			1	15.00	5.90	5.35	5.63	0.45	37.97		
15.00	30.00			1	15.00	5.35	5.00	5.18	0.45	34.93		
30.00	45.00			1	15.00	5.00	5.20	5.10	0.45	34.43		
45.00	60.00			1	15.00	5.20	5.25	5.23	0.45	35.27		
60.00	75.00			1	15.00	5.25	5.05	5.15	0.45	34.76		
75.00	90.00			1	15.00	5.05	5.45	5.25	0.45	35.44		
90.00	105.00			1	15.00	5.45	5.45	5.45	0.45	36.79		
105.00	120.00			1	15.00	5.45	4.40	4.93	0.45	33.24		
120.00	128.10			1	8.10	4.40	3.95	4.18	0.45	15.22		
		Cross Road 1 (W0870)										
		West to East										
0.00	15.00			1	15.00	4.10	4.65	4.38	0.45	29.53		
15.00	25.60			1	10.60	4.65	4.10	4.38	0.45	20.87		
		Cross Road 2 (W0862)										
		West to East										
0.00	15.00			1	15.00	5.30	5.25	5.28	0.45	35.61		
15.00	30.00			1	15.00	5.25	4.85	5.05	0.45	34.09		
30.00	32.30			1	2.30	4.85	3.50	4.18	0.45	4.32		
		Cross Road (W1297)										
		South to North										
0.00	15.00			1	15.00	5.40	5.10	5.25	0.45	35.44		
15.00	30.00			1	15.00	5.10	4.70	4.90	0.45	33.08		
30.00	45.00			1	15.00	4.70	4.60	4.65	0.45	31.39		
45.00	60.00			1	15.00	4.60	4.50	4.55	0.45	30.71		
60.00	75.00			1	15.00	4.50	4.30	4.40	0.45	29.70		

Drainage From	Drainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
				1	15.00	4.30	4.00	4.15	0.45	28.01		
				1	15.00	4.00	4.00	4.00	0.45	27.00		
		Vishwarathna #951 House Beside Road										
		(East To West)										
0.00	15.00		Cum	1	15.00	5.20	5.70	5.45	0.45	36.79		
15.00	30.00		Cum	1	15.00	5.70	6.00	5.85	0.45	39.49		
30.00	37.80		Cum	1	7.80	6.00	6.30	6.15	0.45	21.59		
		Sri Laxmi Narayana opp Road										
		(South To North)										
0.00	15.00		Cum	1	15.00	2.70	2.20	2.45	0.45	16.54		
15.00	16.90		Cum	1	1.90	2.20	2.15	2.18	0.45	1.86		
16.90	30.00		Cum	1	13.10	2.45	2.90	2.68	0.45	15.77		
30.00	45.00		Cum	1	15.00	2.90	2.85	2.88	0.45	19.41		
45.00	60.00		Cum	1	15.00	2.85	2.85	2.85	0.45	19.24		
60.00	61.50		Cum	1	1.50	2.85	2.80	2.83	0.45	1.91		
		7 star Multi Cusine Beside Road										
		(South To North)										
0.00	15.00		Cum	1	15.00	3.55	3.25	3.40	0.45	22.95		
15.00	30.00		Cum	1	15.00	3.25	3.10	3.18	0.45	21.43		
30.00	34.70		Cum	1	4.70	3.10	2.80	2.95	0.45	6.24		
		Cross Road										
0.00	15.00		Cum	1	15.00	4.00	4.00	4.00	0.45	27.00		
15.00	30.00		Cum	1	15.00	4.00	4.00	4.00	0.45	27.00		
30.00	45.00		Cum	1	15.00	4.00	4.00	4.00	0.45	27.00		
45.00	58.00		Cum	1	13.00	4.00	4.00	4.00	0.45	23.40		
		DEDUCTION										
		Chambers	Cum	-10	0.45	0.45	0.45	0.45	0.45	-0.91		
		Manhole 0.75dia	Cum	-3	0.44				0.45	-0.60		
					(3.14*0.75*0.75)/4=0.44							
			Cum	-4	0.45	0.45	0.45	0.45	0.35	-0.28		
									Total Executed Quantity	**3700.42**		
									Tender Quantity	**3314.53**		
									Quantity Upto 125%	**3700.42**	**30.00**	**111013.00**
Item no.13		Compaction of original ground by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM complete as per specifications and directions of the Engineer in charge.										
		For Asphalt Road										
		Kuvempu Layout										
		2nd Main Road 1st Cross Road (W0977)										
0.00	15.00		Sqm	1	15.00	7.50	6.65	7.08		106.13		
15.00	23.80			1	8.80	6.65	6.65	6.65		58.52		
23.80	34.40	No work		1	0.00	0.00	0.00	0.00		0.00		
34.40	45.00			1	10.60	6.45	5.50	5.98		63.34		
45.00	57.90			1	12.90	5.60	6.25	5.93		76.43		
		2nd Main Road 2nd Cross Road (W0616)										
0.00	15.00			1	15.00	4.90	5.20	5.05		75.75		
15.00	29.80			1	14.80	5.20	5.60	5.40		79.92		
		1st Main Road 2nd Cross Road (W0983)										
0.00	15.00			1	15.00	6.40	6.20	6.30		94.50		
15.00	30.00			1	15.00	6.20	6.30	6.25		93.75		
30.00	45.00			1	15.00	6.30	6.40	6.35		95.25		
45.00	62.50			1	17.50	6.40	5.45	5.93		103.69		
		1st Main Road 1st Cross Road (W0973)										
0.00	15.00			1	15.00	6.40	6.20	6.30		94.50		
15.00	30.00			1	15.00	6.20	6.30	6.25		93.75		
30.00	45.00			1	15.00	6.30	6.40	6.35		95.25		

...hainage From	To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
...00	58.20			1	13.20	6.40	5.45	5.93		78.21		
		1st Main Road (W0612)										
0.00	15.00			1	15.00	5.25	5.35	5.30		79.50		
15.00	30.00			1	15.00	5.35	6.60	5.98		89.63		
30.00	45.00			1	15.00	6.60	6.20	6.40		96.00		
45.00	60.00			1	15.00	6.20	6.05	6.13		91.88		
60.00	75.00			1	15.00	6.05	5.70	5.88		88.13		
75.00	90.00			1	15.00	5.70	5.90	5.80		87.00		
90.00	95.60			1	5.60	6.00	7.50	6.75		37.80		
95.60	105.00			1	9.40	7.50	7.30	7.40		69.56		
105.00	120.00			1	15.00	7.30	7.30	7.30		109.50		
120.00	124.00			1	4.00	7.30	8.20	7.75		31.00		
124.00	126.40			1	2.40	8.20	12.20	10.20		24.48		
126.40	135.00			1	8.60	12.20	12.30	12.25		105.35		
135.00	146.20			1	11.20	11.10	8.20	9.65		108.08		
146.20	160.00			1	13.80	8.20	8.70	8.45		116.61		
160.00	165.20			1	5.20	8.70	5.80	7.25		37.70		
165.20	180.00			1	14.80	5.80	6.15	5.98		88.43		
180.00	195.00			1	15.00	6.15	6.20	6.18		92.63		
195.00	201.40			1	6.40	6.20	6.50	6.35		40.64		
201.40	205.10			1	3.70	6.50	3.70	5.10		18.87		
205.10	207.50			1	2.40	3.70	1.60	2.65		6.36		
		1st Main 3rd Cross (W0989)										
0.00	15.00			1	15.00	5.65	5.60	5.63		84.38		
15.00	30.00			1	15.00	5.60	5.65	5.63		84.38		
30.00	45.00			1	15.00	5.65	5.45	5.55		83.25		
45.00	61.20			1	16.20	5.45	5.20	5.33		86.27		
		2nd Main Road (W0616)										
0.00	1.30			1	1.30	4.45	4.45	4.45		5.79		
15.00	16.70			1	1.70	6.60	6.85	6.73		11.43		
16.70	18.00	No Work		1	0.00	0.00	0.00	0.00		0.00		
18.00	30.00			1	12.00	5.20	5.40	5.30		63.60		
30.00	45.00			1	15.00	5.40	5.60	5.50		82.50		
45.00	60.00			1	15.00	5.60	5.50	5.55		83.25		
60.00	75.00			1	15.00	5.50	5.30	5.40		81.00		
75.00	90.00			1	15.00	5.30	5.65	5.48		82.13		
90.00	105.00			1	15.00	5.50	5.30	5.40		81.00		
105.00	120.00			1	15.00	5.30	6.70	6.00		90.00		
120.00	135.00			1	15.00	6.70	6.70	6.70		100.50		
135.00	150.00			1	15.00	6.70	6.70	6.70		100.50		
150.00	164.00			1	14.00	6.40	5.20	5.80		81.20		
164.00	180.00			1	16.00	5.20	6.20	5.70		91.20		
180.00	195.00			1	15.00	6.20	5.40	5.80		87.00		
195.00	210.00			1	15.00	5.40	6.70	6.05		90.75		
210.00	218.00			1	8.00	6.70	6.40	6.55		52.40		
218.00	219.50	No Work		1	0.00	0.00	0.00	0.00		0.00		
219.50	230.00			1	10.50	5.80	6.00	5.90		61.95		
230.00	245.00			1	15.00	6.00	5.00	5.50		82.50		
245.00	260.00			1	15.00	5.00	6.20	5.60		84.00		
260.00	275.00			1	15.00	6.20	5.20	5.70		85.50		
275.00	284.80			1	9.80	5.20	5.50	5.35		52.43		
		21th Cross Road (W0969)										
0.00	15.00			1	15.00	7.90	6.20	7.05		105.75		
15.00	20.20			1	5.20	6.05	5.50	5.78		30.03		
20.20	33.00			1	12.80	5.60	6.00	5.80		74.24		
33.00	45.00			1	12.00	6.00	6.80	6.40		76.80		
45.00	60.00			1	15.00	5.60	6.60	6.10		91.50		
60.00	75.00			1	15.00	6.60	6.70	6.65		99.75		
75.00	90.00			1	15.00	6.70	6.65	6.68		100.13		
90.00	105.00			1	15.00	6.65	6.70	6.68		100.13		
105.00	120.00			1	15.00	6.70	6.70	6.70		100.50		
120.00	130.00			1	10.00	6.70	6.70	6.70		67.00		
		Connecting Road-1 (W0608)										
0.00	3.90			1	3.90	7.20	6.95	7.08		27.59		
3.90	15.00			1	11.10	9.00	8.00	8.50		94.35		
15.00	23.80			1	8.80	8.00	7.60	7.80		68.64		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in ₦'s	Amount in ₦'s
		Dead End (WR065)										
0.00	15.00			1	15.00	5.25	5.49	5.18		92.63		
15.00	25.40			1	10.40	5.49	5.49	5.49		56.56		
		Connecting Road 2										
0.00	15.00			1	15.00	5.99	5.99	5.99		88.50		
15.00	24.00			1	9.00	5.99	5.99	5.99		53.10		
		1st A Cross Road (WR073)										
0.00	15.00			1	15.00	7.79	7.99	7.89		117.99		
15.00	31.30			1	16.30	7.99	8.00	7.93		129.22		
		18th A Cross Road (WR018)										
0.00	15.00			1	15.00	5.80	5.60	5.70		85.50		
15.00	30.00			1	15.00	5.60	5.60	5.60		84.00		
30.00	45.00			1	15.00	5.60	5.50	5.55		83.25		
45.00	60.00			1	15.00	5.50	4.99	5.29		78.99		
60.00	74.20			1	14.20	5.60	4.99	5.25		74.55		
		Munikemunpama Layout										
		1st Cross Road (WR073)										
		From South to North										
0.00	15.00		Sqm	1	15.00	5.39	6.00	5.65		84.75		
15.00	30.00		Sqm	1	15.00	6.00	5.70	5.85		87.75		
30.00	45.00		Sqm	1	15.00	5.70	5.85	5.78		86.63		
45.00	60.00		Sqm	1	15.00	5.85	5.45	5.65		84.75		
60.00	73.10		Sqm	1	13.10	5.45	5.95	5.70		74.67		
		For CC Road										
		Kaven Layout										
		Kristina Hivas House (WR399)										
		South to North										
0.00	15.00			1	15.00	5.39	4.95	5.13		76.88		
15.00	30.00			1	15.00	4.95	5.29	5.08		76.13		
30.00	45.00			1	15.00	5.29	5.15	5.18		77.63		
45.00	60.00			1	15.00	5.15	5.15	5.15		77.25		
60.00	75.00			1	15.00	5.15	5.29	5.18		77.63		
75.00	90.00			1	15.00	5.29	3.99	4.55		68.25		
90.00	91.10			1	1.10	3.99	3.99	3.99		4.29		
		Joseph House Road (WR084)										
		West to East										
0.00	15.00			1	15.00	4.99	5.15	5.03		75.38		
15.00	30.00			1	15.00	5.15	4.99	5.03		75.38		
30.00	45.00			1	15.00	4.99	5.80	5.35		80.25		
45.00	46.20			1	1.20	5.80	5.85	5.83		6.99		
		Mono Works Organ (WR299)										
		South to North										
0.00	15.00			1	15.00	5.99	5.35	5.63		84.38		
15.00	30.00			1	15.00	5.35	5.00	5.18		77.63		
30.00	45.00			1	15.00	5.00	5.20	5.10		76.50		
45.00	60.00			1	15.00	5.20	5.25	5.23		78.38		
60.00	75.00			1	15.00	5.25	5.05	5.15		77.25		
75.00	90.00			1	15.00	5.05	5.45	5.25		78.75		
90.00	105.00			1	15.00	5.45	5.45	5.45		81.75		
105.00	120.00			1	15.00	5.45	4.40	4.93		73.88		
120.00	128.10			1	8.10	4.40	3.95	4.18		33.82		
		Cross Road 1 (WR079)										
		West to East										
0.00	15.00			1	15.00	4.10	4.65	4.38		65.63		
15.00	25.00			1	10.00	4.65	4.10	4.38		46.38		
		Cross Road 2 (WR082)										
		West to East										
0.00	15.00			1	15.00	5.30	5.25	5.28		79.13		
15.00	30.00			1	15.00	5.25	4.85	5.05		75.75		
30.00	32.30			1	2.30	4.85	3.50	4.18		9.60		
		Cross Road (WR297)										

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
		South to North										
0.00	15.00			1	15.00	1.40	1.10	1.25		78.75		
15.00	30.00			1	15.00	1.10	1.70	1.40		73.50		
30.00	45.00			1	15.00	1.70	1.60	1.65		86.63		
45.00	60.00			1	15.00	1.60	1.50	1.55		81.38		
60.00	75.00			1	15.00	1.50	1.30	1.40		73.50		
75.00	90.00			1	15.00	1.30	1.05	1.18		61.95		
90.00	105.00			1	15.00	1.05	1.05	1.05		55.13		
		Vishwaradhna #951 House Beside Road (East To West)										
0.00	15.00		Sqm	1	15.00	3.25	2.70	2.98		41.73		
15.00	30.00		Sqm	1	15.00	2.70	1.80	2.25		37.13		
30.00	37.80		Sqm	1	7.80	1.80	1.30	1.55		67.37		
		Sri Lavani Narayana opp Road (South To North)										
0.00	15.00		Sqm	1	15.00	2.70	2.25	2.48		36.72		
15.00	16.90		Sqm	1	1.90	2.25	2.10	2.18		6.13		
16.90	30.00		Sqm	1	13.10	2.10	2.30	2.20		55.26		
30.00	45.00		Sqm	1	15.00	2.30	2.25	2.28		63.13		
45.00	60.00		Sqm	1	15.00	2.25	2.25	2.25		62.25		
60.00	61.50		Sqm	1	1.50	2.25	2.20	2.23		6.26		
		7 star Multi Cusine Beside Road (South To North)										
0.00	15.00		Sqm	1	15.00	3.50	3.25	3.38		51.00		
15.00	30.00		Sqm	1	15.00	3.25	3.10	3.18		47.63		
30.00	34.70		Sqm	1	4.70	3.10	2.80	2.95		13.87		
		Cross Road										
0.00	15.00		Sqm	1	15.00	6.00	6.00	6.00		90.00		
15.00	30.00		Sqm	1	15.00	6.00	6.00	6.00		90.00		
30.00	45.00		Sqm	1	15.00	6.00	6.00	6.00		90.00		
45.00	58.00		Sqm	1	13.00	6.00	6.00	6.00		52.00		
		DEDUCTION										
		Chambers	Sqm	-10	0.65	0.65	0.65	0.65		-2.19		
		Manhole & Misc	Sqm	-3	0.66					-1.32		
						(2 Nos, 1.5m x 1.5)	0.66					
			Sqm	-4	0.65	0.65	0.65	0.65		-2.31		
								Total Executed Quantity		3761.78		
								Tender Quantity		3954.75		
								Quantity Less 125%		3761.78	7.00	68333.00
Item no.16		Construction of granular sub base/Grading-I as Sub base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per specifications and directions of the Engineer in charge.										
		For Asphalt Road										
		Kuvempu Layout										
		2nd Main Road 1st Cross Road (NORTH)										
0.00	15.00		Cum	1	15.00	7.50	6.65	7.08	0.15	15.92		
15.00	23.80			1	8.80	6.65	6.65	6.65	0.15	8.78		
23.80	34.40	No work		1	0.00	0.00	0.00	0.00	0.15	0.00		
34.40	45.00			1	10.60	6.65	5.50	5.98	0.15	9.50		
45.00	57.00			1	12.00	6.65	6.25	5.95	0.15	11.66		
		2nd Main Road 2nd Cross Road (NORTH)										
0.00	15.00			1	15.00	6.50	5.20	5.85	0.15	11.30		
15.00	29.00			1	14.00	5.20	5.60	5.40	0.15	11.34		
		1st Main Road 2nd Cross Road (NORTH)										
0.00	15.00			1	15.00	6.60	6.20	6.30	0.15	14.18		
15.00	30.00			1	15.00	6.20	6.30	6.25	0.15	14.06		
30.00	45.00			1	15.00	6.30	6.60	6.35	0.15	14.29		
45.00	62.50			1	17.50	6.60	5.60	5.98	0.15	15.55		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		1st Main Road 1st Cross Road (W0973)										
0.00	15.00			1	15.00	6.40	6.20	6.30	0.15	14.18		
15.00	30.00			1	15.00	6.20	6.30	6.25	0.15	14.06		
30.00	45.00			1	15.00	6.30	6.40	6.35	0.15	14.29		
45.00	58.20			1	13.20	6.40	5.45	5.93	0.15	11.73		
		1st Main Road (W0612)										
0.00	15.00			1	15.00	5.25	5.35	5.30	0.15	11.93		
15.00	30.00			1	15.00	5.35	6.60	5.98	0.15	13.44		
30.00	45.00			1	15.00	6.60	6.20	6.40	0.15	14.40		
45.00	60.00			1	15.00	6.20	6.05	6.13	0.15	13.78		
60.00	75.00			1	15.00	6.05	5.70	5.88	0.15	13.22		
75.00	90.00			1	15.00	5.70	5.90	5.80	0.15	13.05		
90.00	95.60			1	5.60	6.00	7.50	6.75	0.15	5.67		
95.60	105.00			1	9.40	7.50	7.30	7.40	0.15	10.43		
105.00	120.00			1	15.00	7.30	7.30	7.30	0.15	16.43		
120.00	124.00			1	4.00	7.30	8.20	7.75	0.15	4.65		
124.00	126.40			1	2.40	8.20	12.20	10.20	0.15	3.67		
126.40	135.00			1	8.60	12.20	12.30	12.25	0.15	15.80		
135.00	146.20			1	11.20	11.10	8.20	9.65	0.15	16.21		
146.20	160.00			1	13.80	8.20	8.70	8.45	0.15	17.49		
160.00	165.20			1	5.20	8.70	5.80	7.25	0.15	5.65		
165.20	180.00			1	14.80	5.80	6.15	5.98	0.15	13.26		
180.00	195.00			1	15.00	6.15	6.20	6.18	0.15	13.89		
195.00	201.40			1	6.40	6.20	6.50	6.35	0.15	6.10		
201.40	205.10			1	3.70	6.50	3.70	5.10	0.15	2.83		
205.10	207.50			1	2.40	3.70	1.60	2.65	0.15	0.95		
		1st Main 3rd Cross (W0989)										
0.00	15.00			1	15.00	5.65	5.60	5.63	0.15	12.66		
15.00	30.00			1	15.00	5.60	5.65	5.63	0.15	12.66		
30.00	45.00			1	15.00	5.65	5.45	5.55	0.15	12.49		
45.00	61.20			1	16.20	5.45	5.20	5.33	0.15	12.94		
		2nd Main Road (W0616)										
0.00	1.30			1	1.30	4.45	4.45	4.45	0.15	0.87		
15.00	16.70			1	1.70	6.60	6.85	6.73	0.15	1.71		
16.70	18.00	No Work		1	0.00	0.00	0.00	0.00	0.15	0.00		
18.00	30.00			1	12.00	5.20	5.40	5.30	0.15	9.54		
30.00	45.00			1	15.00	5.40	5.60	5.50	0.15	12.38		
45.00	60.00			1	15.00	5.60	5.50	5.55	0.15	12.49		
60.00	75.00			1	15.00	5.50	5.30	5.40	0.15	12.15		
75.00	90.00			1	15.00	5.30	5.65	5.48	0.15	12.32		
90.00	105.00			1	15.00	5.50	5.30	5.40	0.15	12.15		
105.00	120.00			1	15.00	5.30	6.70	6.00	0.15	13.50		
120.00	135.00			1	15.00	6.70	6.70	6.70	0.15	15.08		
135.00	150.00			1	15.00	6.70	6.70	6.70	0.15	15.08		
150.00	164.00			1	14.00	6.40	5.20	5.80	0.15	12.18		
164.00	180.00			1	16.00	5.20	6.20	5.70	0.15	13.68		
180.00	195.00			1	15.00	6.20	5.40	5.80	0.15	13.05		
195.00	210.00			1	15.00	5.40	6.70	6.05	0.15	13.61		
210.00	218.00			1	8.00	6.70	6.40	6.55	0.15	7.86		
218.00	219.50	No Work		1	0.00	0.00	0.00	0.00	0.15	0.00		
219.50	230.00			1	10.50	5.80	6.00	5.90	0.15	9.29		
230.00	245.00			1	15.00	6.00	5.00	5.50	0.15	12.38		
245.00	260.00			1	15.00	5.00	6.20	5.60	0.15	12.60		
260.00	275.00			1	15.00	6.20	5.20	5.70	0.15	12.83		
275.00	284.80			1	9.80	5.20	5.50	5.35	0.15	7.86		
		21th Cross Road (W0969)										
0.00	15.00			1	15.00	7.90	6.20	7.05	0.15	15.86		
15.00	20.20			1	5.20	6.05	5.50	5.78	0.15	4.50		
20.20	33.00			1	12.80	5.60	6.00	5.80	0.15	11.14		
33.00	45.00			1	12.00	6.00	6.80	6.40	0.15	11.52		
45.00	60.00			1	15.00	5.60	6.60	6.10	0.15	13.73		
60.00	75.00			1	15.00	6.60	6.70	6.65	0.15	14.96		
75.00	90.00			1	15.00	6.70	6.65	6.68	0.15	15.02		
90.00	105.00			1	15.00	6.65	6.70	6.68	0.15	15.02		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
00	120.00			1	15.00	6.70	6.70	6.70	0.15	15.08		
00	130.00			1	10.00	6.70	6.70	6.70	0.15	10.05		
		Connecting Road-1 (W0608)										
0.00	3.90			1	3.90	7.20	6.95	7.08	0.15	4.14		
3.90	15.00			1	11.10	9.00	8.00	8.50	0.15	14.15		
15.00	23.80			1	8.80	8.00	7.60	7.80	0.15	10.30		
		Dead End (W0965)										
0.00	15.00			1	15.00	5.95	6.40	6.18	0.15	13.89		
15.00	25.40			1	10.40	6.40	6.40	6.40	0.15	9.98		
		Connecting Road-2										
0.00	15.00			1	15.00	5.90	5.90	5.90	0.15	13.28		
15.00	24.00			1	9.00	5.90	5.90	5.90	0.15	7.97		
		1st A Cross Road (W0975)										
0.00	15.00			1	15.00	7.70	7.90	7.80	0.15	17.55		
15.00	31.30			1	16.30	7.90	8.00	7.95	0.15	19.44		
		18th A Cross Road (W0618)										
0.00	15.00			1	15.00	5.80	5.60	5.70	0.15	12.83		
15.00	30.00			1	15.00	5.60	5.60	5.60	0.15	12.60		
30.00	45.00			1	15.00	5.60	5.50	5.55	0.15	12.49		
45.00	60.00			1	15.00	5.50	4.90	5.20	0.15	11.70		
60.00	74.20			1	14.20	5.60	4.90	5.25	0.15	11.18		
		Munikenmpama Layout										
		1st Cross Road (W0973)										
		From South to North										
0.00	15.00		Cum	1	15.00	5.30	6.00	5.65	0.15	12.71		
15.00	30.00		Cum	1	15.00	6.00	5.70	5.85	0.15	13.16		
30.00	45.00		Cum	1	15.00	5.70	5.85	5.78	0.15	12.99		
45.00	60.00		Cum	1	15.00	5.85	5.45	5.65	0.15	12.71		
60.00	73.10		Cum	1	13.10	5.45	5.95	5.70	0.15	11.20		
		For CC Road										
		Kaveri Layout										
		Krishna Nivas House (W1309)										
		South to North										
0.00	15.00			1	15.00	5.30	4.95	5.13	0.15	11.53		
15.00	30.00			1	15.00	4.95	5.20	5.08	0.15	11.42		
30.00	45.00			1	15.00	5.20	5.15	5.18	0.15	11.64		
45.00	60.00			1	15.00	5.15	5.15	5.15	0.15	11.59		
60.00	75.00			1	15.00	5.15	5.20	5.18	0.15	11.64		
75.00	90.00			1	15.00	5.20	3.90	4.55	0.15	10.24		
90.00	91.10			1	1.10	3.90	3.90	3.90	0.15	0.64		
		Joseph House Road (W0884)										
		West to East										
0.00	15.00			1	15.00	4.90	5.15	5.03	0.15	11.31		
15.00	30.00			1	15.00	5.15	4.90	5.03	0.15	11.31		
30.00	45.00			1	15.00	4.90	5.80	5.35	0.15	12.04		
45.00	46.20			1	1.20	5.80	5.85	5.83	0.15	1.05		
		Moto Works Oppo. (W1299)										
		South to North										
0.00	15.00			1	15.00	5.90	5.35	5.63	0.15	12.66		
15.00	30.00			1	15.00	5.35	5.00	5.18	0.15	11.64		
30.00	45.00			1	15.00	5.00	5.20	5.10	0.15	11.48		
45.00	60.00			1	15.00	5.20	5.25	5.23	0.15	11.76		
60.00	75.00			1	15.00	5.25	5.05	5.15	0.15	11.59		
75.00	90.00			1	15.00	5.05	5.45	5.25	0.15	11.81		
90.00	105.00			1	15.00	5.45	5.45	5.45	0.15	12.26		
105.00	120.00			1	15.00	5.45	4.40	4.93	0.15	11.08		
120.00	128.10			1	8.10	4.40	3.95	4.18	0.15	5.07		
		Cross Road 1 (W0870)										
		West to East										
0.00	15.00			1	15.00	4.10	4.65	4.38	0.15	9.84		
15.00	25.60			1	10.60	4.65	4.10	4.38	0.15	6.96		

Number	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Ave B	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
	Cross Road 2 (W/S&E)										
	West to East										
			1	15.00	5.30	5.25	5.28	0.15	11.87		
			1	15.00	5.25	4.85	5.05	0.15	11.36		
			1	2.30	4.85	3.90	4.38	0.15	1.51		
	Cross Road (W/12ST)										
	South to North										
0.00	15.00		1	15.00	5.90	5.10	5.25	0.15	11.81		
15.00	30.00		1	15.00	5.10	4.70	4.90	0.15	11.03		
30.00	45.00		1	15.00	4.70	4.00	4.45	0.15	10.01		
45.00	60.00		1	15.00	4.80	4.20	4.53	0.15	10.20		
60.00	75.00		1	15.00	4.50	4.30	4.40	0.15	9.90		
75.00	90.00		1	15.00	4.30	4.00	4.15	0.15	9.34		
90.00	105.00		1	15.00	4.30	4.00	4.15	0.15	9.34		
	Kamaraj Nagar #351 House Beside Road										
	(East To West)										
0.00	15.00	Cum	1	15.00	5.20	5.70	5.45	0.15	12.26		
15.00	30.00	Cum	1	15.00	5.70	6.00	5.85	0.15	13.16		
30.00	37.85	Cum	1	7.80	6.00	6.30	6.15	0.15	7.20		
	Sri Lavasu Narayana 2nd Road										
	(South To North)										
0.00	15.00	Cum	1	15.00	2.70	2.20	2.45	0.15	5.51		
15.00	30.00	Cum	1	15.00	2.20	2.15	2.18	0.15	4.91		
30.00	43.19	Cum	1	13.19	2.45	2.30	2.38	0.15	5.26		
43.19	58.19	Cum	1	15.00	2.30	2.35	2.33	0.15	5.24		
58.19	73.19	Cum	1	15.00	2.35	2.35	2.35	0.15	5.41		
73.19	88.19	Cum	1	15.00	2.35	2.30	2.33	0.15	5.24		
88.19	91.19	Cum	1	1.50	2.35	2.30	2.33	0.15	0.54		
	7 Star Multi Cuisine Beside Road										
	(South To North)										
0.00	15.00	Cum	1	15.00	3.55	3.25	3.40	0.15	7.65		
15.00	30.00	Cum	1	15.00	3.25	3.10	3.18	0.15	7.16		
30.00	34.75	Cum	1	4.70	3.10	2.80	2.95	0.15	2.08		
	Cross Road										
0.00	15.00	Cum	1	15.00	4.60	4.60	4.60	0.15	9.66		
15.00	30.00	Cum	1	15.00	4.60	4.60	4.60	0.15	9.66		
30.00	45.00	Cum	1	15.00	4.60	4.60	4.60	0.15	9.66		
45.00	58.00	Cum	1	13.00	4.60	4.60	4.60	0.15	7.80		
	DEDUCTION										
	Chamber	Cum	-10	0.45	0.45	0.45	0.45	0.15	-0.30		
	Manhole 0.75dia	Cum	-3	0.44				0.15	-0.20		
				(3.14*0.75*0.75)/4=0.44							
		Cum	-4	0.45	0.45	0.45	0.45	0.15	-0.12		
								Total Executed Quantity	1464.27		
								Tender Quantity	1343.21		
								Quantity Upto 125%	1464.27	200.00	292854.00

Item no.15	Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications and directions of the Engineer in charge.

		Kavungu Layout										
		2nd Main Road 1st Cross Road (W/S&T)										
0.00	15.00		Cum	1	15.00	7.50	6.65	7.08	0.20	21.23		
15.00	23.80			1	8.80	6.65	6.65	6.65	0.20	11.70		
23.80	34.60	No work		1	0.00	0.00	0.00	0.00	0.20	0.00		
34.60	45.00			1	10.60	6.45	5.50	5.98	0.20	12.67		
45.00	57.00			1	12.00	5.60	6.25	5.93	0.20	15.29		
		2nd Main Road 2nd Cross Road (W/S&T)										
0.00	15.00			1	15.00	4.90	5.20	5.05	0.20	15.15		
15.00	29.80			1	14.80	5.20	5.60	5.40	0.20	15.98		

(Ward No 06)

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		1st Main Road 2nd Cross Road (W0983)										
0.00	15.00			1	15.00	6.40	6.20	6.30	0.20	18.90		
15.00	30.00			1	15.00	6.20	6.30	6.25	0.20	18.75		
30.00	45.00			1	15.00	6.30	6.40	6.35	0.20	19.05		
45.00	62.50			1	17.50	6.40	5.45	5.93	0.20	20.74		
		1st Main Road 1st Cross Road (W0973)										
0.00	15.00			1	15.00	6.40	6.20	6.30	0.20	18.90		
15.00	30.00			1	15.00	6.20	6.30	6.25	0.20	18.75		
30.00	45.00			1	15.00	6.30	6.40	6.35	0.20	19.05		
45.00	58.20			1	13.20	6.40	5.45	5.93	0.20	15.64		
		1st Main Road (W0612)										
0.00	15.00			1	15.00	5.25	5.35	5.30	0.20	15.90		
15.00	30.00			1	15.00	5.35	6.60	5.98	0.20	17.93		
30.00	45.00			1	15.00	6.60	6.20	6.40	0.20	19.20		
45.00	60.00			1	15.00	6.20	6.05	6.13	0.20	18.38		
60.00	75.00			1	15.00	6.05	5.70	5.88	0.20	17.63		
75.00	90.00			1	15.00	5.70	5.90	5.80	0.20	17.40		
90.00	95.60			1	5.60	6.00	7.50	6.75	0.20	7.56		
95.60	105.00			1	9.40	7.50	7.30	7.40	0.20	13.91		
105.00	120.00			1	15.00	7.30	7.30	7.30	0.20	21.90		
120.00	124.00			1	4.00	7.30	8.20	7.75	0.20	6.20		
124.00	126.40			1	2.40	8.20	12.20	10.20	0.20	4.90		
126.40	135.00			1	8.60	12.20	12.30	12.25	0.20	21.07		
135.00	146.20			1	11.20	11.10	8.20	9.65	0.20	21.62		
146.20	160.00			1	13.80	8.20	8.70	8.45	0.20	23.32		
160.00	165.20			1	5.20	8.70	5.80	7.25	0.20	7.54		
165.20	180.00			1	14.80	5.80	6.15	5.98	0.20	17.69		
180.00	195.00			1	15.00	6.15	6.20	6.18	0.20	18.53		
195.00	201.40			1	6.40	6.20	6.50	6.35	0.20	8.13		
201.40	205.10			1	3.70	6.50	3.70	5.10	0.20	3.77		
205.10	207.50			1	2.40	3.70	1.60	2.65	0.20	1.27		
		1st Main 3rd Cross (W0989)										
0.00	15.00			1	15.00	5.65	5.60	5.63	0.20	16.88		
15.00	30.00			1	15.00	5.60	5.65	5.63	0.20	16.88		
30.00	45.00			1	15.00	5.65	5.45	5.55	0.20	16.65		
45.00	61.20			1	16.20	5.45	5.20	5.33	0.20	17.25		
		2nd Main Road (W0616)										
0.00	1.30			1	1.30	4.45	4.45	4.45	0.20	1.16		
15.00	16.70			1	1.70	6.60	6.85	6.73	0.20	2.29		
16.70	18.00	No Work		1	0.00	0.00	0.00	0.00	0.20	0.00		
18.00	30.00			1	12.00	5.20	5.40	5.30	0.20	12.72		
30.00	45.00			1	15.00	5.40	5.60	5.50	0.20	16.50		
45.00	60.00			1	15.00	5.60	5.50	5.55	0.20	16.65		
60.00	75.00			1	15.00	5.50	5.30	5.40	0.20	16.20		
75.00	90.00			1	15.00	5.30	5.65	5.48	0.20	16.43		
90.00	105.00			1	15.00	5.50	5.30	5.40	0.20	16.20		
105.00	120.00			1	15.00	5.30	6.70	6.00	0.20	18.00		
120.00	135.00			1	15.00	6.70	6.70	6.70	0.20	20.10		
135.00	150.00			1	15.00	6.70	6.70	6.70	0.20	20.10		
150.00	164.00			1	14.00	6.40	5.20	5.80	0.20	16.24		
164.00	180.00			1	16.00	5.20	6.20	5.70	0.20	18.24		
180.00	195.00			1	15.00	6.20	5.40	5.80	0.20	17.40		
195.00	210.00			1	15.00	5.40	6.70	6.05	0.20	18.15		
210.00	218.00			1	8.00	6.70	6.40	6.55	0.20	10.48		
218.00	219.50	No Work		1	0.00	0.00	0.00	0.00	0.20	0.00		
219.50	230.00			1	10.50	5.80	6.00	5.90	0.20	12.39		
230.00	245.00			1	15.00	6.00	5.00	5.50	0.20	16.50		
245.00	260.00			1	15.00	5.00	6.20	5.60	0.20	16.80		
260.00	275.00			1	15.00	6.20	5.20	5.70	0.20	17.10		
275.00	284.80			1	9.80	5.20	5.50	5.35	0.20	10.49		
		21th Cross Road (W0969)										
0.00	15.00			1	15.00	7.90	6.20	7.05	0.20	21.15		
15.00	20.20			1	5.20	6.05	5.50	5.78	0.20	6.01		

	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
			01	12.80	5.60	6.00	5.80	0.20	14.85		
			01	12.00	6.00	6.80	6.40	0.20	15.36		
			01	15.00	5.60	6.60	6.10	0.20	18.30		
			01	15.00	6.60	6.70	6.65	0.20	19.95		
			01	15.00	6.70	6.65	6.68	0.20	20.03		
			01	15.00	6.65	6.70	6.68	0.20	20.03		
			01	15.00	6.70	6.70	6.70	0.20	20.10		
			01	10.00	6.70	6.70	6.70	0.20	13.40		
	Connecting Road-1 (W0968)										
1.00	3.90		01	3.90	7.20	6.95	7.08	0.20	5.52		
3.90	15.00		01	11.10	8.00	8.00	8.00	0.20	17.76		
15.00	23.80		01	8.80	8.00	7.60	7.80	0.20	13.73		
	Dead End (W0965)										
1.00	16.00		01	15.00	5.95	6.40	6.18	0.20	18.53		
16.00	25.40		01	10.40	6.40	6.40	6.40	0.20	13.31		
	Connecting Road-2										
1.00	16.00		01	15.00	5.90	5.90	5.90	0.20	17.70		
16.00	24.00		01	9.00	5.90	5.90	5.90	0.20	10.62		
	1st A Cross Road (W0975)										
1.00	16.00		01	15.00	7.70	7.90	7.80	0.20	23.40		
16.00	31.30		01	16.30	7.90	8.00	7.95	0.20	25.92		
	2Bit A Cross Road (W0978)										
1.00	16.00		01	15.00	5.80	5.60	5.70	0.20	17.10		
16.00	32.00		01	15.00	5.60	5.60	5.60	0.20	16.80		
32.00	48.00		01	15.00	5.60	5.50	5.55	0.20	16.65		
48.00	64.00		01	15.00	5.50	4.90	5.20	0.20	15.60		
64.00	74.20		01	14.20	5.60	4.90	5.25	0.20	14.91		
	Muddemmpatta Layout										
	1st Cross Road (W0973)										
	From South to North										
1.00	16.00	Cum	1	15.00	5.30	6.00	5.65	0.20	16.95		
16.00	32.00	Cum	1	15.00	6.00	5.70	5.85	0.20	17.55		
32.00	48.00	Cum	1	15.00	5.70	5.85	5.78	0.20	17.33		
48.00	64.00	Cum	1	15.00	5.85	5.45	5.65	0.20	16.95		
64.00	78.10	Cum	1	13.10	5.45	5.95	5.70	0.20	14.93		
	Deduction										
		Cum	-4	0.45	0.45	0.45	0.45	0.20	-0.16		
								Total Executed Quantity	**1384.76**	**2100.00**	**2907999.00**
								Tender Quantity	**1430.21**		
Item no.16	Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications and directions of the Engineer in charge										
	1st Main 3rd Cross (W0969)										
	From South to North										
0.00	3.20	Sqm	1	3.20	6.20	5.50	5.85		18.72		
3.20	15.00	Sqm	1	11.80	5.50	5.60	5.55		65.49		
15.00	30.00	Sqm	1	15.00	5.60	5.45	5.53		82.88		
30.00	45.00	Sqm	1	15.00	5.45	5.40	5.43		81.38		
45.00	60.00	Sqm	1	15.00	5.40	4.95	5.18		77.63		
60.00	62.70	Sqm	1	2.70	4.95	4.90	4.93		13.30		
	1st Main Road 2nd Cross Road (W0983)										
	From South to North										
0.00	15.00	Sqm	1	15.00	6.15	6.00	6.08		91.13		
15.00	30.00	Sqm	1	15.00	6.00	6.20	6.10		91.50		
30.00	45.00	Sqm	1	15.00	6.20	6.35	6.28		94.13		
45.00	60.00	Sqm	1	15.00	6.35	5.45	5.90		88.50		
60.00	62.30	Sqm	1	2.30	5.45	5.40	5.43		12.48		
	1st Main Road 1st Cross Road (W0973)										
	From South to North										
0.00	15.00	Sqm	1	15.00	6.40	5.55	5.98		89.63		
15.00	16.00	Sqm	1	1.00	5.55	5.55	5.55		5.55		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
	30.00		Sqm	1	14.00	6.00	6.10	6.05		84.70		
	45.00		Sqm	1	15.00	6.10	6.50	6.30		94.50		
	58.30		Sqm	1	13.30	6.50	6.10	6.30		83.79		
		21th Cross Road (W0969)										
		From North to South										
0.00	15.00		Sqm	1	15.00	7.15	6.85	7.00		105.00		
15.00	30.00		Sqm	1	15.00	6.85	6.20	6.53		97.88		
30.00	45.00		Sqm	1	15.00	6.20	6.80	6.50		97.50		
45.00	60.00		Sqm	1	15.00	6.80	6.85	6.83		102.38		
60.00	75.00		Sqm	1	15.00	6.85	6.80	6.83		102.38		
75.00	90.00		Sqm	1	15.00	6.80	6.80	6.80		102.00		
90.00	105.00		Sqm	1	15.00	6.80	4.75	5.78		86.63		
105.00	107.70		Sqm	1	2.70	4.75	4.80	4.78		12.89		
107.70	116.40		Sqm	1	8.70	5.80	6.00	5.90		51.33		
116.40	120.00		Sqm	1	3.60	5.30	6.80	6.05		21.78		
120.00	128.70		Sqm	1	8.70	6.80	7.55	7.18		62.42		
		Connecting Road 2										
		From East to West										
0.00	4.30		Sqm	1	4.30	7.20	6.95	7.08		30.42		
4.30	15.00		Sqm	1	10.70	9.00	7.80	8.40		89.88		
15.00	25.30		Sqm	1	10.30	7.80	7.85	7.83		80.60		
		Dead End (W0965)										
		From North to South										
0.00	15.00		Sqm	1	15.00	6.20	6.50	6.35		95.25		
15.00	24.90		Sqm	1	9.90	6.50	6.45	6.48		64.10		
		1st Main Road (W0612)										
		From West to East										
0.00	15.00		Sqm	1	15.00	5.10	5.40	5.25		78.75		
15.00	25.30		Sqm	1	10.30	5.40	6.60	6.00		61.80		
25.30	30.00		Sqm	1	4.70	6.60	6.30	6.45		30.32		
30.00	45.00		Sqm	1	15.00	6.30	6.10	6.20		93.00		
45.00	47.80		Sqm	1	2.80	6.10	5.90	6.00		16.80		
47.80	51.10		Sqm	1	3.30	5.60	6.20	5.90		19.47		
51.10	60.00		Sqm	1	8.90	6.20	5.90	6.05		53.85		
60.00	75.00		Sqm	1	15.00	5.90	5.40	5.65		84.75		
75.00	90.00		Sqm	1	15.00	5.40	5.90	5.65		84.75		
90.00	94.80		Sqm	1	4.80	5.90	5.95	5.93		28.44		
94.80	105.00		Sqm	1	10.20	7.40	7.25	7.33		74.72		
105.00	120.00		Sqm	1	15.00	7.25	7.20	7.23		108.38		
120.00	122.90		Sqm	1	2.90	7.20	7.20	7.20		20.88		
122.90	125.00		Sqm	1	2.10	8.15	9.40	8.78		18.43		
125.00	135.00		Sqm	1	10.00	12.03	12.25	12.14		121.40		
135.00	141.40		Sqm	1	6.40	12.25	12.15	12.20		78.08		
141.40	145.10		Sqm	1	3.70	11.30	11.00	11.15		41.25		
145.10	150.00		Sqm	1	4.90	8.10	8.10	8.10		39.69		
150.00	164.40		Sqm	1	14.40	8.10	8.00	8.05		115.92		
164.40	180.00		Sqm	1	15.60	5.85	6.10	5.98		93.21		
180.00	195.00		Sqm	1	15.00	6.10	6.20	6.15		92.25		
195.00	200.40		Sqm	1	5.40	6.20	6.40	6.30		34.02		
200.40	203.20		Sqm	1	2.80	6.40	4.40	5.40		15.12		
203.20	206.40		Sqm	1	3.20	4.40	1.90	3.15		10.08		
		2nd Main Road 2nd Cross Road (W0616)										
		From North to South										
0.00	15.00		Sqm	1	15.00	4.90	5.15	5.03		75.38		
15.00	30.10		Sqm	1	15.10	5.15	5.25	5.20		78.52		
		2nd Main Road (W0616)										
		From East to West										
0.00	15.00		Sqm	1	15.00	6.40	6.55	6.48		97.13		
15.00	17.30		Sqm	1	2.30	6.55	6.60	6.58		15.12		
17.30	90.80	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
90.80	98.00		Sqm	1	7.20	5.45	6.30	5.88		42.30		
98.00	105.00		Sqm	1	7.00	5.90	5.00	5.45		38.15		
105.00	120.00		Sqm	1	15.00	5.00	6.70	5.85		87.75		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
	130.30		Sqm	1	10.30	6.70	6.70	6.70		69.01		
	135.00		Sqm	1	4.70	5.50	5.40	5.45		25.61		
	150.00		Sqm	1	15.00	5.40	5.30	5.35		80.25		
	165.00		Sqm	1	15.00	5.30	5.35	5.33		79.88		
	180.00		Sqm	1	15.00	5.35	5.10	5.23		78.38		
	183.40		Sqm	1	3.40	5.10	5.00	5.05		17.17		
	195.00		Sqm	1	11.60	5.60	5.40	5.50		63.80		
	210.00		Sqm	1	15.00	5.40	6.40	5.90		88.50		
	211.40		Sqm	1	1.40	6.40	6.40	6.40		8.96		
	225.00		Sqm	1	13.60	5.90	6.00	5.95		80.92		
	240.20		Sqm	1	15.20	6.00	5.90	5.95		90.44		
	241.70		Sqm	1	0.00	0.00	0.00	0.00		0.00		
	247.00		Sqm	1	5.30	10.15	9.60	9.88		52.34		
	255.00		Sqm	1	8.00	5.20	5.15	5.18		41.40		
	270.00		Sqm	1	15.00	5.15	6.00	5.58		83.63		
	278.90		Sqm	1	8.90	6.00	5.90	5.95		52.95		
	285.20		Sqm	1	6.30	5.55	5.50	5.53		34.81		
	287.30		Sqm	1	2.10	5.35	5.35	5.35		11.24		
		20th Cross Road (W0967)										
		From North to South										
0.00	15.00		Sqm	1	15.00	6.80	6.15	6.48		97.13		
15.00	26.20		Sqm	1	11.20	6.15	5.30	5.73		64.12		
26.20	30.00		Sqm	1	3.80	6.35	6.15	6.25		23.75		
30.00	33.50		Sqm	1	3.50	6.15	5.80	5.98		20.91		
		18th A Cross Road (W0618)										
		From West to East										
0.00	9.40		Sqm	1	9.40	5.90	5.50	5.70		53.58		
9.40	15.00		Sqm	1	5.60	5.85	5.70	5.78		32.34		
15.00	30.00		Sqm	1	15.00	5.70	5.70	5.70		85.50		
30.00	45.00		Sqm	1	15.00	5.70	5.25	5.48		82.13		
45.00	60.00		Sqm	1	15.00	5.25	5.40	5.33		79.88		
60.00	72.30		Sqm	1	12.30	5.40	6.00	5.70		70.11		
		2nd Main Road 1st Cross Road (W0977)										
		From North to South										
0.00	12.10		Sqm	1	12.10	7.60	7.30	7.45		90.15		
12.10	23.30		Sqm	1	11.20	6.70	6.35	6.53		73.08		
23.30	34.60		Sqm	1	0.00	0.00	0.00	0.00		0.00		
34.60	45.00		Sqm	1	10.40	6.20	6.25	6.23		64.74		
45.00	47.80		Sqm	1	2.80	5.50	5.00	5.25		14.70		
47.80	58.30		Sqm	1	10.50	5.60	5.20	5.40		56.70		
58.30	60.00		Sqm	1	1.70	6.20	6.20	6.20		10.54		
60.00	71.63		Sqm	1	11.63	6.20	6.40	6.30		73.27		
		1st A Cross Road (W0975)										
		From South to North										
0.00	15.00		Sqm	1	15.00	7.60	7.05	7.33		109.88		
15.00	30.00		Sqm	1	15.00	7.05	7.05	7.05		105.75		
			Sqm	1	2.20	7.05	7.00	7.03		15.46		
		Munikemmpama Layout										
		1st Cross Road (W0973)										
		From South to North										
0.00	15.00		Sqm	1	15.00	5.30	6.00	5.65		84.75		
15.00	30.00		Sqm	1	15.00	6.00	5.70	5.85		87.75		
30.00	45.00		Sqm	1	15.00	5.70	5.85	5.78		86.63		
45.00	60.00		Sqm	1	15.00	5.85	5.45	5.65		84.75		
60.00	73.10		Sqm	1	13.10	5.45	5.95	5.70		74.67		
		Deduction										
			Sqm	-1	0.50	0.50	0.50	0.50		-0.25		
			Sqm	-12	0.45	0.45	0.45	0.45		-2.43		
			Sqm	-1	0.60	0.60	0.60	0.60		-0.36		
			Sqm	-1	1.40	0.70	0.70	0.70		-0.98		
			Sqm	-1	2.20	0.60	0.60	0.60		-1.32		
			Sqm	-2	0.90	0.45	0.45	0.45		-0.81		
			Sqm	-1	1.50	1.35	1.35	1.35		-2.03		
			Sqm	-9	0.64					-5.73		

Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
			Area 3.142*0.9/2/4 0.636							
	Sqm	1	1.77					1.77		
			Area 3.142*1.5/2/4 1.77							
							Total Executed Quantity	6713.23	35.00	234964.00
							Tender Quantity	7151.05		

Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per clause mix formula for base / binding course including heating of aggregates with I.C. loader, hot mixing of stone aggregates and bitumen in hot mix plant, transporting the mixed materials in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by smooth wheeled, vibratory & tandem rollers to achieve the desired density, but excluding cost of primer / tack coat including lead, lift and cost of all materials, labour, hiring of machineries complete as per specifications and directions of the Engineer in charge.

		8. Main 3rd Cross (W20B9)									
		From South to North									
0.00	3.20		Cum	1	3.20	0.20	3.30	3.83	0.03	0.94	
3.20	5.00		Cum	1	11.80	3.30	3.00	3.33	0.03	3.27	
5.00	30.00		Cum	1	13.00	3.00	3.43	3.33	0.03	4.14	
30.00	45.00		Cum	1	13.00	3.43	3.40	3.43	0.03	4.07	
45.00	58.00		Cum	1	13.00	3.40	4.93	3.18	0.03	3.88	
58.00	62.70		Cum	1	2.70	4.93	4.90	4.93	0.03	0.99	
		8a. Main Road 2nd Cross Road (W20B3)									
		From South to North									
0.00	5.00		Cum	1	13.00	0.13	0.00	0.08	0.03	1.50	
5.00	30.00		Cum	1	13.00	0.00	0.20	0.10	0.03	1.58	
30.00	45.00		Cum	1	13.00	0.20	0.33	0.28	0.03	1.71	
45.00	58.00		Cum	1	13.00	0.33	3.43	3.90	0.03	1.43	
58.00	62.30		Cum	1	2.30	3.43	3.40	3.43	0.03	0.02	
		8a. Main Road 1st Cross Road (W20B3)									
		From South to North									
0.00	25.00		Cum	1	13.00	0.40	3.33	3.98	0.03	1.48	
25.00	26.00		Cum	1	1.00	3.33	3.33	3.33	0.03	0.28	
26.00	30.00		Cum	1	14.00	0.00	0.10	0.03	0.03	4.24	
30.00	45.00		Cum	1	13.00	0.10	0.30	0.30	0.03	4.73	
45.00	58.30		Cum	1	13.30	0.30	0.10	0.30	0.03	4.19	
		24th Cross Road (W20B0)									
		From North to South									
0.00	25.00		Cum	1	13.00	7.13	0.83	7.00	0.03	5.23	
25.00	30.00		Cum	1	13.00	0.83	0.20	0.53	0.03	4.89	
30.00	45.00		Cum	1	13.00	0.20	0.80	0.50	0.03	4.88	
45.00	58.00		Cum	1	13.00	0.80	0.83	0.83	0.03	5.12	
58.00	75.00		Cum	1	13.00	0.83	0.80	0.83	0.03	5.12	
75.00	90.00		Cum	1	13.00	0.80	0.80	0.80	0.03	5.10	
90.00	105.00		Cum	1	13.00	0.80	4.75	3.78	0.03	4.33	
105.00	107.70		Cum	1	2.70	4.75	4.80	4.78	0.03	0.04	
107.70	116.40		Cum	1	8.70	3.80	0.00	3.90	0.03	2.57	
116.40	120.00		Cum	1	3.60	3.30	0.80	0.03	0.03	1.09	
120.00	128.70		Cum	1	8.70	0.80	7.33	7.18	0.03	3.12	
		Connecting Road 2									
		From East to West									
0.00	4.30		Cum	1	4.30	7.20	0.93	7.08	0.03	1.32	
4.30	15.00		Cum	1	10.70	9.00	7.80	8.40	0.03	4.49	
15.00	25.30		Cum	1	10.30	7.80	7.83	7.83	0.03	4.03	
		Dead End (W0B3)									
		From North to South									
0.00	15.00		Cum	1	15.00	0.20	0.30	0.33	0.03	4.76	
15.00	24.90		Cum	1	9.90	0.30	0.45	0.48	0.03	3.21	
		1st Main Road (W0B12)									
		From West to East									
0.00	15.00		Cum	1	15.00	3.10	3.40	3.23	0.03	3.94	
15.00	25.30		Cum	1	10.30	3.40	0.00	0.00	0.03	3.09	
25.30	30.00		Cum	1	4.70	0.00	0.30	0.13	0.03	1.52	
30.00	45.00		Cum	1	15.00	0.30	0.10	0.20	0.03	4.03	
45.00	47.80		Cum	1	2.80	0.10	3.90	0.00	0.03	0.84	
47.80	51.10		Cum	1	3.30	3.00	0.20	3.90	0.03	0.97	

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
51.10	60.00		Cum	1	8.90	6.20	5.90	6.05	0.05	2.69		
60.00	75.00		Cum	1	15.00	5.90	5.40	5.65	0.05	4.24		
75.00	90.00		Cum	1	15.00	5.40	5.90	5.65	0.05	4.24		
90.00	94.80		Cum	1	4.80	5.90	5.95	5.93	0.05	1.42		
94.80	105.00		Cum	1	10.20	7.40	7.25	7.33	0.05	3.74		
105.00	120.00		Cum	1	15.00	7.25	7.20	7.23	0.05	5.42		
120.00	122.90		Cum	1	2.90	7.20	7.20	7.20	0.05	1.04		
122.90	125.00		Cum	1	2.10	8.15	9.40	8.78	0.05	0.92		
125.00	135.00		Cum	1	10.00	12.03	12.25	12.14	0.05	6.07		
135.00	141.40		Cum	1	6.40	12.25	12.15	12.20	0.05	3.90		
141.40	145.10		Cum	1	3.70	11.30	11.00	11.15	0.05	2.06		
145.10	150.00		Cum	1	4.90	8.10	8.10	8.10	0.05	1.98		
150.00	164.40		Cum	1	14.40	8.10	8.00	8.05	0.05	5.80		
164.40	180.00		Cum	1	15.60	5.85	6.10	5.98	0.05	4.66		
180.00	195.00		Cum	1	15.00	6.10	6.20	6.15	0.05	4.61		
195.00	200.40		Cum	1	5.40	6.20	6.40	6.30	0.05	1.70		
200.40	203.20		Cum	1	2.80	6.40	4.40	5.40	0.05	0.76		
203.20	206.40		Cum	1	3.20	4.40	1.90	3.15	0.05	0.50		
		2nd Main Road 2nd Cross Road (W0616)										
		From North to South										
0.00	15.00		Cum	1	15.00	4.90	5.15	5.03	0.05	3.77		
15.00	30.10		Cum	1	15.10	5.15	5.25	5.20	0.05	3.93		
		2nd Main Road (W0616)										
		From East to West										
0.00	15.00		Cum	1	15.00	6.40	6.55	6.48	0.05	4.86		
15.00	17.30		Cum	1	2.30	6.55	6.60	6.58	0.05	0.76		
17.30	90.80	No Work	Cum	1	0.00	0.00	0.00	0.00	0.05	0.00		
90.80	98.00		Cum	1	7.20	5.45	6.30	5.88	0.05	2.12		
98.00	105.00		Cum	1	7.00	5.90	5.00	5.45	0.05	1.91		
105.00	120.00		Cum	1	15.00	5.00	6.70	5.85	0.05	4.39		
120.00	130.30		Cum	1	10.30	6.70	6.70	6.70	0.05	3.45		
130.30	135.00		Cum	1	4.70	5.50	5.40	5.45	0.05	1.28		
135.00	150.00		Cum	1	15.00	5.40	5.30	5.35	0.05	4.01		
150.00	165.00		Cum	1	15.00	5.30	5.35	5.33	0.05	3.99		
165.00	180.00		Cum	1	15.00	5.35	5.10	5.23	0.05	3.92		
180.00	183.40		Cum	1	3.40	5.10	5.00	5.05	0.05	0.86		
183.40	195.00		Cum	1	11.60	5.60	5.40	5.50	0.05	3.19		
195.00	210.00		Cum	1	15.00	5.40	6.40	5.90	0.05	4.43		
210.00	211.40		Cum	1	1.40	6.40	6.40	6.40	0.05	0.45		
211.40	225.00		Cum	1	13.60	5.90	6.00	5.95	0.05	4.05		
225.00	240.20		Cum	1	15.20	6.00	5.90	5.95	0.05	4.52		
240.20	241.70		Cum	1	0.00	0.00	0.00	0.00	0.05	0.00		
241.70	247.00		Cum	1	5.30	10.15	9.60	9.88	0.05	2.62		
247.00	255.00		Cum	1	8.00	5.20	5.15	5.18	0.05	2.07		
255.00	270.00		Cum	1	15.00	5.15	6.00	5.58	0.05	4.18		
270.00	278.90		Cum	1	8.90	6.00	5.90	5.95	0.05	2.65		
278.90	285.20		Cum	1	6.30	5.55	5.50	5.53	0.05	1.74		
285.20	287.30		Cum	1	2.10	5.35	5.35	5.35	0.05	0.56		
		20th Cross Road (W0967)										
		From North to South										
0.00	15.00		Cum	1	15.00	6.80	6.15	6.48	0.05	4.86		
15.00	26.20		Cum	1	11.20	6.15	5.30	5.73	0.05	3.21		
26.20	30.00		Cum	1	3.80	6.35	6.15	6.25	0.05	1.19		
30.00	33.50		Cum	1	3.50	6.15	5.80	5.98	0.05	1.05		
		18th A Cross Road (W0618)										
		From West to East										
0.00	9.40		Cum	1	9.40	5.90	5.50	5.70	0.05	2.68		
9.40	15.00		Cum	1	5.60	5.85	5.70	5.78	0.05	1.62		
15.00	30.00		Cum	1	15.00	5.70	5.70	5.70	0.05	4.28		
30.00	45.00		Cum	1	15.00	5.70	5.25	5.48	0.05	4.11		
45.00	60.00		Cum	1	15.00	5.25	5.40	5.33	0.05	3.99		
60.00	72.30		Cum	1	12.30	5.40	6.00	5.70	0.05	3.51		
		2nd Main Road 1st Cross Road (W0977)										

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		From North to South										
0.00	12.10		Cum	1	12.10	7.60	7.30	7.45	0.05	4.51		
12.10	23.30		Cum	1	11.20	6.70	6.35	6.53	0.05	3.65		
23.30	34.60		Cum	1	0.00	0.00	0.00	0.00	0.05	0.00		
34.60	45.00		Cum	1	10.40	6.20	6.25	6.23	0.05	3.24		
45.00	47.80		Cum	1	2.80	5.50	5.00	5.25	0.05	0.73		
47.80	58.30		Cum	1	10.50	5.60	5.20	5.40	0.05	2.84		
58.30	60.00		Cum	1	1.70	6.20	6.20	6.20	0.05	0.53		
60.00	71.63		Cum	1	11.63	6.20	6.40	6.30	0.05	3.66		
		1st A Cross Road (W0975)										
		From South to North										
0.00	15.00		Cum	1	15.00	7.60	7.05	7.33	0.05	5.49		
15.00	30.00		Cum	1	15.00	7.05	7.05	7.05	0.05	5.29		
30.00	32.20		Cum	1	2.20	7.05	7.00	7.03	0.05	0.77		
		Munikempana Layout										
		1st Cross Road (W0973)										
		From South to North										
0.00	15.00		Cum	1	15.00	5.30	6.00	5.65	0.05	4.24		
15.00	30.00		Cum	1	15.00	6.00	5.70	5.85	0.05	4.39		
30.00	45.00		Cum	1	15.00	5.70	5.85	5.78	0.05	4.33		
45.00	60.00		Cum	1	15.00	5.85	5.45	5.65	0.05	4.24		
60.00	73.10		Cum	1	13.10	5.45	5.95	5.70	0.05	3.73		
		Deduction										
			Cum	-1	0.50	0.50	0.50	0.50	0.05	-0.01		
			Cum	-12	0.45	0.45	0.45	0.45	0.05	-0.12		
			Cum	-1	0.60	0.60	0.60	0.60	0.05	-0.02		
			Cum	-1	1.40	0.70	0.70	0.70	0.05	-0.05		
			Cum	-1	2.20	0.60	0.60	0.60	0.05	-0.07		
			Cum	-2	0.90	0.45	0.45	0.45	0.05	-0.04		
			Cum	-1	1.50	1.35	1.35	1.35	0.05	-0.10		
			Cum	-9	0.64				0.05	-0.29		
					Area=3.142*0.9^2/4=0.636							
			Cum	-1	1.77				0.05	-0.09		
					Area=3.142*1.5^2/4=1.77							
										Total Executed Quantity	335.66	8000.00	2685293.00
										Tender Quantity	357.55		
Item no.18		Providing and applying tack coat using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM complete as per specifications and directions of the Engineer in charge.										
		1st Main 3rd Cross (W0989)										
		From South to North										
0.00	3.20		Sqm	1	3.20	6.20	5.50	5.85		18.72		
3.20	15.00		Sqm	1	11.80	5.50	5.60	5.55		65.49		
15.00	30.00		Sqm	1	15.00	5.60	5.45	5.53		82.88		
30.00	45.00		Sqm	1	15.00	5.45	5.40	5.43		81.38		
45.00	60.00		Sqm	1	15.00	5.40	4.95	5.18		77.63		
60.00	62.70		Sqm	1	2.70	4.95	4.90	4.93		13.30		
		1st Main Road 2nd Cross Road (W0983)										
		From South to North										
0.00	15.00		Sqm	1	15.00	6.15	6.00	6.08		91.13		
15.00	30.00		Sqm	1	15.00	6.00	6.20	6.10		91.50		
30.00	45.00		Sqm	1	15.00	6.20	6.35	6.28		94.13		
45.00	60.00		Sqm	1	15.00	6.35	5.45	5.90		88.50		
60.00	62.30		Sqm	1	2.30	5.45	5.40	5.43		12.48		
		1st Main Road 1st Cross Road (W0973)										
		From South to North										
0.00	15.00		Sqm	1	15.00	6.40	5.55	5.98		89.63		
15.00	16.00		Sqm	1	1.00	5.55	5.55	5.55		5.55		
16.00	30.00		Sqm	1	14.00	6.00	6.10	6.05		84.70		
30.00	45.00		Sqm	1	15.00	6.10	6.50	6.30		94.50		
45.00	58.30		Sqm	1	13.30	6.50	6.10	6.30		83.79		
		21th Cross Road (W0969)										

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
		From North to South										
0.00	15.00		Sqm	1	15.00	7.15	6.85	7.00		105.00		
15.00	30.00		Sqm	1	15.00	6.85	6.20	6.53		97.88		
30.00	45.00		Sqm	1	15.00	6.20	6.80	6.50		97.50		
45.00	60.00		Sqm	1	15.00	6.80	6.85	6.83		102.38		
60.00	75.00		Sqm	1	15.00	6.85	6.80	6.83		102.38		
75.00	90.00		Sqm	1	15.00	6.80	6.80	6.80		102.00		
90.00	105.00		Sqm	1	15.00	6.80	4.75	5.78		86.63		
105.00	107.70		Sqm	1	2.70	4.75	4.80	4.78		12.89		
107.70	116.40		Sqm	1	8.70	5.80	6.00	5.90		51.33		
116.40	120.00		Sqm	1	3.60	5.30	6.80	6.05		21.78		
120.00	128.70		Sqm	1	8.70	6.80	7.55	7.18		62.42		
		Connecting Road 2										
		From East to West										
0.00	4.30		Sqm	1	4.30	7.20	6.95	7.08		30.42		
4.30	15.00		Sqm	1	10.70	9.00	7.80	8.40		89.88		
15.00	25.30		Sqm	1	10.30	7.80	7.85	7.83		80.66		
		Dead End (W0965)										
		From North to South										
0.00	15.00		Sqm	1	15.00	6.20	6.50	6.35		95.25		
15.00	24.90		Sqm	1	9.90	6.50	6.45	6.48		64.16		
		1st Main Road (W0612)										
		From West to East										
0.00	15.00		Sqm	1	15.00	5.10	5.40	5.25		78.75		
15.00	25.30		Sqm	1	10.30	5.40	6.60	6.00		61.80		
25.30	30.00		Sqm	1	4.70	6.60	6.30	6.45		30.32		
30.00	45.00		Sqm	1	15.00	6.30	6.10	6.20		93.00		
45.00	47.80		Sqm	1	2.80	6.10	5.90	6.00		16.80		
47.80	51.10		Sqm	1	3.30	5.60	6.20	5.90		19.47		
51.10	60.00		Sqm	1	8.90	6.20	5.90	6.05		53.85		
60.00	75.00		Sqm	1	15.00	5.90	5.40	5.65		84.75		
75.00	90.00		Sqm	1	15.00	5.40	5.90	5.65		84.75		
90.00	94.80		Sqm	1	4.80	5.90	5.95	5.93		28.44		
94.80	105.00		Sqm	1	10.20	7.40	7.25	7.33		74.72		
105.00	120.00		Sqm	1	15.00	7.25	7.20	7.23		108.38		
120.00	122.90		Sqm	1	2.90	7.20	7.20	7.20		20.88		
122.90	125.00		Sqm	1	2.10	8.15	9.40	8.78		18.43		
125.00	135.00		Sqm	1	10.00	12.03	12.25	12.14		121.40		
135.00	141.40		Sqm	1	6.40	12.25	12.15	12.20		78.08		
141.40	145.10		Sqm	1	3.70	11.30	11.00	11.15		41.25		
145.10	150.00		Sqm	1	4.90	8.10	8.10	8.10		39.69		
150.00	164.40		Sqm	1	14.40	8.10	8.00	8.05		115.92		
164.40	180.00		Sqm	1	15.60	5.85	6.10	5.98		93.21		
180.00	195.00		Sqm	1	15.00	6.10	6.20	6.15		92.25		
195.00	200.40		Sqm	1	5.40	6.20	6.40	6.30		34.02		
200.40	203.20		Sqm	1	2.80	6.40	4.40	5.40		15.12		
203.20	206.40		Sqm	1	3.20	4.40	1.90	3.15		10.08		
		2nd Main Road 2nd Cross Road (W0616)										
		From North to South										
0.00	15.00		Sqm	1	15.00	4.90	5.15	5.03		75.38		
15.00	30.10		Sqm	1	15.10	5.15	5.25	5.20		78.52		
		2nd Main Road (W0616)										
		From East to West										
0.00	15.00		Sqm	1	15.00	6.40	6.55	6.48		97.13		
15.00	17.30		Sqm	1	2.30	6.55	6.60	6.58		15.12		
17.30	90.80	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
90.80	98.00		Sqm	1	7.20	5.45	6.30	5.88		42.30		
98.00	105.00		Sqm	1	7.00	5.90	5.00	5.45		38.15		
105.00	120.00		Sqm	1	15.00	5.00	6.70	5.85		87.75		
120.00	130.30		Sqm	1	10.30	6.70	6.70	6.70		69.01		
130.30	135.00		Sqm	1	4.70	5.50	5.40	5.45		25.61		
135.00	150.00		Sqm	1	15.00	5.40	5.30	5.35		80.25		
150.00	165.00		Sqm	1	15.00	5.30	5.35	5.33		79.88		
165.00	180.00		Sqm	1	15.00	5.33	5.10	5.23		78.38		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
180.40	183.40		Sqm	1	3.40	5.10	5.00	5.05		17.17		
185.00	196.80		Sqm	1	11.80	5.60	5.40	5.50		63.80		
210.00	225.00		Sqm	1	15.00	5.10	6.40	5.90		88.50		
211.40	213.00		Sqm	1	1.40	6.40	6.40	6.40		8.96		
225.00	236.60		Sqm	1	11.60	5.90	6.00	5.95		80.92		
235.00	240.20		Sqm	1	15.20	6.00	5.90	5.95		90.44		
240.20	241.20		Sqm	1	0.00	0.00	0.00	0.00		0.00		
241.20	247.00		Sqm	1	5.10	10.15	9.60	9.88		52.34		
247.00	255.00		Sqm	1	8.00	5.20	5.15	5.18		41.40		
255.00	270.00		Sqm	1	15.00	5.15	6.00	5.58		83.63		
270.00	278.90		Sqm	1	8.90	6.00	5.90	5.95		52.95		
278.90	283.20		Sqm	1	6.30	5.55	5.50	5.51		34.81		
283.20	287.30		Sqm	1	2.10	5.35	5.35	5.35		11.24		
		20th Cross Road (W0967) From North to South										
0.00	15.00		Sqm	1	15.00	6.80	6.15	6.48		97.13		
15.00	26.20		Sqm	1	11.20	6.15	5.30	5.73		64.12		
26.20	30.00		Sqm	1	3.80	6.15	6.15	6.25		23.75		
30.00	33.50		Sqm	1	3.50	6.15	5.80	5.98		20.91		
		18th A Cross Road (W0618) From West to East										
0.00	9.40		Sqm	1	9.40	5.90	5.50	5.70		53.58		
9.40	15.00		Sqm	1	5.60	5.85	5.70	5.78		32.34		
15.00	30.00		Sqm	1	15.00	5.70	5.70	5.70		85.50		
30.00	45.00		Sqm	1	15.00	5.70	5.25	5.48		82.13		
45.00	60.00		Sqm	1	15.00	5.25	5.40	5.33		79.88		
60.00	72.30		Sqm	1	12.30	5.40	6.00	5.70		70.11		
		2nd Main Road 1st Cross Road (W0977) From North to South										
0.00	12.10		Sqm	1	12.10	7.60	7.30	7.45		90.15		
12.10	24.30		Sqm	1	11.20	6.70	6.35	6.53		73.08		
24.30	34.60		Sqm	1	0.00	0.00	0.00	0.00		0.00		
34.60	43.00		Sqm	1	10.40	6.20	6.25	6.23		64.74		
43.00	47.80		Sqm	1	2.80	5.50	5.00	5.25		14.70		
47.80	58.30		Sqm	1	10.50	5.60	5.20	5.40		56.70		
58.30	60.00		Sqm	1	1.70	6.20	6.20	6.20		10.54		
60.00	71.63		Sqm	1	11.63	6.20	6.40	6.30		73.27		
		1st A Cross Road (W0975) From South to North										
0.00	15.00		Sqm	1	15.00	7.60	7.05	7.33		109.88		
15.00	30.00		Sqm	1	15.00	7.05	7.05	7.05		105.75		
30.00	42.20		Sqm	1	2.20	7.05	7.00	7.03		15.46		
		Mankemmpana Layout 1st Cross Road (W0973) From South to North										
0.00	15.00		Sqm	1	15.00	5.30	6.00	5.65		84.75		
15.00	30.00		Sqm	1	15.00	6.00	5.70	5.85		87.75		
30.00	45.00		Sqm	1	15.00	5.70	5.85	5.78		86.63		
45.00	60.00		Sqm	1	15.00	5.85	5.45	5.65		84.75		
60.00	73.10		Sqm	1	13.10	5.45	5.95	5.70		74.67		
		Deduction										
			Sqm	-1	0.50	0.50	0.50	0.50		-0.25		
			Sqm	-12	0.45	0.45	0.45	0.45		-2.43		
			Sqm	-1	0.60	0.60	0.60	0.60		-0.36		
			Sqm	-1	1.40	0.70	0.70	0.70		-0.98		
			Sqm	-1	2.20	0.60	0.60	0.60		-1.32		
			Sqm	-2	0.90	0.45	0.45	0.45		-0.81		
			Sqm	-1	1.50	1.35	1.35	1.35		-2.03		
			Sqm	-9	0.64					-5.73		
			Sqm		Area=3.142*0.9^2/4=0.636							
			Sqm	-1	1.77					-1.77		
			Sqm		Area=3.142*1.5^2/4=1.77							
									Total Executed Quantity	6713.23	15.00	100699.00

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
									Tender Quantity	7151.05		
Item no.19		Providing and laying bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications and directions of the Engineer in charge.										
		1st Main 3rd Cross (W0989)										
		From South to North										
0.00	3.20		Cum	1	3.20	6.20	5.50	5.85	0.04	0.75		
3.20	15.00		Cum	1	11.80	5.50	5.60	5.55	0.04	2.62		
15.00	30.00		Cum	1	15.00	5.60	5.45	5.53	0.04	3.32		
30.00	45.00		Cum	1	15.00	5.45	5.40	5.43	0.04	3.26		
45.00	60.00		Cum	1	15.00	5.40	4.95	5.18	0.04	3.11		
60.00	62.70		Cum	1	2.70	4.95	4.90	4.93	0.04	0.53		
		1st Main Road 2nd Cross Road (W0983)										
		From South to North										
0.00	15.00		Cum	1	15.00	6.15	6.00	6.08	0.04	3.65		
15.00	30.00		Cum	1	15.00	6.00	6.20	6.10	0.04	3.66		
30.00	45.00		Cum	1	15.00	6.20	6.35	6.28	0.04	3.77		
45.00	60.00		Cum	1	15.00	6.35	5.45	5.90	0.04	3.54		
60.00	62.30		Cum	1	2.30	5.45	5.40	5.43	0.04	0.50		
		1st Main Road 1st Cross Road (W0973)										
		From South to North										
0.00	15.00		Cum	1	15.00	6.40	5.55	5.98	0.04	3.59		
15.00	16.00		Cum	1	1.00	5.55	5.55	5.55	0.04	0.22		
16.00	30.00		Cum	1	14.00	6.00	6.10	6.05	0.04	3.39		
30.00	45.00		Cum	1	15.00	6.10	6.50	6.30	0.04	3.78		
45.00	58.30		Cum	1	13.30	6.50	6.10	6.30	0.04	3.35		
		21th Cross Road (W0969)										
		From North to South										
0.00	15.00		Cum	1	15.00	7.15	6.85	7.00	0.04	4.20		
15.00	30.00		Cum	1	15.00	6.85	6.20	6.53	0.04	3.92		
30.00	45.00		Cum	1	15.00	6.20	6.80	6.50	0.04	3.90		
45.00	60.00		Cum	1	15.00	6.80	6.85	6.83	0.04	4.10		
60.00	75.00		Cum	1	15.00	6.85	6.80	6.83	0.04	4.10		
75.00	90.00		Cum	1	15.00	6.80	6.80	6.80	0.04	4.08		
90.00	105.00		Cum	1	15.00	6.80	4.75	5.78	0.04	3.47		
105.00	107.70		Cum	1	2.70	4.75	4.80	4.78	0.04	0.52		
107.70	116.40		Cum	1	8.70	5.80	6.00	5.90	0.04	2.05		
116.40	120.00		Cum	1	3.60	5.30	6.80	6.05	0.04	0.87		
120.00	128.70		Cum	1	8.70	6.80	7.55	7.18	0.04	2.50		
		Connecting Road 2										
		From East to West										
0.00	4.30		Cum	1	4.30	7.20	6.95	7.08	0.04	1.22		
4.30	15.00		Cum	1	10.70	9.00	7.80	8.40	0.04	3.60		
15.00	25.30		Cum	1	10.30	7.80	7.85	7.83	0.04	3.22		
		Dead End (W0965)										
		From North to South										
0.00	15.00		Cum	1	15.00	6.20	6.50	6.35	0.04	3.81		
15.00	24.90		Cum	1	9.90	6.50	6.45	6.48	0.04	2.56		
		1st Main Road (W0612)										
		From West to East										
0.00	15.00		Cum	1	15.00	5.10	5.40	5.25	0.04	3.15		
15.00	25.30		Cum	1	10.30	5.40	6.60	6.00	0.04	2.47		
25.30	30.00		Cum	1	4.70	6.60	6.30	6.45	0.04	1.21		
30.00	45.00		Cum	1	15.00	6.30	6.10	6.20	0.04	3.72		
45.00	47.80		Cum	1	2.80	6.10	5.90	6.00	0.04	0.67		
47.80	51.10		Cum	1	3.30	5.60	6.20	5.90	0.04	0.78		
51.10	60.00		Cum	1	8.90	6.20	5.90	6.05	0.04	2.15		
60.00	75.00		Cum	1	15.00	5.90	5.40	5.65	0.04	3.39		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
[illegible]	[illegible]		Cum	1	15.00	5.40	5.90	5.65	0.04	3.39		
[illegible]	[illegible]		Cum	1	4.80	5.90	5.95	5.93	0.04	1.14		
[illegible]	[illegible]		Cum	1	10.20	7.40	7.25	7.33	0.04	2.99		
[illegible]	[illegible]		Cum	1	15.00	7.25	7.20	7.23	0.04	4.34		
[illegible]	[illegible]		Cum	1	2.90	7.20	7.20	7.20	0.04	0.84		
[illegible]	[illegible]		Cum	1	2.10	8.15	9.40	8.78	0.04	0.74		
[illegible]	[illegible]		Cum	1	10.00	12.13	12.25	12.14	0.04	4.86		
[illegible]	[illegible]		Cum	1	6.40	12.25	12.15	12.20	0.04	3.12		
[illegible]	[illegible]		Cum	1	3.70	11.30	11.00	11.15	0.04	1.65		
[illegible]	[illegible]		Cum	1	4.90	8.10	8.10	8.10	0.04	1.59		
[illegible]	[illegible]		Cum	1	14.40	8.10	8.00	8.05	0.04	4.64		
[illegible]	[illegible]		Cum	1	15.60	5.85	6.10	5.98	0.04	3.73		
[illegible]	[illegible]		Cum	1	15.00	6.10	6.20	6.15	0.04	3.69		
[illegible]	[illegible]		Cum	1	5.40	6.20	6.40	6.30	0.04	1.36		
[illegible]	[illegible]		Cum	1	2.80	6.40	4.40	5.40	0.04	0.60		
[illegible]	[illegible]		Cum	1	3.20	4.40	1.90	3.15	0.04	0.40		
		2nd Main Road 2nd Cross Road (W.K.16)										
		From North to South										
0.00	15.00		Cum	1	15.00	4.90	5.15	5.03	0.04	3.02		
15.00	30.10		Cum	1	15.10	5.15	5.25	5.20	0.04	3.14		
		2nd Main Road (W.K.16)										
		From East to West										
0.00	15.00		Cum	1	15.00	6.40	6.55	6.48	0.04	3.89		
15.00	17.30		Cum	1	2.30	6.55	6.60	6.58	0.04	0.60		
17.30	[illegible]	No Work	Cum	1	0.00	0.00	0.00	0.00	0.04	0.00		
[illegible]	[illegible]		Cum	1	7.20	5.45	6.30	5.88	0.04	1.69		
[illegible]	[illegible]		Cum	1	7.00	5.90	5.00	5.45	0.04	1.53		
[illegible]	[illegible]		Cum	1	15.00	5.00	6.70	5.85	0.04	3.51		
[illegible]	[illegible]		Cum	1	10.30	6.70	6.70	6.70	0.04	2.76		
[illegible]	[illegible]		Cum	1	4.70	5.50	5.40	5.45	0.04	1.02		
[illegible]	[illegible]		Cum	1	15.00	5.40	5.30	5.35	0.04	3.21		
[illegible]	[illegible]		Cum	1	15.00	5.30	5.35	5.33	0.04	3.20		
[illegible]	[illegible]		Cum	1	15.00	5.35	5.10	5.23	0.04	3.14		
[illegible]	[illegible]		Cum	1	3.40	5.10	5.00	5.05	0.04	0.69		
[illegible]	[illegible]		Cum	1	11.60	5.60	5.40	5.50	0.04	2.55		
[illegible]	[illegible]		Cum	1	15.00	5.40	6.40	5.90	0.04	3.54		
[illegible]	[illegible]		Cum	1	1.40	6.40	6.40	6.40	0.04	0.36		
[illegible]	[illegible]		Cum	1	13.60	5.90	6.00	5.95	0.04	3.24		
[illegible]	[illegible]		Cum	1	15.20	6.00	5.90	5.95	0.04	3.62		
[illegible]	[illegible]		Cum	1	0.00	0.00	0.00	0.00	0.04	0.00		
[illegible]	[illegible]		Cum	1	5.30	10.15	9.60	9.88	0.04	2.09		
[illegible]	[illegible]		Cum	1	8.00	5.20	5.15	5.18	0.04	1.66		
[illegible]	[illegible]		Cum	1	15.00	5.15	6.00	5.58	0.04	3.35		
[illegible]	[illegible]		Cum	1	8.90	6.00	5.90	5.95	0.04	2.12		
[illegible]	[illegible]		Cum	1	6.30	5.55	5.50	5.53	0.04	1.39		
[illegible]	[illegible]		Cum	1	2.10	5.35	5.35	5.35	0.04	0.45		
		10th Cross Road (W.K.07)										
		From North to South										
0.00	15.00		Cum	1	15.00	6.80	6.15	6.48	0.04	3.89		
15.00	26.20		Cum	1	11.20	6.15	5.30	5.73	0.04	2.56		
26.20	30.00		Cum	1	3.80	6.35	6.15	6.25	0.04	0.95		
30.00	33.50		Cum	1	3.50	6.15	5.80	5.98	0.04	0.84		
		10th A Cross Road (W.K.12)										
		From West to East										
0.00	9.40		Cum	1	9.40	5.90	5.50	5.70	0.04	2.14		
9.40	15.00		Cum	1	5.60	5.85	5.70	5.78	0.04	1.29		
15.00	30.00		Cum	1	15.00	5.70	5.70	5.70	0.04	3.42		
30.00	45.00		Cum	1	15.00	5.70	5.25	5.48	0.04	3.29		
45.00	60.00		Cum	1	15.00	5.25	5.40	5.33	0.04	3.20		
60.00	72.30		Cum	1	12.30	5.40	6.00	5.70	0.04	2.80		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		2nd Main Road 1st Cross Road (W0977)										
		From North to South										
0.00	12.10		Cum	1	12.10	7.60	7.30	7.45	0.04	3.61		
12.10	23.30		Cum	1	11.20	6.70	6.35	6.53	0.04	2.92		
23.30	34.60		Cum	1	0.00	0.00	0.00	0.00	0.04	0.00		
34.60	45.00		Cum	1	10.40	6.20	6.25	6.23	0.04	2.59		
45.00	47.80		Cum	1	2.80	5.50	5.00	5.25	0.04	0.59		
47.80	58.30		Cum	1	10.50	5.60	5.20	5.40	0.04	2.27		
58.30	60.00		Cum	1	1.70	6.20	6.20	6.20	0.04	0.42		
60.00	71.63		Cum	1	11.63	6.20	6.40	6.30	0.04	2.93		
		1st A Cross Road (W0975)										
		From South to North										
0.00	15.00		Cum	1	15.00	7.60	7.05	7.33	0.04	4.40		
15.00	30.00		Cum	1	15.00	7.05	7.05	7.05	0.04	4.23		
30.00	32.20		Cum	1	2.20	7.05	7.00	7.03	0.04	0.62		
		Munikemmpama Layout										
		1st Cross Road (W0973)										
		From South to North										
0.00	15.00		Cum	1	15.00	5.30	6.00	5.65	0.04	3.39		
15.00	30.00		Cum	1	15.00	6.00	5.70	5.85	0.04	3.51		
30.00	45.00		Cum	1	15.00	5.70	5.85	5.78	0.04	3.47		
45.00	60.00		Cum	1	15.00	5.85	5.45	5.65	0.04	3.39		
60.00	73.10		Cum	1	13.10	5.45	5.95	5.70	0.04	2.99		
		Deduction										
			Cum	-1	0.50	0.50	0.50	0.50	0.04	-0.01		
			Cum	-12	0.45	0.45	0.45	0.45	0.04	-0.10		
			Cum	-1	0.60	0.60	0.60	0.60	0.04	-0.01		
			Cum	-1	1.40	0.70	0.70	0.70	0.04	-0.04		
			Cum	-1	2.20	0.60	0.60	0.60	0.04	-0.05		
			Cum	-2	0.90	0.45	0.45	0.45	0.04	-0.03		
			Cum	-1	1.50	1.35	1.35	1.35	0.04	-0.08		
			Cum	-9	0.64				0.04	-0.23		
					Area=3.142*0.9^2/4=0.636							
			Cum	-1	1.77				0.04	-0.07		
					Area=3.142*1.5^2/4=1.77							
										Total Executed Quantity	268.53	10000.00	2685293.00
										Tender Quantity	286.04		
Item no.20		Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface/ Concrete Surface: Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 standards specified. The finished surface to be level, uniform and free from streaks and holes complete as per specifications and directions of the Engineer in charge.										
		1st Main 3rd Cross (W0989)										
		From South to North										
0.00	3.20		Sqm	2	3.20	0.10	0.10	0.10		0.64		
3.20	15.00		Sqm	2	11.80	0.10	0.10	0.10		2.36		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	62.70		Sqm	2	2.70	0.10	0.10	0.10		0.54		
		1st Main Road 2nd Cross Road (W0983)										
		From South to North										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	62.30		Sqm	2	2.30	0.10	0.10	0.10		0.46		
		1st Main Road 1st Cross Road (W0973)										
		From South to North										
0.00	15.00											
15.00	16.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	1.00	0.10	0.10	0.10		0.20		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
16.00	30.00		Sqm	2	14.00	0.10	0.10	0.10		2.80		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	58.30		Sqm	2	13.30	0.10	0.10	0.10		2.66		
		21th Cross Road (W0969)										
		From North to South										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	107.70		Sqm	2	2.70	0.10	0.10	0.10		0.54		
107.70	116.40		Sqm	2	8.70	0.10	0.10	0.10		1.74		
116.40	120.00		Sqm	2	3.60	0.10	0.10	0.10		0.72		
120.00	128.70		Sqm	2	8.70	0.10	0.10	0.10		1.74		
		Connecting Road 2										
		From East to West										
0.00	4.30		Sqm	2	4.30	0.10	0.10	0.10		0.86		
4.30	15.00		Sqm	2	10.70	0.10	0.10	0.10		2.14		
15.00	25.30		Sqm	2	10.30	0.10	0.10	0.10		2.06		
		Dead End (W0965)										
		From North to South										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	24.90		Sqm	2	9.90	0.10	0.10	0.10		1.98		
		1st Main Road (W0612)										
		From West to East										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	25.30		Sqm	2	10.30	0.10	0.10	0.10		2.06		
25.30	30.00		Sqm	2	4.70	0.10	0.10	0.10		0.94		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	47.80		Sqm	2	2.80	0.10	0.10	0.10		0.56		
47.80	51.10		Sqm	2	3.30	0.10	0.10	0.10		0.66		
51.10	60.00		Sqm	2	8.90	0.10	0.10	0.10		1.78		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	94.80		Sqm	2	4.80	0.10	0.10	0.10		0.96		
94.80	105.00		Sqm	2	10.20	0.10	0.10	0.10		2.04		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	122.90		Sqm	2	2.90	0.10	0.10	0.10		0.58		
122.90	125.00		Sqm	2	2.10	0.10	0.10	0.10		0.42		
125.00	135.00		Sqm	2	10.00	0.10	0.10	0.10		2.00		
135.00	141.40		Sqm	2	6.40	0.10	0.10	0.10		1.28		
141.40	145.10		Sqm	2	3.70	0.10	0.10	0.10		0.74		
145.10	150.00		Sqm	2	4.90	0.10	0.10	0.10		0.98		
150.00	164.40		Sqm	2	14.40	0.10	0.10	0.10		2.88		
164.40	180.00		Sqm	2	15.60	0.10	0.10	0.10		3.12		
180.00	195.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
195.00	200.40		Sqm	2	5.40	0.10	0.10	0.10		1.08		
200.40	203.20		Sqm	2	2.80	0.10	0.10	0.10		0.56		
203.20	206.40		Sqm	2	3.20	0.10	0.10	0.10		0.64		
		2nd Main Road 2nd Cross Road (W0616)										
		From North to South										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.10		Sqm	2	15.10	0.10	0.10	0.10		3.02		
		2nd Main Road (W0616)										
		From East to West										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	17.30		Sqm	2	2.30	0.10	0.10	0.10		0.46		
17.30	90.80	No Work	Sqm	2	0.00	0.10	0.10	0.10		0.00		
90.80	98.00		Sqm	2	7.20	0.10	0.10	0.10		1.44		
98.00	105.00		Sqm	2	7.00	0.10	0.10	0.10		1.40		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	130.30		Sqm	2	10.30	0.10	0.10	0.10		2.06		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
130.30	135.00		Sqm	2	4.70	0.10	0.10	0.10		0.94		
135.00	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
150.00	165.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
165.00	180.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
180.00	183.40		Sqm	2	3.40	0.10	0.10	0.10		0.68		
183.40	195.00		Sqm	2	11.60	0.10	0.10	0.10		2.32		
195.00	210.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
210.00	211.40		Sqm	2	1.40	0.10	0.10	0.10		0.28		
211.40	225.00		Sqm	2	13.60	0.10	0.10	0.10		2.72		
225.00	240.20		Sqm	2	15.20	0.10	0.10	0.10		3.04		
240.20	241.70		Sqm	2	0.00	0.10	0.10	0.10		0.00		
241.70	247.00		Sqm	2	5.30	0.10	0.10	0.10		1.06		
247.00	255.00		Sqm	2	8.00	0.10	0.10	0.10		1.60		
255.00	270.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
270.00	278.90		Sqm	2	8.90	0.10	0.10	0.10		1.78		
278.90	285.20		Sqm	2	6.30	0.10	0.10	0.10		1.26		
285.20	287.30		Sqm	2	2.10	0.10	0.10	0.10		0.42		
		20th Cross Road (W0967)										
		From North to South										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	26.20		Sqm	2	11.20	0.10	0.10	0.10		2.24		
26.20	30.00		Sqm	2	3.80	0.10	0.10	0.10		0.76		
30.00	33.50		Sqm	2	3.50	0.10	0.10	0.10		0.70		
		18th A Cross Road (W0618)										
		From West to East										
0.00	9.40		Sqm	0.5	9.40	0.10	0.10	0.10		0.47		
9.40	15.00		Sqm	0.5	5.60	0.10	0.10	0.10		0.28		
15.00	30.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
30.00	45.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
45.00	60.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
60.00	72.30		Sqm	0.5	12.30	0.10	0.10	0.10		0.62		
		2nd Main Road 1st Cross Road (W0977)										
		From North to South										
0.00	12.10		Sqm	2	12.10	0.10	0.10	0.10		2.42		
12.10	23.30		Sqm	2	11.20	0.10	0.10	0.10		2.24		
23.30	34.60		Sqm	2	0.00	0.10	0.10	0.10		0.00		
34.60	45.00		Sqm	2	10.40	0.10	0.10	0.10		2.08		
45.00	47.80		Sqm	2	2.80	0.10	0.10	0.10		0.56		
47.80	58.30		Sqm	2	10.50	0.10	0.10	0.10		2.10		
58.30	60.00		Sqm	2	1.70	0.10	0.10	0.10		0.34		
60.00	71.63		Sqm	2	11.63	0.10	0.10	0.10		2.33		
		1st A Cross Road (W0975)										
		From South to North										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	32.20		Sqm	2	2.20	0.10	0.10	0.10		0.44		
		Munikemmpama Layout										
		1st Cross Road (W0973)										
		From South to North										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	73.10		Sqm	2	13.10	0.10	0.10	0.10		2.62		
									Total Executed Quantity	**205.64**	**460.00**	**94595.00**
									Tender Quantity	**221.80**		
Item no.21		Providing and Constructing dry lean cement concrete mix CC1:5:10 Base with OPC 25mm and down size graded granite metal coarse aggregate at 0.86cum and fine aggregates @ 0.58cum over a prepared sub-base coarse and fine aggregate conforming to IS: 383-2016. aggregate cement ratio not to exceed 15:1. Aggregate gradation after blending to be as per Table 600-1, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 8-10 tonnes vibratory roller, finishing and curing complete as per specifications and directions of the Engineer in charge.											
		Kaveri Layout										
		Krishna Nivas House (W1309)										

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		South to North										
0.00	15.00		Cum	1	15.00	5.30	4.95	5.13	0.15	11.53		
15.00	30.00			1	15.00	4.95	5.20	5.08	0.15	11.42		
30.00	45.00			1	15.00	5.20	5.15	5.18	0.15	11.64		
45.00	60.00			1	15.00	5.15	5.15	5.15	0.15	11.59		
60.00	75.00			1	15.00	5.15	5.20	5.18	0.15	11.64		
75.00	90.00			1	15.00	5.20	3.90	4.55	0.15	10.24		
90.00	91.10			1	1.10	3.90	3.90	3.90	0.15	0.64		
		Joseph House Road (W0884)										
		West to East										
0.00	15.00			1	15.00	4.90	5.15	5.03	0.15	11.31		
15.00	30.00			1	15.00	5.15	4.90	5.03	0.15	11.31		
30.00	45.00			1	15.00	4.90	5.80	5.35	0.15	12.04		
45.00	46.20			1	1.20	5.80	5.85	5.83	0.15	1.05		
		Moto Works Oppo. (W1299)										
		South to North										
0.00	15.00			1	15.00	5.90	5.35	5.63	0.15	12.66		
15.00	30.00			1	15.00	5.35	5.00	5.18	0.15	11.64		
30.00	45.00			1	15.00	5.00	5.20	5.10	0.15	11.48		
45.00	60.00			1	15.00	5.20	5.25	5.23	0.15	11.76		
60.00	75.00			1	15.00	5.25	5.05	5.15	0.15	11.59		
75.00	90.00			1	15.00	5.05	5.45	5.25	0.15	11.81		
90.00	105.00			1	15.00	5.45	5.45	5.45	0.15	12.26		
105.00	120.00			1	15.00	5.45	4.40	4.93	0.15	11.08		
120.00	128.10			1	8.10	4.40	3.95	4.18	0.15	5.07		
		Cross Road 1 (W0870)										
		West to East										
0.00	15.00			1	15.00	4.10	4.65	4.38	0.15	9.84		
15.00	25.60			1	10.60	4.65	4.10	4.38	0.15	6.96		
		Cross Road 2 (W0862)										
		West to East										
0.00	15.00			1	15.00	5.30	5.25	5.28	0.15	11.87		
15.00	30.00			1	15.00	5.25	4.85	5.05	0.15	11.36		
30.00	32.30			1	2.30	4.85	3.50	4.18	0.15	1.44		
		Cross Road (W1297)										
		South to North										
0.00	15.00			1	15.00	5.40	5.10	5.25	0.15	11.81		
15.00	30.00			1	15.00	5.10	4.70	4.90	0.15	11.03		
30.00	45.00			1	15.00	4.70	4.60	4.65	0.15	10.46		
45.00	60.00			1	15.00	4.60	4.50	4.55	0.15	10.24		
60.00	75.00			1	15.00	4.50	4.30	4.40	0.15	9.90		
75.00	90.00			1	15.00	4.30	4.00	4.15	0.15	9.34		
90.00	105.00			1	15.00	4.00	4.00	4.00	0.15	9.00		
		Vishwarathna #951 House Beside Road										
		(East To West)										
0.00	15.00		Cum	1	15.00	5.20	5.70	5.45	0.15	12.26		
15.00	30.00		Cum	1	15.00	5.70	6.00	5.85	0.15	13.16		
30.00	37.80		Cum	1	7.80	6.00	6.30	6.15	0.15	7.20		
		Sri Laxmi Narayana opp Road										
		(South To North)										
0.00	15.00		Cum	1	15.00	2.70	2.20	2.45	0.15	5.51		
15.00	16.90		Cum	1	1.90	2.20	2.15	2.18	0.15	0.62		
16.90	30.00		Cum	1	13.10	2.45	2.90	2.68	0.15	5.26		
30.00	45.00		Cum	1	15.00	2.90	2.85	2.88	0.15	6.47		
45.00	60.00		Cum	1	15.00	2.85	2.85	2.85	0.15	6.41		
60.00	61.50		Cum	1	1.50	2.85	2.80	2.83	0.15	0.64		
		7 star Multi Cusine Beside Road										
		(South To North)										
0.00	15.00		Cum	1	15.00	3.55	3.25	3.40	0.15	7.65		
15.00	30.00		Cum	1	15.00	3.25	3.10	3.18	0.15	7.14		
30.00	34.70		Cum	1	4.70	3.10	2.80	2.95	0.15	2.08		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Cross Road										
0.00	15.00		Cum	1	15.00	4.00	4.00	4.00	0.15	9.00		
15.00	30.00		Cum	1	15.00	4.00	4.00	4.00	0.15	9.00		
30.00	45.00		Cum	1	15.00	4.00	4.00	4.00	0.15	9.00		
45.00	58.00		Cum	1	13.00	4.00	4.00	4.00	0.15	7.80		
		DEDUCTION										
		Chambers	Cum	-19	0.45	0.45	0.45	0.45	0.15	-0.70		
		Manhole 0.75dia	Cum	-3	0.44				0.15	-0.20		
					(3.14*0.75*0.75)/4 0.44							
									Total Executed Quantity	425.70		
									Tender Quantity	270.56		
									Quantity upto 125%	338.20	5000.00	1691000.00
									Quantity Above 125%	87.50	4399.88	384989.50
Item no 22		Cement concrete pavement Construction of un reinforced plain cement concrete pavement, using a grade concrete M30 over a prepared base with OPC coarse aggregate @ 0.67cum fine aggregate @ 0.40cum coarse and fine aggregate conforming to IS 383-2016 with superplasticiser @ conforming to IS9103-1999mixed in a concrete mixer of not less than 0.4 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane, sealant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades, textured with texturing machine and curing including cost of all materials,labour,hire charges of machines,all lead and lift charges etc., complete as per specifications and as per the directions of the Engineer in charge of the work										
		Kaveri Layout										
		Krishna Kiran House (7/1399) South to North										
0.00	15.00		Cum	1	15.00	5.30	4.95	5.13	0.15	11.53		
15.00	30.00			1	15.00	4.95	5.20	5.08	0.15	11.42		
30.00	45.00			1	15.00	5.20	5.15	5.18	0.15	11.64		
45.00	60.00			1	15.00	5.15	5.15	5.15	0.15	11.59		
60.00	75.00			1	15.00	5.15	5.20	5.18	0.15	11.64		
75.00	90.00			1	15.00	5.20	3.90	4.55	0.15	10.24		
90.00	91.10			1	1.10	3.90	3.90	3.90	0.15	0.64		
		Joseph House Road (7/8884) West to East										
0.00	15.00			1	15.00	4.90	5.15	5.03	0.15	11.31		
15.00	30.00			1	15.00	5.15	4.90	5.03	0.15	11.31		
30.00	45.00			1	15.00	4.90	5.80	5.35	0.15	12.04		
45.00	46.20			1	1.20	5.80	5.85	5.83	0.15	1.05		
		Gas Works Opp. (7/1255) South to North										
0.00	15.00			1	15.00	5.90	5.35	5.63	0.15	12.66		
15.00	30.00			1	15.00	5.35	5.00	5.18	0.15	11.64		
30.00	45.00			1	15.00	5.00	5.20	5.10	0.15	11.48		
45.00	60.00			1	15.00	5.20	5.25	5.23	0.15	11.76		
60.00	75.00			1	15.00	5.25	5.05	5.15	0.15	11.59		
75.00	90.00			1	15.00	5.05	5.45	5.25	0.15	11.81		
90.00	105.00			1	15.00	5.45	5.45	5.45	0.15	12.26		
105.00	120.00			1	15.00	5.45	4.40	4.93	0.15	11.08		
120.00	128.10			1	8.10	4.40	3.95	4.18	0.15	5.07		
		Cross Road 1 (7/8876) West to East										
0.00	15.00			1	15.00	4.10	4.65	4.38	0.15	9.85		
15.00	25.60			1	10.60	4.65	4.10	4.38	0.15	6.96		
		Cross Road 2 (7/8862)										
		West to East										
0.00	15.00			1	15.00	5.30	5.25	5.28	0.15	11.87		
15.00	30.00			1	15.00	5.25	4.85	5.05	0.15	11.36		
30.00	32.30			1	2.30	4.85	3.50	4.18	0.15	1.44		
		Cross Road (7/1297) South to North										
0.00	15.00			1	15.00	5.40	5.10	5.25	0.15	11.81		
15.00	30.00			1	15.00	5.10	4.70	4.90	0.15	11.03		

BBMP (Ward No 06)

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
30.00	45.00			1	15.00	4.70	4.60	4.65	0.15	10.46		
45.00	60.00			1	15.00	4.60	4.50	4.55	0.15	10.24		
60.00	75.00			1	15.00	4.50	4.30	4.40	0.15	9.90		
75.00	90.00			1	15.00	4.30	4.00	4.15	0.15	9.34		
90.00	105.00			1	15.00	4.00	4.00	4.00	0.15	9.00		
		Vishwarathna #951 House Beside Road										
		(East To West)										
0	15		Cum	1	15.00	5.20	5.70	5.45	0.15	12.26		
15	30		Cum	1	15.00	5.70	6.00	5.85	0.15	13.16		
30	37.8		Cum	1	7.80	6.00	6.30	6.15	0.15	7.20		
		Sri Laxmi Narayana opp Road										
		(South To North)										
0	15		Cum	1	15.00	2.70	2.20	2.45	0.15	5.51		
15	16.9		Cum	1	1.90	2.20	2.15	2.18	0.15	0.62		
16.9	30		Cum	1	13.10	2.45	2.90	2.68	0.15	5.26		
30	45		Cum	1	15.00	2.90	2.85	2.88	0.15	6.47		
45	60		Cum	1	15.00	2.85	2.85	2.85	0.15	6.41		
60	61.5		Cum	1	1.50	2.85	2.80	2.83	0.15	0.64		
		7 star Multi Cusine Beside Road										
		(South To North)										
0	15		Cum	1	15.00	3.55	3.25	3.40	0.15	7.65		
15	30		Cum	1	15.00	3.25	3.10	3.18	0.15	7.14		
30	34.7		Cum	1	4.70	3.10	2.80	2.95	0.15	2.08		
		Cross Road										
0	15		Cum	1	15.00	4.00	4.00	4.00	0.15	9.00		
15	30		Cum	1	15.00	4.00	4.00	4.00	0.15	9.00		
30	45		Cum	1	15.00	4.00	4.00	4.00	0.15	9.00		
45	58		Cum	1	13.00	4.00	4.00	4.00	0.15	7.80		
		DEDUCTION										
		Chambers	Cum	-10	0.45	0.45	0.45	0.45	0.15	-0.30		
		Manhole 0.75dia	Cum	-3	0.44				0.15	-0.20		
						(3.14*0.75*0.75)/4-0.44						
									Total	425.70		
									Tender Quantity	270.56		
									Quantity upto 125%	338.20	6800.00	2299760.00
									Quantity Above 125%	87.50	6266.43	548287.00
											Sub Total	45041564.00
											For 12% Applicable GST	5404988.00
											6% GST Extra Paid in 2nd RA	708979.00
											Total Amount	51155531.00

Assistant Engineer
BBMP
ಸಹಾಯಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ ಬ್ಯಾಟರಾಯನಪುರ ಉಪ ವಿಭಾಗ

Assistant Executive Engineer
BBMP
ಸಹಾಯಕ ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ಉಪ ವಿಭಾಗ
ಬಿ.ಬಿ.ಎಂ.ಪಿ ಬೆಂಗಳೂರು-24

Executive Engineer
BBMP
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು.
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ.
ಬೃ.ಬೆ.ಮ.ಪಾ. ಬೆಂಗಳೂರು.

Technical Sanction
Accorded For Rs 51155531.00
Head of A/C P 3873
CER NO : 94 Dt: 15-03-23